

IN THE UNITED STATES DISTRICT COURT  
FOR THE EASTERN DISTRICT OF  
TENNESSEE  
(Southern Division)

THE UNITED STATES OF AMERICA )  
and THE STATE OF TENNESSEE, ex.rel. )  
JONATHAN SKRMETTI, in his )  
official capacity as the Attorney General )  
and Reporter of Tennessee, )

Plaintiffs, )

v. )

THE CITY OF CHATTANOOGA, )

Defendant. )

Case: No. 1:12-cv-00245 Collier/Lee

Consolidated with Case No. 1:10-CV-281  
Collier/Lee

TENNESSEE CLEAN WATER )  
NETWORK,<sup>1</sup> )

Plaintiff, )

v. )

CITY OF CHATTANOOGA, )

Defendant. )

FIRST MATERIAL CONSENT DECREE MODIFICATION

WHEREAS, Plaintiff, the United States of America (“United States”), by the authority of the Attorney General of the United States and through its undersigned counsel, acting at the request and on behalf of the United States Environmental Protection Agency (“EPA”), filed a

---

<sup>1</sup> A representative of the Tennessee Clean Water Network has advised EPA that TCWN is no longer an active organization and is in the process of dissolving. Accordingly, they have not joined in this Modification.

Complaint (the “Complaint”) alleging that Defendant, the City of Chattanooga, Tennessee (“Chattanooga”), has violated and will continue to violate Section 301 of the Clean Water Act, 33 U.S.C. § 1311 (“CWA”), and terms and conditions of its National Pollutant Discharge Elimination System (“NPDES”) permit issued under Section 402 of the CWA, 33 U.S.C. § 1342; and

WHEREAS, Plaintiff, the State of Tennessee (“State”), acting at the request of the Tennessee Department of Environment and Conservation (“TDEC”), joined in the Complaint seeking injunctive relief and civil penalties for Chattanooga’s alleged violations of the Tennessee Water Quality Control Act (“TWQCA”), Tenn. Code Ann. §§ 69-3-101 *et seq.*, and the regulations promulgated pursuant thereto; and

WHEREAS, on October 13, 2010, Plaintiff, the Tennessee Clean Water Network (“TCWN”), filed a complaint against Chattanooga, Civil Action No. 1:10-CV-281 Collier/Lee (USDC E.D. TN), which case was consolidated with this matter, alleging CWA violations, including unauthorized discharges from the West Bank and East Bank Outfalls, sanitary sewer overflows (“SSO”), combined sewer overflows (“CSOs”) during dry weather, exceedances of E. coli limits in the discharge from the Moccasin Bend Wastewater Treatment Plant, and failure to properly measure and report the volume of SSOs (the “TCWN Complaint”); and

WHEREAS, the Court entered the Consent Decree (“Consent Decree”) in this matter on April 24, 2013, requiring that certain injunctive relief be undertaken by Chattanooga with the goal of eliminating SSOs; and

WHEREAS, the United States, TDEC, and Chattanooga (the “Parties”) have determined that there are provisions of the Consent Decree that need to be amended in this First Material Consent Decree Modification (“First Material Modification”); and

WHEREAS, the Parties agree that Chattanooga has materially complied with all of the requirements of the Consent Decree to date; and

WHEREAS, Chattanooga has presented information indicating that its ability to meet deadlines for several of the provisions in the Consent Decree has been affected by the continuation of substantial flows of wastewater to Chattanooga's sewer system from satellite sewer systems, including a sewer system owned and operated by the Hamilton County Water and Wastewater Treatment Authority ("WWTA"); and

WHEREAS, at the time it signed the Consent Decree, Chattanooga anticipated that, as a result of its Interjurisdictional Agreement Program (see Paragraph 20.(i). of the Consent Decree) with municipal satellite sewer systems, WWTA would be timely conducting assessment and remediation work in the WWTA sewer system that would reduce peak flows to the Chattanooga sewer system and, together with substantial work undertaken by Chattanooga under its Consent Decree, enable Chattanooga to meet various requirements of the Consent Decree; and

WHEREAS, for a variety of reasons, WWTA has not undertaken assessment and remediation work to mitigate flows to Chattanooga's sewer system at the pace that was anticipated by Chattanooga; and

WHEREAS, in addition to mitigating the substantial flows of wastewater from WWTA to Chattanooga's sewer system, WWTA must prevent the occurrence of unauthorized bypasses of the treatment works that occur at its only publicly operated treatment works ("POTW"), the Signal Mountain POTW, during certain rain events; and

WHEREAS, one remedial option the WWTA is considering is to decommission the Signal Mountain POTW, and reroute the flows currently being treated at that POTW to Chattanooga's sewer system for treatment; and

WHEREAS, Chattanooga has agreed to accept substantial and potentially increased flows of wastewater from WWTa, including from the Signal Mountain POTW if WWTa determines to decommission the POTW, on the condition that it receive relief in the form of the extension of certain deadlines in the Consent Decree while WWTa and Chattanooga together undertake additional work that will reduce peak flows from WWTa and enhance Chattanooga's ability to manage flows from WWTa and from within its own sanitary sewer system ("SSS"); and

WHEREAS, Chattanooga has agreed to perform, in collaboration with WWTa, a number of infrastructure projects not originally required by the Consent Decree, but which substantially relate to the improvement of water quality and sewer system capacity in the area surrounding the City of Chattanooga, all as reflected in this First Material Modification and in a separate agreement between Chattanooga and WWTa, the Environmental and Economic Infrastructure Improvements Plan signed on December 5, 2019 (the "e2i2 Agreement"), as amended on April 6, 2021, April 22, 2022, and April 18, 2023, and the e2i2 Agreement and each of its amendments are attached hereto as Exhibit 1 to this First Material Modification; and

WHEREAS, Chattanooga's commitment to accept substantial and potentially increased flows of wastewater from WWTa is reflected in the Interjurisdictional Agreement between Chattanooga and WWTa (attached as Exhibit 2 to this First Material Modification), in the e2i2 Agreement as amended, and in this First Material Modification; and

WHEREAS, Chattanooga has demonstrated that it is appropriate to extend the deadlines for several of the provisions of the Consent Decree, due in significant part to its commitment to continue to accept substantial and potentially increased flows of wastewater from WWTa and also because of its voluntary agreement to perform, in collaboration with WWTa, a number of other projects not originally required by the Consent Decree, but which substantially relate to the

improvement of water quality and sewer system capacity in the area surrounding the City of Chattanooga; and

WHEREAS, there was a typographical error in the Consent Decree concerning the distribution of stipulated penalties that has led to the distribution of penalties between the United States and Tennessee in a manner that is not consistent with the intent of the Parties, and it is corrected in this First Material Modification; and

WHEREAS, the Parties agree, and the Court by entering this First Material Modification finds, that this First Material Modification is fair, reasonable and in the public interest;

NOW, THEREFORE, it is hereby ORDERED, ADJUDGED and DECREED as follows:

1. The Court has jurisdiction over the subject matter of this action and over the Parties to this First Material Modification pursuant to Paragraphs 1 and 86 of the Consent Decree.
2. Pursuant to Paragraph 87 of the Consent Decree, material modifications of the Consent Decree may be made by written agreement of the Parties and shall be effective only upon approval by the Court.
3. The following Paragraph is hereby substituted for Paragraph 20.(h).ii of the Consent Decree:

Capacity Certifications. Except as provided in Paragraph 20.(h).iii. through vi. below, commencing sixty (60) Months after the Effective Date of the First Material Modification to this Consent Decree (“First Material Modification”), Chattanooga shall authorize a new sewer service connection in the SSS, or additional flow from an existing sewer service connection in the SSS, only after it certifies that the analysis procedures contained in the approved CAP have been

used and that Chattanooga has determined, based on those procedures, that there is Adequate Treatment Capacity, Adequate Transmission Capacity, and Adequate Collection Capacity as set forth in Paragraph 20.(h).ii.(A) through (E) below.

4. The following Paragraph is hereby substituted for Paragraph 20.(h).ix. of the Consent Decree:

Existing Capacity Program. Upon its execution of this Consent Decree and until Capacity Certifications are required by Paragraph 20.(h)(ii), Chattanooga shall continue to implement its current capacity program, to ensure that new sewer service connections, or increases in flow from existing sewer service connections, are authorized only if there will be adequate treatment, transmission, and collection capacity prior to the time such proposed additional flow is introduced into the WCTS. A copy of Chattanooga's current capacity program is hereby attached as Appendix F to this Consent Decree.

5. The following Paragraph is hereby substituted for Paragraph 22 of the Consent Decree:

Early Action Capital Improvement Projects. Based on previous investigations, Chattanooga has identified certain rehabilitation and other projects that are intended to address conditions currently causing SSOs in the WCTS and other violations alleged in the Complaint and the TCWN Complaint which shall be referred to as "Early Action Capital Improvement Projects." The Early Action Capital Improvement Projects are identified and described in Appendix C, attached hereto and incorporated herein. Chattanooga contends that the Early Action Capital Improvement Projects, along with the Sewersheds to be

remediated in SSES Phase I, constitute approximately fifteen percent (15%) of the WCTS by linear foot. Chattanooga shall complete each of these Early Action Capital Improvement Projects in accordance with the schedules set forth in Appendix C. Such schedules do not extend past five (5) years after the Effective Date of this Consent Decree, unless otherwise indicated in Appendix C. Any change to this list of projects or schedule approved by EPA shall not constitute a material modification to this Consent Decree as set forth in Section XIX below.

6. The following Paragraph is hereby substituted for Paragraph 23 of the Consent Decree:

East Bank/West Bank Outfall Assessment and Rehabilitation Plan. Chattanooga's WCTS has experienced SSOs containing large volumes of wet weather flow from the SSS at unpermitted outfalls known as the East Bank Outfall and the West Bank Outfall. Based on previous investigations, Chattanooga contends that the SSOs from these unpermitted outfalls will be eliminated through the reduction of I/I in the WCTS as a result of implementation of the Inter-jurisdictional Agreement Program, SSES Phase I, and the Early Action Capital Improvement Projects. However, in the event that either the East Bank Outfall or the West Bank Outfall experiences an SSO within a 12-month period commencing sixty (60) Months from Effective Date of the First Material Modification, Chattanooga shall submit to EPA and TDEC for review and comment within seven (7) Months after such SSO event (that occurs during that 12-month period) an East Bank/West Bank Assessment and Rehabilitation Plan to eliminate SSOs from these unpermitted outfalls. The Parties acknowledge that this Plan may include a

proposal by Chattanooga to have the East Bank and/or West Bank Outfall permitted as a CSO Outfall. The East Bank/West Bank Assessment and Rehabilitation Plan shall include expeditious schedules for specific assessment and rehabilitation projects for the elimination of the SSOs and/or the potential permitting of the East Bank and/or West Bank Outfall as a CSO Outfall. Such expeditious schedules shall not exceed seven (7) years after EPA approves the East Bank/West Bank Assessment and Rehabilitation Plan.

7. The following projects are hereby added to the table in Appendix C of the

Consent Decree:

No	Projects	Description	Completion Date
16	e2i2 – Lee Highway	This project is described in detail in the e2i2 Agreement, as amended. The main features of this project are to perform a flow analysis to determine a basis of design and install a wet weather pump station, storage tank to equalize wet weather flows, and upgrade gravity sewer and other appurtenances.	60 mos. after the Effective Date of the First Material Modification
17	e2i2 – East Ridge	This project is described in detail in the e2i2 Agreement, as amended. The main features of this project are to perform a flow analysis to determine a basis of design and install a wet weather pump station, storage tanks to equalize wet weather flows, and upgrade gravity sewer and other appurtenances.	60 mos. after the Effective Date of the First Material Modification
18	e2i2 – Signal Mountain/Red Bank	This project is described in detail in the e2i2 Agreement, as amended. The main features of this project are to perform a flow analysis to allow for the upgrade of gravity sewers and other appurtenances and to determine a basis of design and install wet weather pump station(s) and storage tank(s) to equalize wet weather flows from Red Bank and potentially flows from the Signal Mountain POTW.	July 1, 2028



No	Projects	Description	Completion Date
		<p>If Chattanooga has received notification by July 1, 2024, that WWTA will decommission the Signal Mountain plant and send Signal Mountain flow to Chattanooga, this project shall be sized, designed and constructed to accommodate Red Bank flows and flows from the Signal Mountain WWTP, as described in the e2i2 Agreement, as amended.</p> <p>If Chattanooga has not received notification by July 1, 2024, that WWTA will decommission the Signal Mountain plant and send Signal Mountain flows to Chattanooga, this project, if necessary, shall be sized, designed and constructed to accommodate Red Bank flows, as described in the e2i2 Agreement, as amended, and Chattanooga shall not be required to manage any Signal Mountain WWTP flows through this project.</p>	

8. The following Paragraph is hereby substituted for Paragraph 50 of the Consent Decree:

Except for the stipulated penalty in Subparagraph 48.(i)., Chattanooga shall pay stipulated penalties within thirty (30) Days of a written demand by EPA. For the stipulated penalty in Subparagraph 48.(i)., Chattanooga shall pay stipulated penalties within thirty (30) Days of a written demand by TDEC. Except for the stipulated penalties in Subparagraphs 48.(h). and (i)., Chattanooga shall pay fifty (50) percent of the total stipulated penalty amount demanded to the United States and fifty (50) percent of the total stipulated penalty amount demanded to the State. For the stipulated penalty in Subparagraph 48.(h)., Chattanooga shall pay

one hundred (100) percent of the total stipulated penalty amount due to the United States. For the stipulated penalty in Subparagraph 48.(i)., Chattanooga shall pay one hundred (100) percent of the total stipulated penalty amount due to the State.

9. The following description of Chattanooga's current capacity program is hereby added as Appendix F to the Consent Decree:

Appendix F  
Chattanooga's Current Capacity Program

**Step 1.** Chattanooga's Water Resources Division ("WRD") receives a completed capacity ("CAP") request with the following information:

- CAP request form including project data;
- Flow calculations sealed by a licensed Professional Engineer in the State of Tennessee; and
- GIS map indicating the location of the wastewater connection point.

**Step 2.** If the expected additional flow is less than 2,500 gallons per day ("gpd"), it is considered a minor connection and is approved after confirmation that the connection is not directly upstream of a "Chronic Overflow Location," as that term is defined in Chattanooga's NPDES permit. All minor connection flows are logged in the banking credit system contemplated by the Consent Decree, and all minor connections will be cumulated and added to the City's hydraulic model (developed pursuant to 20.(g) under the Consent Decree) semi-annually, with all connections for the preceding six months being added to the model within thirty (30) days of January 1 and July 1 of each year.

**Step 3.** If the expected additional flow is greater than 2,500 gpd the proposed flow is added to the City's hydraulic model. The flow is then simulated and the output is analyzed by WRD engineering staff.

**Step 3a.** If the model output shows that there are no new sanitary sewer overflows ("SSOs") caused by the additional flow based on a 2-year, 24-hour storm event, and the flow does not contribute to a Chronic Overflow Location, then the capacity request is approved and logged into the banking credit system.

**Step 3.b.** If the model output shows that there are new SSOs that may be caused by the additional flow based on a 2-year, 24-hour storm, or that the additional flow will contribute to an existing Chronic Overflow Location, then the applicant is notified of any necessary capacity improvements that they are required to perform prior to approving the connection. Such necessary improvements shall include, at a minimum, for non-storage projects, an estimated reduction in peak flows or added capacity resulting from capacity improvement projects that exceed a factor of 2:1. Storage projects are credited on a 1:1 ratio. The required improvements then must be completed prior to making the connection and the improvements and connection are logged in the banking credit system.

10. The following Paragraph is hereby substituted for Paragraph 98 of the Consent Decree:

The following appendices are attached to and part of this Consent Decree:

"Appendix A" is the map of Chattanooga's Sewersheds.

"Appendix B" is the CDROM disk containing EPA Region IV's MOM guidance.

"Appendix C" is the list and description of the Early Action Capital Improvement

Projects.

“Appendix D” is the description of the State Project.

“Appendix E” is the description of the Supplemental Environmental Project.

“Appendix F” is the description of Chattanooga’s Current Capacity Program.

11. This First Material Modification shall be lodged with the Court for a period of not less than thirty (30) days for public notice and comment in accordance with 28 C.F.R. § 50.7.

The United States reserves the right to withdraw or withhold its consent if the comments regarding the First Material Modification disclose facts or considerations indicating that the First Material Modification is inappropriate, improper, or inadequate. Chattanooga consents to entry of this First Material Modification without further notice and agrees not to withdraw from or oppose entry of this First Material Modification by the Court or to challenge any provision of the First Material Modification, unless the United States has notified Chattanooga in writing that it no longer supports entry of this First Material Modification.

12. The Effective Date of this First Material Modification shall be the date upon which this First Material Modification is entered by the Court or a motion to enter the First Material Modification is granted, whichever occurs first, as recorded on the Court’s docket.

[THIS SPACE IS INTENTIONALLY LEFT BLANK]

Dated and entered this \_\_\_\_\_ day of \_\_\_\_\_, 2023.

---

CURTIS L. COLLIER  
UNITED STATES DISTRICT JUDGE

WE HEREBY CONSENT to the entry of this Consent Decree, subject to the public notice and comment provisions of 28 C.F.R. § 50.7:

FOR PLAINTIFF UNITED STATES OF AMERICA:

TODD KIM  
Assistant Attorney General  
U.S. Department of Justice  
Environment and Natural Resources Division

Date 12/3/2023

s/ Peter Krzywicki  
PETER KRZYWICKI  
Trial Attorney  
U.S. Department of Justice  
Environment and Natural Resources Division  
Environmental Enforcement Section  
Denver Place Building  
Suite 370 – South Terrace  
Denver, Colorado 80202  
Telephone: 202-532-3218

WE HEREBY CONSENT to the entry of this Consent Decree, subject to the public notice and comment provisions of 28 C.F.R. § 50.7:

FOR PLAINTIFF UNITED STATES OF AMERICA (Continued):

FRANCIS M. (TREY) HAMILTON III  
Acting United States Attorney  
Eastern District of Tennessee

ROBERT C. MCCONKEY, III  
Chief, Civil Division  
Assistant United States Attorney  
Eastern District of Tennessee  
800 Market Street, Suite 211  
Knoxville, TN 37902  
Phone: 865-225-1657  
Email: Robert.McConkey@usdoj.gov

WE HEREBY CONSENT to the entry of this Consent Decree, subject to the public notice and comment provisions of 28 C.F.R. § 50.7:

FOR PLAINTIFF UNITED STATES OF AMERICA (Continued):

**Leif Palmer** Digitally signed by Leif Palmer  
Date: 2023.09.07 10:07:50 -04'00'

---

LEIF PALMER  
Regional Counsel  
United States Environmental Protection Agency  
Region 4  
61 Forsyth Street  
Atlanta, GA 30303

PAUL SCHWARTZ Digitally signed by PAUL  
SCHWARTZ  
Date: 2023.09.05 11:34:25 -04'00'

---

PAUL SCHWARTZ  
Associate Regional Counsel  
United States Environmental Protection Agency  
Region 4  
61 Forsyth Street  
Atlanta, GA 30303  
Telephone: 404-562-9576  
Fax: 404-562-9486



WE HEREBY CONSENT to the entry of this Consent Decree, subject to the public notice and comment provisions of 28 C.F.R. § 50.7:

FOR PLAINTIFF UNITED STATES OF AMERICA (Continued):

JOSEPH THEIS Digitally signed by JOSEPH  
THEIS  
Date: 2023.11.13 09:11:39  
-05'00'

---

JOSEPH THEIS  
Acting Director, Water Enforcement Division  
Office of Civil Enforcement  
Office of Enforcement and Compliance Assurance  
United States Environmental Protection Agency


FOR PLAINTIFF STATE OF TENNESSEE:

JONATHAN SKRMETTI  
Attorney General and Reporter of Tennessee




SOHNIA W. HONG, TN BPR No. 017415  
Deputy Attorney General  
Environmental Division  
Office of Attorney General  
P.O. Box 20207  
Nashville, Tennessee 37202-0207  
Telephone: 615-741-2379  
Fax: 615-741-4151  
E-Mail: [sohnia.hong@ag.tn.gov](mailto:sohnia.hong@ag.tn.gov)

FOR DEFENDANT CITY OF CHATTANOOGA:

  
Tim Kelly (Nov 15, 2023 9:50 EST)

TIM KELLY  
City of Chattanooga  
Office of the Mayor  
City Hall  
101 E. 11th Street  
Chattanooga, TN 37402  
Telephone (423) 643-7800  
E-Mail: mayor@chattanooga.gov

  
Phillip A. Noblett (Nov 15, 2023 10:01 EST)

PHILLIP A. NOBLETT  
Chattanooga City Attorney  
City of Chattanooga  
100 E. 11th Street, Suite 200  
Chattanooga, TN 37402  
Telephone: (423) 643-8250  
Fax: (423) 643-8255  
E-Mail: pnoblett@chattanooga.gov

  
Adam G Sowatzka (Nov 15, 2023 10:03 EST)

ADAM G. SOWATZKA  
Partner  
McGuireWoods LLP  
1175 Peachtree St., N.E., 35th Floor  
Atlanta, Georgia 30309  
Telephone: (404) 443-5749  
Cell: (770) 309-5349  
E-Mail: asowatzka@mcguirewoods.com

Exhibit 1  
e2i2 Agreement and Amendments

**ENVIRONMENTAL AND ECONOMIC INFRASTRUCTURE IMPROVEMENTS PLAN  
AN INTER LOCAL AGREEMENT FOR COST SHARING BETWEEN  
THE CITY OF CHATTANOOGA, TENNESSEE AND THE HAMILTON COUNTY  
WATER AND WASTEWATER TREATMENT AUTHORITY GOVERNING SEWER  
FLOW AND SEWER SYSTEM CAPITAL IMPROVEMENTS**

THIS INTER LOCAL AGREEMENT FOR COST SHARING (“Agreement”) is entered into between the CITY OF CHATTANOOGA, TENNESSEE, a municipal corporation located in Hamilton County, Tennessee, organized and existing under the laws of the State of Tennessee (hereinafter referred to as "Chattanooga" or the “City”), and, THE HAMILTON COUNTY WATER AND WASTEWATER TREATMENT AUTHORITY, an authority organized and existing under the laws of the State of Tennessee (hereinafter referred to as "WWTA"). Chattanooga and WWTA are sometimes referred to in this Agreement individually as a “Party” and collectively as the “Parties.”

WHEREAS, Chattanooga entered into a consent decree with the United States and the State of Tennessee, and the Tennessee Clean Water Network, in the case styled United States of America et. al. v. City of Chattanooga, No. 1:12-cv-00245, which became effective on April 23, 2013 (the “Chattanooga Consent Decree”); and

WHEREAS, Chattanooga has certain obligations under the Chattanooga Consent Decree, which requires it to spend significant financial resources to meet those obligations; and

WHEREAS, in November 2018, the Tennessee Riverkeeper (“Riverkeeper”) filed a lawsuit against WWTA alleging violations of the Clean Water Act related to WWTA’s sewer system; and

WHEREAS, the WWTA is engaged in confidential settlement discussions with the United States Environmental Protection Agency (“EPA”), the Tennessee Department of Environment and Conservation (“TDEC”) and Riverkeeper and WWTA intends to seek a settlement of the lawsuit filed by the Riverkeeper; and

WHEREAS, there are certain sewer projects, that if performed cooperatively by WWTA and Chattanooga, would significantly lower the size and cost of the projects if they were otherwise performed independently by WWTA and Chattanooga, resulting in savings for the taxpayers and rate payers in Chattanooga and WWTA; and

WHEREAS, in order to have the financial resources necessary to complete the mutually beneficial projects on the timeframe that WWTA needs for its possible settlement with EPA, TDEC and Riverkeeper, Chattanooga will need the EPA, TDEC, and the TCWN to agree to extend the schedule of certain requirements set forth in the Chattanooga Consent Decree, as set forth more fully below; and

WHEREAS, in a desire to work cooperatively on the mutually beneficial projects, it is necessary to enter into this Agreement; and

NOW, THEREFORE, IN CONSIDERATION of the premises and mutual undertakings as set forth herein, it is mutually agreed by and between Chattanooga and WWTA, each acting by and through its duly authorized officials, and pursuant to resolutions duly, legally, and properly adopted:

### LEE HIGHWAY AREA

1. Chattanooga will plan for, engineer, and oversee the construction of an equalization ("EQ") station for wet weather storage at 7148 Lee Hwy Rd, Chattanooga, Tennessee, with a capacity of an estimated 10 million gallons ("Lee Highway EQ Station Project"). The Lee Highway EQ Station Project will also include a pump station, force main, gravity sewer line improvements and other infrastructure improvements needed to allow the regional connections the ability to deliver approximately 10 million gallons per day ("MGD") through this location.
2. WWTA will be responsible for paying for their share of the total project cost (to include, but not be limited to, engineering, design, construction, and finance but excluding ongoing maintenance) of the Lee Highway EQ Station Project based on the final total capacity of the Lee Highway EQ Station Project, which is currently estimated to be 30% (e.g., 3 million gallons out of a total of an estimated 10 million gallons). Chattanooga will be responsible for funding the overall cost of the Lee Highway EQ Station Project and WWTA agrees to fully repay Chattanooga by contributing a down payment of 5% of its ultimate obligation at the time of construction notice to proceed and paying the balance in equal monthly installments, which Chattanooga will invoice at the same time it invoices its wheelage and treatment to WWTA and which WWTA will pay at the same time it pays its monthly wheelage and treatment obligations.
3. WWTA will plan for, engineer, and undertake other sewer projects in its sewer system to ensure that the maximum flow rate at the connection point from the WWTA's system from the Lee Highway Area into the Chattanooga system (as shown in the inter-jurisdictional agreement ("IJA") entered into between the Parties) does not exceed 6 MGD downstream of the Lee Highway EQ Station Project, which will be accomplished before the EQ station is online. If the flow contributed by WWTA at this connection point exceeds 6 MGD, WWTA shall pay penalties of 15% as set forth in the IJA between the Parties.
4. Chattanooga's obligation to perform the work on the Lee Highway EQ Station Project under this Agreement is subject to WWTA meeting its financial obligations.
5. Chattanooga will offer the City of Collegedale an opportunity to contribute to the Lee Highway EQ Station Project in exchange for Collegedale's agreement to reimburse Chattanooga in proportion to the amount of flow Collegedale sends to the Lee Highway EQ Station Project. Chattanooga may agree to increase the capacity of the Lee Highway EQ station if Collegedale commits to participating and the relative percentage of the responsibility for the cost will be offset by Collegedale's participation if they choose to participate. For purposes of illustration, if the total capacity increases to 12 million gallons and Collegedale is allocated 2 million gallons, Chattanooga is allocated 7 million

gallons, and WWTa is allocated 3 million gallons, WWTa will be responsible for 25% of the total project costs for the Lee Highway EQ Station Project.

6. Chattanooga and WWTa agree that Chattanooga will retain legal ownership over the Lee Highway EQ Station Project and will have the responsibility to operate it and maintain it following completion of construction.

#### **EAST RIDGE AREA**

7. Chattanooga will conduct a feasibility study to determine the size, location characteristics and infrastructure for an EQ station to be located near the intersection of I-75 and South Chickamauga Creek with a capacity of up to 20 million gallons ("East Ridge EQ Station Project"). The East Ridge EQ Station Project will include plus a pump station, force main, and gravity sewer improvements sufficient to take full advantage of the EQ station. If the feasibility study determines that the project is economically and technically feasible, Chattanooga will fund the design and construction of the East Ridge EQ Station Project in a location and capacity consistent with the findings of the study. The primary factors in the feasibility study that will determine the size of the EQ station will be current inflow and infiltration ("I/I") rates as well as projected regional growth.
8. WWTa will be responsible for paying for their share of the total project cost (to include, but not be limited to, engineering, design, construction, and finance but excluding ongoing maintenance) of the East Ridge EQ Station Project in an amount financially proportional to its share of the total flow into the EQ station as determined during the feasibility analysis. Chattanooga will be responsible for funding the overall cost of the East Ridge EQ Station Project and WWTa agrees to fully repay Chattanooga by contributing a down payment of 5% of its ultimate obligation at the time of construction notice to proceed and paying the balance in equal monthly installments, which Chattanooga will invoice at the same time it invoices its wheelage and treatment to WWTa and which WWTa will pay at the same time it pays its monthly wheelage and treatment obligations.
9. Currently, WWTa is sending Chattanooga peak flows of 22 MGD from the East Ridge area. WWTa will plan for, engineer, and undertake projects to reduce these peak flows to 10 MGD on a schedule to be agreed to by Chattanooga and WWTa. WWTa will pay a surcharge of 15% for volume it discharges that exceeds the volume allowed in the schedule, which the Parties agree will be provided for in an IJA.
10. Before commencement of the Feasibility Study, Chattanooga will offer the town of Fort Oglethorpe, Georgia an opportunity to participate in the EQ project in exchange for 1) Fort Oglethorpe's agreement to accept ownership of and responsibility for the Spring Creek Pumping Station and the Northwest Georgia Interceptor; and 2) making a financial contribution to the project proportional to the amount of storage Fort Oglethorpe will require, which will be determined by the Feasibility Study and Fort Oglethorpe's agreement to enter into an updated IJA with Chattanooga.

11. Before commencement of the Feasibility Study, Chattanooga will offer the town of Ringgold, Georgia the opportunity to participate in the EQ project in exchange for 1) making a financial contribution to the project proportional to the amount of storage Ringgold Fort Oglethorpe will require, which will be determined by the Feasibility Study and 2) Ringgold's agreement to enter into an updated IJA with Chattanooga.
12. Chattanooga and WWTA agree that Chattanooga will retain legal ownership over the East Ridge EQ Station Project subject to the requirements of the funding mechanisms employed by Chattanooga and WWTA and will have the responsibility to operate it and maintain it following completion of construction.

#### **RED BANK AREA**

13. Chattanooga will conduct a feasibility study regarding the possibility of constructing an EQ station near the intersection of Pineville Road and Hudson Road ("Red Bank EQ Station Project"). If the feasibility study determines the construction of the EQ station is economically and technically feasible, Chattanooga will take the next step of acquiring the property.
14. Once the property is acquired, Chattanooga will plan for, engineer and oversee the completion of the Red Bank EQ Station Project in this location with an approximate size of 11 million gallons of wet weather storage (subject to the findings of the feasibility study). Additional components include a pump station, force main, and gravity sewer improvements.
15. WWTA will be responsible for paying for their share of the total project cost (to include, but not be limited to, engineering, design, construction, and finance but excluding ongoing maintenance) of the Red Bank EQ Station Project in an amount financially proportional to its share of the total flow into the EQ station, which is currently expected to be 10 million gallons of the estimated 11 million gallons. Final capacity of the EQ station and the components to be determined by the feasibility study. Chattanooga will be responsible for funding the overall cost of the Red Bank EQ Station Project and WWTA agrees to fully repay Chattanooga by contributing a down payment of 5% of its ultimate obligation at the time of construction notice to proceed and paying the balance in equal monthly installments, which Chattanooga will invoice at the same time it invoices its wheelage and treatment to WWTA and which WWTA will pay at the same time it pays its monthly wheelage and treatment obligations.
16. Chattanooga will agree to take the flow from Signal Mountain, not to exceed 5.0 MGD. Chattanooga does not have transmission capacity for this flow. Therefore, WWTA shall install a force main so that the flow is transmitted directly to a diversion structure to the EQ station. Also, there is not currently an inter-jurisdictional agreement ("IJA") between Chattanooga and WWTA that addresses this flow. WWTA and Chattanooga agree to negotiate and enter into an IJA to allow flow from Signal Mountain to enter Chattanooga's collection system, once the Red Bank EQ Station Project is completed. The Red Bank IJA will specify that the peak flow from Signal Mountain shall not exceed 5.0 MGD and all such flows will be transmitted directly to a diversion structure to the EQ



station associated with the Red Bank EQ Station Project. If this flow rate is exceeded, WWTA will pay penalties of 15%, which the Parties agree will be provided for in an IJA.

17. WWTA is currently sending Chattanooga peak flows of approximately 8.3 MGD from Red Bank. WWTA will plan for, engineer, and undertake projects in Signal Mountain and Red Bank to reduce these flows through the reduction in inflow and infiltration and other related projects agreed upon by the Parties. If this flow rate is exceeded WWTA shall pay excess flow penalties of 15%, which the Parties agree will be provided for in an IJA.
18. Chattanooga and WWTA agree that Chattanooga will retain legal ownership over the Red Bank EQ Station Project subject to the requirements of the funding mechanisms employed by Chattanooga and WWTA and will have the responsibility to operate it and maintain it following completion of construction.

#### **ADDITIONAL TERMS**

19. WWTA will commit to the following, which will be reflected a settlement between WWTA, the Riverkeeper, TDEC, and EPA:
  - a. Eliminate discharges from the Signal Mountain waste water treatment plant by eliminating the treatment plant altogether when the Red Bank EQ station is completed.
  - b. Accelerating the reduction of overflows in the South Chickamauga Creek basin by accelerating key I/I projects, including those in Signal Mountain, East Ridge, and Red Bank.
  - c. Accelerating elimination of the SSOs in several key areas, including East Ridge, Signal Mountain, and Red Bank sooner than would otherwise occur under WWTA's current schedule for performance of its required collection system rehabilitation, through the acceleration of the following projects:
    - i. EQ Stations in strategic areas as described in this Agreement;
    - ii. Construction of pump station and force main leading to the diversion structure for the Red Bank EQ station; and
    - iii. I/I reduction projects in Signal Mountain in East Ridge and in Red Bank.
20. The obligations of the Parties set forth above are subject to the lodging and entry by the United States District Court of the WWTA Consent Decree. If the Consent Decree is not entered and lodged within twelve (12) months after the Effective Date of this Agreement, this Agreement will become null and void.
21. The obligations of the Parties set forth above are subject to modification of the Chattanooga Consent Decree to extend the deadlines established in Paragraphs 20(h)(ii) and 23 of Chattanooga's Consent Decree by 60 months. If the Court does not approve a

modification to the Chattanooga Consent Decree within twelve (12) months of the Effective Date of this Agreement regarding the extension of time, this Agreement will be null and void.

22. Chattanooga's obligations to allow WWTa to use capacity created through the development of the Lee Highway EQ Station Project, the East Ridge EQ Station Project, and the Red Bank EQ Station Project, is contingent on WWTa meeting its financial obligations under this Agreement.
23. General Provisions:
  - a. Effective Date. This Agreement will be effective when signed by both Parties below.
  - b. Counterparts. The Parties may execute this Agreement in separate counterparts, and each counterpart shall be deemed to be an original instrument
  - c. Controlling Law and Venue. The Parties hereto agree that this Agreement will be enforced and interpreted according to the laws of the State of Tennessee. The Parties hereto further agree that any action brought to enforce this agreement shall be brought in the State or Federal Courts in the State of Tennessee.
  - d. Dispute Resolution. Unless otherwise specifically provided for herein, if there is a dispute between the Parties, the Parties shall meet and confer for a period not to exceed thirty (30) days. If the matter is not resolved to the mutual satisfaction of the Parties, either Party has a right to seek relief from a court of competent jurisdiction. The prevailing party has the right to seek reimbursement of the cost of such legal challenge, including without limitation the reimbursement of attorney's fees, costs, and expenses.
  - e. Assignment. The Parties agree that the rights, liabilities, and obligations of either may be assigned to a successor governmental entity or authority, and that either Party's interest in this Agreement may be used to secure financing to improve the system of that Party or to establish a sewer authority. Providing, if the assignment involves a change in operational control, the assignee shall agree to assume the liability and duty of the assignor to perform all of the terms and conditions of this Agreement.
  - f. Severability. Should any phrase, clause, sentence, or paragraph of this contract be held invalid, or unconstitutional by any Court or competent jurisdiction in any manner or respect whatsoever, it shall in no wise affect any or all of the remaining provisions, all of which shall remain in full force and effect.
  - g. Third-Party Beneficiaries. Except as expressly provided herein, the Parties do not intend to create any rights in third persons and the Parties agree that there are no third-party beneficiaries to this Agreement. Except as expressly set forth herein, no person other than a Party to this Agreement may enforce this Agreement's

terms, claim the right to benefit from its provisions, or rely upon the existence of its terms or conditions for its benefit.

- h. Additional Documentation. Each Party hereto covenants to execute such additional documentation as will be necessary to effectuate the intent of this Agreement.

IN WITNESS WHEREOF, the Parties hereto enter into this Agreement. Each person signing this Agreement represents and warrants that he or she has been duly authorized to enter into this Agreement by the corporate body or municipality on whose behalf it is indicated that the person is signing.



City of Chattanooga, Tennessee

By: Justin Holland

Its: Administrator of Public Works

Date: 12/5/19



Hamilton County Water and Wastewater Treatment Authority

By: MICHAEL C. PATRICK

Its: EXECUTIVE DIRECTOR

Date: 11/27/19

**FIRST AMENDMENT TO THE  
ENVIRONMENTAL AND ECONOMIC INFRASTRUCTURE IMPROVEMENTS PLAN  
AN INTER LOCAL AGREEMENT FOR COST SHARING BETWEEN THE CITY OF  
CHATTANOOGA, TENNESSEE AND THE HAMILTON COUNTY WATER AND  
WASTEWATER TREATMENT AUTHORITY GOVERNING SEWER FLOW AND  
SEWER SYSTEM CAPITAL IMPROVEMENTS**

The purpose of this document is to amend the ENVIRONMENTAL AND ECONOMIC INFRASTRUCTURE IMPROVEMENTS PLAN AN INTER LOCAL AGREEMENT FOR COST SHARING BETWEEN THE CITY OF CHATTANOOGA, TENNESSEE AND THE HAMILTON COUNTY WATER AND WASTEWATER TREATMENT AUTHORITY GOVERNING SEWER FLOW AND SEWER SYSTEM CAPITAL IMPROVEMENTS ("e2i2 Agreement"), which is hereby entered into between the CITY OF CHATTANOOGA, TENNESSEE, a municipal corporation located in Hamilton County, Tennessee, organized and existing under the laws of the State of Tennessee (hereinafter referred to as "Chattanooga" or the "City"), and, THE HAMILTON COUNTY WATER AND WASTEWATER TREATMENT AUTHORITY, an authority organized and existing under the laws of the State of Tennessee (hereinafter referred to as "WWTA"), and shall be referred to as the 1<sup>st</sup> Amendment. Chattanooga and WWTA are sometimes referred to in this 1<sup>st</sup> Amendment individually as a "Party" and collectively as the "Parties."

WHEREAS, the Parties hereby acknowledge that the Effective Date of the e2i2 Agreement is December 5, 2019, and without this 1<sup>st</sup> Amendment, the e2i2 would be null and void on its own terms;

WHEREAS, the Parties intend to modify the terms of the e2i2 Agreement as set forth in this 1<sup>st</sup> Amendment;

The Parties hereby agree to the following:

1. Amend paragraph 19.a of the e2i2 agreement so that it reads as follows:  
**Consider eliminating the** ~~Eliminate~~ discharges from the Signal Mountain waste water treatment plant by **considering** eliminating the treatment plant altogether, **as well as options to upgrade the plant**, when the Red Bank EQ station is completed.
2. Amend paragraph 20 of the e2i2 agreement so that it reads as follows: The obligations of the Parties set forth above are subject to the lodging and entry by the United States District Court of the WWTA Consent Decree. If the Consent Decree is not entered and lodged within **twenty-four (24)** ~~twelve (12)~~ months after the Effective Date of this Agreement, this Agreement will become null and void.
3. Amend paragraph 21 of the e2i2 agreement so that it reads as follows: The obligations of the Parties set forth above are subject to modification of the Chattanooga Consent Decree to extend the deadlines established in Paragraphs 20(h)(ii) and 23 of Chattanooga's Consent Decree by 60 months. If the Court does not approve a modification to the Chattanooga Consent Decree within **twenty-four (24)** ~~twelve (12)~~ months of the Effective Date of this Agreement regarding the extension of time, this Agreement will be null and void.

4. The Parties may execute this Agreement in separate counterparts, and each counterpart shall be deemed to be an original instrument.

5. The Effective Date of this 1<sup>st</sup> Amendment shall be the date signed by both Parties below.

IN WITNESS WHEREOF, the Parties hereto enter into this 1<sup>st</sup> Amendment. Each person signing this 1<sup>st</sup> Amendment represents and warrants that he or she has been duly authorized to enter into this agreement by the corporate body or municipality on whose behalf it is indicated that the person is signing.

City of Chattanooga, Tennessee	Hamilton County Water and Wastewater Treatment Authority
By: <i>[Signature]</i>	By: <i>Michael [Signature]</i>
Its: Interim Administrator	Its: EXECUTIVE DIRECTOR
Date: Mar 15, 2021	Date: 4/6/21

RESOLUTION NO. 31013

A RESOLUTION AUTHORIZING THE ADMINISTRATOR FOR THE DEPARTMENT OF PUBLIC WORKS TO EXECUTE A SECOND AMENDMENT TO THE ENVIRONMENTAL AND ECONOMIC INFRASTRUCTURE IMPROVEMENTS PLAN (E2I2), AN INTERLOCAL AGREEMENT FOR COST SHARING BETWEEN THE CITY OF CHATTANOOGA AND THE HAMILTON COUNTY WATER AND WASTEWATER TREATMENT AUTHORITY, AS PART OF THE CITY OF CHATTANOOGA'S CONSENT DECREE AND SAID AMENDMENT TO EXTEND THE DEADLINE TO COMPLETE THE PROJECT.

---

BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF CHATTANOOGA, it is hereby authorizing the Administrator for the Department of Public Works to execute a Second Amendment to the Environmental and Economic Infrastructure Improvements Plan (e2i2), an Interlocal Agreement for cost sharing between the City of Chattanooga and the Hamilton County Water and Wastewater Treatment Authority, as part of the City of Chattanooga's Consent Decree and said amendment to extend the deadline to complete the project.

ADOPTED: January 11, 2022

/mem

RESOLUTION NO. 25213

A RESOLUTION AUTHORIZING WILLIAM PAYNE, CITY ENGINEER, DEPARTMENT OF PUBLIC WORKS, TO SIGN VOUCHERS, REQUISITIONS, SHIPPING RELEASES, AND OTHER NECESSARY DOCUMENTS FOR AND ON BEHALF OF THE PUBLIC WORKS DEPARTMENT.

---

BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF CHATTANOOGA, TENNESSEE, That William Payne, City Engineer, Department of Public Works, be and is hereby authorized to sign vouchers, requisitions, shipping releases, and other necessary documents for and on behalf of the Public Works Department.

ADOPTED: August 14, 2007

/add

**HAMILTON COUNTY WATER & WASTEWATER  
TREATMENT AUTHORITY**

**RESOLUTION**

NO. 0222-08

**TITLE:** A HAMILTON COUNTY WATER & WASTEWATER TREATMENT AUTHORITY (WWTA) BOARD RESOLUTION AMENDING THE TERMS OF THE INTERLOCAL AGREEMENT WITH THE CITY OF CHATTANOOGA ENTITLED, "THE ENVIRONMENT AND ECONOMIC INFRASTRUCTURE IMPROVEMENTS (E<sup>2</sup>I<sup>2</sup>)."

**WHEREAS,** Resolution 1119-05 authorized and approved the City of Chattanooga and the WWTA to work cooperatively on the mutually beneficial sewer projects in the "The Environment and Economic Infrastructure Improvements (E<sup>2</sup>I<sup>2</sup>)" interlocal agreement; and,

**WHEREAS,** Resolution 0321-06 modified the the terms set forth in the First Amendment of the E2I2 Agreement; and,

**WHEREAS,** the updated modification of the terms are set forth in the attached Second Amendment.

**NOW THEREFORE, BE IT RESOLVED BY THE COMMISSIONERS OF THE HAMILTON COUNTY WATER & WASTEWATER TREATMENT AUTHORITY:**

A resolution of the WWTA amending the terms in the Interlocal Agreement with the City of Chattanooga entitled, "The Environment and Economic Infrastructure Improvements (E2I2)."

Approved:

  
Chair

2.23.22

Date



**SECOND AMENDMENT TO THE  
ENVIRONMENTAL AND ECONOMIC INFRASTRUCTURE  
IMPROVEMENTS PLAN AN INTER LOCAL AGREEMENT  
FOR COST SHARING BETWEEN THE CITY OF CHATTANOOGA,  
TENNESSEE AND THE HAMILTON COUNTY WATER AND  
WASTEWATER TREATMENT AUTHORITY GOVERNING SEWER FLOW  
AND SEWER SYSTEM CAPITAL IMPROVEMENTS**

The purpose of this document is to amend the ENVIRONMENTAL AND ECONOMIC INFRASTRUCTURE IMPROVEMENTS PLAN AN INTER LOCAL AGREEMENT FOR COST SHARING BETWEEN THE CITY OF CHATTANOOGA, TENNESSEE AND THE HAMILTON COUNTY WATER AND WASTEWATER TREATMENT AUTHORITY GOVERNING SEWER FLOW AND SEWER SYSTEM CAPITAL IMPROVEMENTS ("e2i2 Agreement"), which is hereby entered into between the CITY OF CHATTANOOGA, TENNESSEE, a municipal corporation located in Hamilton County, Tennessee, organized and existing under the laws of the State of Tennessee (hereinafter referred to as "Chattanooga" or the "City"), and, THE HAMILTON COUNTY WATER AND WASTEWATER TREATMENT AUTHORITY, an authority organized and existing under the laws of the State of Tennessee (hereinafter referred to as "WWTA"), and shall be referred to as the 2<sup>nd</sup> Amendment. Chattanooga and WWTA are sometimes referred to in this 2<sup>nd</sup> Amendment individually as a "Party" and collectively as the "Parties."

**WHEREAS**, the Parties hereby acknowledge that the Effective Date of the original e2i2 Agreement was December 5, 2019, and that the original e2i2 Agreement contained provisions that provided for its expiration on December 5, 2020; and

**WHEREAS**, on April 6, 2021, the Parties executed a 1<sup>st</sup> Amendment to the e2i2, which among other things, modified the provisions to allow for the extension of the e2i2 Agreement through December 5, 2021; and

**WHEREAS**, the Parties intend to modify the terms of the e2i2 Agreement as set forth in this 2<sup>nd</sup> Amendment, including extending the expiration date of same; and

The Parties hereby agree to the following:

1. Amend paragraph 16 of the e2i2 Agreement, as amended by the 1<sup>st</sup> Amendment, by adding the following at the end of the paragraph: WWTA agrees to make a determination of whether it is going to send flow from Signal Mountain by June 1, 2023. If WWTA does not send a written notice electing to send flow to Signal Mountain by that date, Chattanooga's agreement to accept such flow is null and void and Chattanooga shall have no contractual obligation under this e2i2 Agreement, or under the current Inter-Jurisdictional Agreement between the Parties, to accept such flow.
2. Amend paragraph 17 of the e2i2 Agreement, as amended by the 1<sup>st</sup> Amendment, by adding the following at the end of the paragraph: The Parties acknowledge that WWTA is in the process of implementing several projects in the Red Bank service area that if successful will substantially reduce flows to Chattanooga and that those projects are estimated to be completed by

June 2024. The sizing of any project contemplated under paragraphs 14, 15 and 16 above will take these projects into account, including but not limited to the fact that such projects may eliminate the need for an EQ Station and may substantially impact the sizing of the pump station upgrade.



3. Amend paragraph 20 of the e2i2 Agreement, as amended by the 1<sup>st</sup> Amendment, so that it reads as follows: The obligations of the Parties set forth above are subject to the lodging and entry by the United States District Court of the WWTa Consent Decree. If the Consent Decree is not entered and lodged within thirty-six (36) months after the Effective Date of this Agreement, this Agreement will become null and void.

4. Amend paragraph 21 of the e2i2 Agreement so that it reads as follows: The obligations of the Parties set forth above are subject to modification of the Chattanooga Consent Decree to extend the deadlines established in Paragraphs 20(h)(ii) and 23 of Chattanooga's Consent Decree by sixty (60) months. If the Court does not approve a modification to the Chattanooga Consent Decree within thirty-six (36) months of the Effective Date of this Agreement regarding the extension of time, this Agreement will be null and void.

5. The Parties may execute this Agreement in separate counterparts, and each counterpart shall be deemed to be an original instrument.

6. The Effective Date of this 2<sup>nd</sup> Amendment shall be the date signed by both Parties below.

IN WITNESS WHEREOF, the Parties hereto enter into this 2<sup>nd</sup> Amendment. Each person signing this 2<sup>nd</sup> Amendment represents and warrants that he or she has been duly authorized to enter into this agreement by the corporate body or municipality on whose behalf it is indicated that the person is signing.

City of Chattanooga, Tennessee	Hamilton County Water and Wastewater Treatment Authority
By:  William C. Payne	By: 
Its: City Engineer for the Administrator	Its: Chair
Date: 04-22-22	Date: 02/23/2022

**THIRD AMENDMENT TO THE  
ENVIRONMENTAL AND ECONOMIC INFRASTRUCTURE IMPROVEMENTS PLAN  
AN INTER LOCAL AGREEMENT FOR COST SHARING BETWEEN THE CITY OF  
CHATTANOOGA, TENNESSEE AND THE HAMILTON COUNTY WATER AND  
WASTEWATER TREATMENT AUTHORITY GOVERNING SEWER FLOW AND  
SEWER SYSTEM CAPITAL IMPROVEMENTS**

The purpose of this document is to amend the ENVIRONMENTAL AND ECONOMIC INFRASTRUCTURE IMPROVEMENTS PLAN AN INTER LOCAL AGREEMENT FOR COST SHARING BETWEEN THE CITY OF CHATTANOOGA, TENNESSEE AND THE HAMILTON COUNTY WATER AND WASTEWATER TREATMENT AUTHORITY GOVERNING SEWER FLOW AND SEWER SYSTEM CAPITAL IMPROVEMENTS (“e2i2 Agreement”), which is hereby entered into between the CITY OF CHATTANOOGA, TENNESSEE, a municipal corporation located in Hamilton County, Tennessee, organized and existing under the laws of the State of Tennessee (hereinafter referred to as "Chattanooga" or the "City"), and, THE HAMILTON COUNTY WATER AND WASTEWATER TREATMENT AUTHORITY, an authority organized and existing under the laws of the State of Tennessee (hereinafter referred to as "WWTA"), and shall be referred to as the Third Amendment. Chattanooga and WWTA are sometimes referred to in this Third Amendment individually as a "Party" and collectively as the "Parties."

WHEREAS, the Parties hereby acknowledge that the Effective Date of the original e2i2 Agreement was December 5, 2019, and that the original e2i2 Agreement contained provisions that provided for its expiration on December 5, 2020;

WHEREAS, on April 6, 2021, the Parties executed a 1<sup>st</sup> Amendment to the e2i2 Agreement, which among other things, modified the provisions to allow for the extension of the e2i2 Agreement through December 5, 2021;

WHEREAS, on April 22, 2022, the Parties executed a 2<sup>nd</sup> Amendment to the e2i2 Agreement, which among other things, modified the provisions to allow for the extension of the e2i2 Agreement through December 5, 2022;

WHEREAS, the parties are currently working on terms for the joint financing of the projects that are the subject of the e2i2 Agreement, which may be included in the e2i2 Agreement by way of an additional future amendment;

WHEREAS, the Parties intend to modify the terms of the e2i2 Agreement as set forth in this Third Amendment, including extending the expiration date of same;

The Parties hereby agree to the following:

1. Amend paragraph 16 of the e2i2 Agreement, as amended by the 1<sup>st</sup> Amendment, by adding the following at the end of the paragraph: “WWTA agrees to make a determination of whether it is going to send flow from Signal Mountain by July 1, 2027. If WWTA does not send a written notice electing to send flow to Signal Mountain by that date, Chattanooga’s agreement to accept such flow is null and void and Chattanooga shall have no contractual obligation under

this e2i2 Agreement, or under the current Inter-Jurisdictional Agreement between the Parties, to accept such flow.”

2. Amend paragraph 20 of the e2i2 Agreement, as amended, so that it reads as follows: “The obligations of the Parties set forth above are subject to the lodging by the United States District Court of the WWTa Consent Decree. If the Consent Decree is not lodged by December 5, 2023, this Agreement will become null and void, unless otherwise extended by the Parties in a writing signed by both Parties.”

3. Amend paragraph 21 of the e2i2 Agreement, as amended, so that it reads as follows: “The obligations of the Parties set forth above are subject to modification of the Chattanooga Consent Decree to extend the deadlines established in Paragraphs 20(h)(ii) and 23 of Chattanooga's Consent Decree by 60 months. If the modification of the Chattanooga Consent Decree is not lodged by the Parties to the Chattanooga Consent Decree by December 5, 2023, this Agreement will become null and void.”

4. The Parties may execute this Third Amendment in separate counterparts, and each counterpart shall be deemed to be an original instrument.

5. The Effective Date of this Third Amendment shall be the date signed by both Parties below.

IN WITNESS WHEREOF, the Parties hereto enter into this Third Amendment. Each person signing this Third Amendment represents and warrants that he or she has been duly authorized to enter into this agreement by the corporate body or municipality on whose behalf it is indicated that the person is signing.

City of Chattanooga, Tennessee	Hamilton County Water and Wastewater Treatment Authority
By: <u>Mark Heinzer</u> Mark Heinzer (Apr 18, 2023 09:22 EDT)	By: <u>Michael Patrick</u> Michael Patrick (Apr 18, 2023 09:24 EDT)
Its: Interim Administrator	Its: Executive Director
Date: Apr 18, 2023	Date: Apr 18, 2023

Exhibit 2  
Interjurisdictional Agreement

## INTER-JURISDICTIONAL AGREEMENT

This INTER-JURISDICTIONAL AGREEMENT (“Agreement”) is hereby entered into between the CITY OF CHATTANOOGA, TENNESSEE, a municipal corporation located in Hamilton County, Tennessee, organized and existing under the laws of the State of Tennessee (“Chattanooga” or the “City”), and THE HAMILTON COUNTY WATER AND WASTEWATER TREATMENT AUTHORITY, an authority organized and existing under the laws of the State of Tennessee (referred to as “WWTA”). Chattanooga and WWTA are sometimes referred to in this Agreement individually as a “Party” and collectively as the “Parties.”

WHEREAS, pursuant to the Chattanooga Area 208 Waste Treatment Management Plan, Chattanooga operates the Moccasin Bend Wastewater Treatment Plant (“WWTP”), a "treatment works" of sufficient size and capacity to serve as an area wide wastewater treatment works for portions of Hamilton County, Tennessee and portions of Northwest Georgia located in Dade, Walker, and Catoosa County, Georgia; and

WHEREAS, pursuant to the Chattanooga Area 208 Waste Treatment Management Plan, Chattanooga constructed and operated its WWTP as a part of the 201 Area Wide Facilities Plan, WWTA being located in the drainage redefined by the 201 Area Wide Facilities Plan and served by Chattanooga's treatment works, desires to convey wastewater to Chattanooga's WWTP for treatment and disposal; and

WHEREAS, pursuant to the National Pollutant Discharge Elimination System (“NPDES”) permit for the treatment works all wastewater and extraneous waters from all sources entering the City of Chattanooga's wastewater collection and transmission system or “WCTS” from inside or outside its boundaries are required to be treated and discharged through permitted point sources; and

WHEREAS, WWTA sends wastewater from its WCTS to various points of Chattanooga's WCTS and over time Chattanooga and WWTA have entered into various inter-jurisdictional and inter-local agreements related to such discharges; and

WHEREAS, Chattanooga and WWTA entered into an agreement on March 2, 2018, titled “Inter-Jurisdictional Agreement Between the City of Chattanooga, Tennessee and Hamilton County Water and Wastewater Treatment Authority – Lee Highway Pump Station,” governing the flows from WWTA to Chattanooga through the pump station to be located at Lee Highway, which is hereinafter referred to as the Lee Highway Agreement; and

WHEREAS, Chattanooga and WWTA entered into an agreement, which was effective on December 5, 2019, titled “Environmental and Economic Infrastructure Improvements Plan and Inter Local Agreement for Cost Sharing Between the City of Chattanooga Tennessee and the Hamilton County Water and Wastewater Treatment Authority Governing Sewer Flow and Sewer System Capital Improvements,” which is hereinafter referred to as the “e2/i2 Agreement”; and

WHEREAS, Chattanooga entered into a consent decree with the United States Environmental Protection Agency (“EPA”), represented by the Justice Department (“DOJ”), the

State of Tennessee, and the Tennessee Clean Water Network, in the case styled *United States of America et. al. v. City of Chattanooga*, No. 1:12-cv-00245, which became effective on April 23, 2013 (“Chattanooga Consent Decree”); and

WHEREAS, WWTA is in the process of negotiating a consent decree with EPA, TDEC, and the Tennessee Riverkeeper, Inc. (“Riverkeeper”) to resolve allegations of violations of the CWA and its NPDES permit (“WWTA Consent Decree”); and

WHEREAS, Chattanooga and WWTA each desire to enter into this Agreement in order to each comply with their respective consent decrees and to replace the previous agreements between Chattanooga and WWTA relating to WWTA’s discharge of wastewater into Chattanooga’s WCTS, except for the e2/i2 Agreement; and

WHEREAS, by virtue of the authority of the laws of Tennessee, particularly T.C.A. §§ 7-35-301 through 7-35-304, Chattanooga is authorized to enter into such an agreement: and

WHEREAS, by virtue of the authority of the laws of Tennessee, WWTA is authorized to enter into this Agreement.

NOW, THEREFORE, IN CONSIDERATION of the premises and mutual undertakings as hereinafter set forth, it is mutually agreed by and between Chattanooga and WWTA, each acting by and through its duly authorized officials, and pursuant to resolutions duly, legally, and properly adopted;

1. Purpose.

a. Flow Limits. WWTA is authorized pursuant to the terms and conditions of this Agreement to discharge wastewater into the Chattanooga WCTS for treatment and disposal of the flow from those connections expressly specified in Exhibits 1-A through 1-F, in the amounts as specified in the Exhibits to this Agreement. All plans related to the inter-connection points will be subject to review and approval by Chattanooga. This Agreement shall not cover any other connections from WWTA to the Chattanooga WCTS that are not specified in this Agreement; provided, however, that the parties agree to amend such flow amounts specified herein as necessary to account for the additional capacity from the projects completed under and as contemplated by the e2/i2 Agreement.

b. New Connections. WWTA shall submit a written request for any new inter-connections from WWTA’s WCTS to the Chattanooga WCTS. If those additional connection points are acceptable to Chattanooga, this Agreement shall be amended in a writing signed by both parties.

c. Chattanooga’s Responsibilities. Chattanooga shall be responsible for the conveyance of wastewater from WWTA’s WCTS to Chattanooga treatment works after the connection points specified in the Exhibits to this Agreement and shall be responsible for appropriate treatment and disposal of such wastewater.

2. Agreement Term.

a. Term. This Agreement shall become effective on the date signed by both Parties (“Effective Date”), and shall remain in effect for a period of fifteen (15) calendar years. The Agreement may be extended through mutual agreement in a writing signed by both Parties.

b. Reopener. The Parties recognize that from time to time there may be changes in federal or state laws and regulations relating to the environment and to the operation of sewer systems and treatment works that necessitate the modification of this Agreement. Either Party may petition the other Party by sending a request for modification in writing. The Parties agree to fully cooperate and take all reasonable measures to modify this Agreement as shall be required under such circumstances. If there is a disagreement regarding the terms of such proposed modification, such disagreement shall be subject to the dispute resolution procedures set forth herein.

3. Definitions. Terms used in this Agreement that are defined in the CWA or in regulations promulgated pursuant to the CWA shall have the meanings assigned to them in the CWA, 33 U.S.C. §§ 1251 et seq., and regulations promulgated under the CWA, unless otherwise provided in this Agreement. Whenever the terms set forth below are used in this Agreement, the following specific definitions shall apply:

a. Act or "the Act" means the Federal Water Pollution Control Act, also known as the Clean Water Act, as amended, 33 U.S.C. §§ 1251, et seq.

b. Chattanooga Area 208 Waste Treatment Management Plan shall mean a plan prepared under the provisions of Section 208 of the Act (33 U.S.C. § 1288) for area wide waste treatment management for areas of Hamilton County, Tennessee, and Dade, Catoosa, and Walker Counties in Georgia, as conditionally certified and designated by the respective governors of Tennessee and Georgia as conditionally approved by the Administrator of the Environmental Protection Agency or as may be modified from time to time hereafter.

c. Capacity, Management, Operation, and Maintenance or “CMOM” program means flexible program of accepted industry practices to properly manage, operate, and maintain sanitary wastewater collection, transmission, and treatment systems; to investigate capacity constrained areas of these system; and to respond to SSO events.

d. Department of Justice or “DOJ” means the United States Department of Justice and any of its successor departments or agencies.

e. Environmental Protection Agency or "EPA" means the United States Environmental Protection Agency, an agency of the United States, or where appropriate the term may also be used as a designation for the Administrator or other duly authorized official of said agency.

f. Georgia Environmental Protection Division or “EPD” means the Environmental Protection Division of the Department of Natural Resources of the State of Georgia as defined by Ga. St. § 12-5-22 which regulates the operation of sewer systems and



activities that alter the waters of the State of Georgia including any successor agency having such responsibility.

g. Infiltration, as defined by 40 C.F.R. § 35.2005(b)(20), means water other than wastewater that enters the sewer system including sewer service connections and foundation drains from the ground through such means as defective pipes, pipe joints, connections and manholes.

h. Inflow, as defined by 40 C.F.R. § 35.2005(b)(21), means water that enters the sewer system (including entering service connections) from sources such as, but not limited to, roof leaders, cellar drains, yard drains, area drains, drains from springs, swampy areas, manhole covers, cross connections between storm sewers and sanitary sewers, catch basins, cooling towers, storm water, surface run off, street wash waters, and drainage.

i. Inflow Infiltration or “I/I” means the total quantity of water from inflow and infiltration. The term excessive I/I is defined by 40 C.F.R. § 35.2005(b)(16).

j. Interference means a discharge which, alone or in conjunction with a discharge(s) from other sources, both inhibits or disrupts the POTW, its treatment process or operations, or its sludge processes, use or disposal, and therefore is a cause of a violation of any requirement of the POTW's NPDES permit (including an increase in the magnitude or duration of a violation) or of the prevention of sewage sludge use or disposal in compliance with the following statutory provisions and regulations or permits issued there under (or more stringent State or local regulations): Section 405 of the Clean Water Act, the Solid Waste Disposal Act (“SWDA”) (including Title 11, more commonly referred to as the Resource Conservation and Recovery Act (“RCRA”), and including State regulations contained in any State sludge management plan prepared pursuant to Subtitle D of the SWDA), the Clean Air Act, the Toxic Substances Control Act, and the Marine Protection, Research and Sanctuaries Act. See 40 C.F.R. §403.3(i). Additionally, excessive I/I that causes or contributes to SSOs and discharge violations at the POTW shall be considered as causes of interference.

k. Local Pretreatment Standards means any substantive or procedural requirement related to pretreatment, other than a National Pretreatment Standard imposed on an industrial user.

l. National Pollutant Discharge Elimination System Permit or “NPDES” Permit means NPDES permit no. TN0024210 issued to Chattanooga pursuant to Section 402 of the Clean Water Act, 33 U.S.C. §1342, for the Moccasin Bend WWTP and any such future extended, modified, or reissued permits.

m. National Pretreatment Standard or Pretreatment Standard means any regulation containing pollutant discharge limits promulgated by the EPA in accordance with Section 307(b) and (c) of the Act (33 U.S.C. § 1317) and applies to Industrial Users. This term includes prohibitive discharge limits established pursuant to 40 C.F.R § 403.5. See 40 C.F.R § 403.3(j).

n. Publicly Owned Treatment Works or “POTW” shall mean a treatment works as defined by Section 212 of the Act (33 U.S.C. 1292), and includes any sewers that convey wastewater to such a treatment works, and any devices and systems used in the storage, treatment, recycling and reclamation of municipal sewage or liquid industrial waste but does not include pipes, sewers or other conveyances not connected to a facility providing treatment.

o. Tennessee Department of Environment and Conservation or “TDEC” means the administrative department or agency of the State of Tennessee that regulates the operation of sewer systems and activities that alter the waters of the State of Tennessee including any successor agency having such responsibility.

p. Wastewater Collection and Transmission System or “WCTS” means the wastewater collection, retention, and transmission systems including all pipes, force mains, gravity collection and interceptor sewer lines, lift stations, pump stations, manholes, and other appurtenances thereto that are designed to collect and convey wastewater to and from the user interconnection points.

4. **Rejection of Wastewater.** Chattanooga reserves the right to reject any wastewater from WWTA which does not meet its standards. Except for instances where there may be an imminent and substantial endangerment to human health or the environment, Chattanooga shall notify WWTA in writing at least thirty (30) days prior to rejecting any such wastewater flow the basis for such rejection. To the extent that Chattanooga rejects such wastewater flow for treatment, WWTA shall then be authorized to attempt to provide additional conveyance and treatment from any other source or to provide necessary pretreatment to bring the rejected wastewater into compliance.

5. **Imminent and Substantial Endangerment.** If any wastewater from WWTA could cause or lead to an imminent or substantial endangerment to human health, the environment or Chattanooga’s WCTS, including without limitation the potential for interference of or other harm to Chattanooga’s WCTS or with the operation of the WWTP, upon discovery or notification of such, WWTA shall immediately take steps to halt said discharge and mitigate the harm. Chattanooga may seek injunctive relief against WWTA and/or any user contributing to the emergency condition, and/or may pursue other self-help remedies. WWTA agrees to assist Chattanooga and to join such litigation and/or hereby assigns to Chattanooga the right to bring such action in its name and for their mutual benefit. In the event Chattanooga seeks injunctive relief or self-help remedies against WWTA and/or any user contributing to the emergency condition, Chattanooga shall be entitled under this Agreement to recover all costs and expenses related to such action from WWTA and/or any user contributing to the emergency condition.

6. **Review of Consent Decree Deliverables by Chattanooga.**

a. Chattanooga and WWTA acknowledge that for the purpose of Chattanooga’s ability to comply with the Chattanooga Consent Decree and to protect the WCTS, Chattanooga has an interest in monitoring whether WWTA is complying with the WWTA Consent Decree and whether the manner in which it is complying with the WWTA Consent Decree will enable Chattanooga to comply with the Chattanooga Consent Decree. To that end, WWTA agrees to provide a copy of all deliverables submitted to EPA and TDEC under the

WWTA Consent Decree, including correspondence, draft and final reports, to Chattanooga prior to the time that they are submitted to EPA and TDEC under the WWTA Consent Decree in accordance with the following schedule:

<b>Deliverable in WWTA Consent Decree</b>	<b>Deadline for WWTA Submission to Chattanooga</b>	<b>Deadline for Chattanooga Response to WWTA</b>	<b>Deadline for WWTA Objection</b>
Sanitary Sewer Evaluation/Rehabilitation Work Plan	Three months before the CD submission deadline for this deliverable	45 days after receipt from WWTA	30 days after Response from Chattanooga
Sewer Overflow Response Plan	Four months before the CD submission deadline for this deliverable	45 days after receipt from WWTA	45 days after response from Chattanooga
Gravity Sewer System Operations and Maintenance Program	Four months before the CD submission deadline for this deliverable	45 days after receipt from WWTA	45 days after response from Chattanooga
Pump Station Operations and Preventative Maintenance Program	Four months before the CD submission deadline for this deliverable	45 days after receipt from WWTA	45 days after response from Chattanooga
Fats, Oils and Grease Control Program	Four months before the CD submission deadline for this deliverable	45 days after receipt from WWTA	45 days after response from Chattanooga
Capacity Assurance Program	Four months before the CD submission deadline for this deliverable	45 days after receipt from WWTA	45 days after Response from Chattanooga
<b>Group Evaluation Work Plans</b>			
Group 1	Four months before the CD submission deadline for this deliverable	45 days after receipt from WWTA	45 days after Response from Chattanooga
Group 2	Four months before the CD submission deadline for this deliverable	45 days after receipt from WWTA	45 days after Response from Chattanooga
Group 3	Four months before the CD submission deadline for this deliverable	45 days after receipt from WWTA	45 days after Response from Chattanooga

<b>Deliverable in WWTA Consent Decree</b>	<b>Deadline for WWTA Submission to Chattanooga</b>	<b>Deadline for Chattanooga Response to WWTA</b>	<b>Deadline for WWTA Objection</b>
Group 4	Four months before the CD submission deadline for this deliverable	45 days after receipt from WWTA	45 days after Response from Chattanooga
Group 5	Four months before the CD submission deadline for this deliverable	45 days after receipt from WWTA	45 days after Response from Chattanooga

b. Chattanooga may review a deliverable identified in the chart in Paragraph 6(a) and if it believes that the deliverable should be amended in order for Chattanooga to be able to meet its Consent Decree obligations or to protect its WCTS, Chattanooga may provide comments to WWTA and request that WWTA amend the deliverable prior to submitting to EPA and TDEC. Chattanooga's request must be specific, must detail the changes requested, and must contain a justification for the request and explanation of why the changes are needed to allow Chattanooga to comply with the Chattanooga Consent Decree or protect its WCTS. Chattanooga's comments on a deliverable must be made in accordance with the schedule in Paragraph 6(a) above. If Chattanooga fails to provide comments within the time period provided above for their review, the WWTA deliverable will be deemed approved by Chattanooga. If WWTA disagrees with Chattanooga's requested changes, it will notify Chattanooga in accordance with the dispute resolution provisions of this Agreement.

c. Nothing contained in this Paragraph 6 shall prevent Chattanooga from providing comments to EPA or TDEC on any deliverable in the WWTA Consent Decree as part of the public comment process set forth in the WWTA Consent Decree.

7. Sewer Use Ordinance. WWTA shall regulate through a comprehensive sewer user ordinance, a contract with any user, or other appropriate regulatory measures, the introduction of wastewater into its WCTS, which discharges through the connection specified in the Exhibits to this Agreement, in a manner essentially consistent with ordinances and other regulatory measures adopted by Chattanooga, including but not limited to those adopted in its sewer use ordinance. WWTA's Sewer Use Ordinance shall comply with the following requirements:

a. Legal Requirements. WWTA's comprehensive sewer user ordinance, contract, or other appropriate measure shall conform to the minimum legal requirements contained in the Federal Pretreatment Regulation (40 C.F.R. § 403). Additionally, said sewer user ordinance, contract, or other appropriate measure shall incorporate local pretreatment standards and other ancillary regulations at least as stringent as those then in effect in Chattanooga.

b. Regulatory Agency Approval. Within three (3) months of the Effective Date of this Agreement, WWTA shall submit its comprehensive sewer user ordinance, contract, or other appropriate measure to Chattanooga for its review and approval.

c. Ordinance Review. Once WWTA's comprehensive sewer user ordinance, contract, or other appropriate measure is approved by Chattanooga, every three (3) years WWTA shall review and update its comprehensive sewer user ordinance, contract, or other appropriate measure and resubmit it to Chattanooga for review and approval. WWTA shall review and update its comprehensive sewer user ordinance, contract, or other appropriate measure for continued compliance with appropriate state agency or EPA regulations and Chattanooga's local pretreatment standards.

8. Discharge and Pretreatment Standards.

a. Discharge Standards. Chattanooga has the obligation under state and Federal law to regulate the introduction of wastewater into Chattanooga's WCTS, including but not limited to discharges from industrial and commercial sources, and to operate the POTW in conformity with applicable federal and state laws, regulations, and NPDES permits. As such, Chattanooga hereby restricts the discharge of the following into its WCTS, and WWTA agrees to comply with such restrictions:

1. Pollutants which create a fire or explosion hazard;
2. Pollutants which will cause corrosive structural damage;
3. Solid or viscous pollutants in amounts which will cause obstruction to the flow in sewers or other interference with the operation of the POTW;
4. Pollutants, including oxygen demanding pollutants (biochemical oxygen demand, etc.), released in a discharge of such volume or strength as to cause interference in the POTW;
5. Pollutants, including oxygen demanding pollutants (biochemical oxygen demand, etc.), released in a discharge of such volume or strength as to cause an objectionable odor or other such public nuisance;
6. Heat which will inhibit biological activity in the POTW;
7. Petroleum oils, non-biodegradable cutting oils, or products of mineral oil origin in amounts that will cause interference or pass through the WWTP;
8. Pollutants which result in the presence of toxic gases, vapors, or fumes in a quantity that may cause acute worker health and safety problems;
9. Pollutants which result in the presence of toxic gases, vapors, or fumes in a quantity that may cause a public nuisance; and

10. Any trucked or hauled pollutants, except at discharge points designated by Chattanooga.

b. Local Pretreatment Standards. To achieve the standards and provisions set forth in the City's NPDES permit, Chattanooga has established specific discharge limitations (sometimes hereinafter referred to as "local pretreatment standards") regulating the introduction of wastewater into the WCTS by certain classes of users, particularly industrial users, which may from time to time need to be revised. Chattanooga may review said local pretreatment standards and revise same from time to time. WWTA agrees to comply with all such standards, and cooperate with Chattanooga in the enforcement of such standards within WWTA's WCTS which is subject to this Agreement.

c. Categorical Pretreatment Standards. WWTA's ordinance, user agreement, or other regulatory measure shall incorporate categorical pretreatment standards promulgated by the EPA by authority of the Act Sections 307(b) and (c), 33 U.S.C. § 1317. These standards shall supersede any specific discharge limits in the ordinance, contract or other regulatory measure which are less stringent than the categorical standards as they apply to the particular industrial subcategory. Further, WWTA shall notify all affected industrial users of pertinent categorical standards, monitoring and reporting requirements contained in 40 C.F.R. § 403.12 or included as part of the categorical standard. WWTA agrees that all industrial wastes will be pretreated in accordance with the foregoing standards before being released into the Chattanooga WCTS at the connection points specified in the Exhibits to this Agreement.

d. Compliance Monitoring and Enforcement. If Chattanooga requests, WWTA agrees to carry out monitoring and inspection activities to determine compliance by industrial users with pretreatment standards in a manner essentially consistent with such activities then being undertaken by Chattanooga. WWTA may contract with a competent person, corporation, or governmental agency, including Chattanooga, to sample and analyze wastewater samples. Chattanooga shall be furnished a copy of the data obtained from such monitoring activities by WWTA and a copy of any industrial monitoring reports submitted by users of the WCTS. WWTA and Chattanooga may collect effluent samples from WWTA's WCTS, including any dischargers within WWTA's WCTS. Chattanooga and WWTA agree to cooperate in the collection of such samples and to exchange the results of any analysis of such split samples. WWTA agrees to work jointly with Chattanooga in processing applications for discharge of industrial waste or other regulated waste into the Chattanooga WCTS. Both Parties shall have the authority to withhold approval of an application for discharge of industrial or other regulated waste for cause. The approval of any such application will not be unreasonably withheld.

e. Chattanooga's Administration of Pretreatment Program. Chattanooga and WWTA may enter into a pretreatment agreement providing Chattanooga with the legal authority and responsibility for performance of technical and administrative activities necessary for implementation of a pretreatment program for WWTA. These activities may include, among others: updating the industrial waste survey; providing technical services, such as sampling, process chemical analysis, and engineering advice; industrial user discharge permitting; compliance monitoring; and enforcement support.

f. Pretreatment Program Enforcement. Chattanooga currently administers pretreatment permitting and compliance for industrial dischargers into WWTA's WCTS. If WWTA begins to administer a pretreatment program for such dischargers, Chattanooga may from time to time review WWTA's pretreatment program, for conformance with 40 C.F.R. § 403, and to ensure inclusion of all other relevant provisions mandated by this Agreement. Chattanooga may periodically review the enforcement efforts of WWTA and any other jurisdiction to ascertain whether pretreatment requirements are being diligently enforced. To the extent WWTA chooses to administer its own pretreatment program, Chattanooga may periodically review WWTA's pretreatment program activities and funding to ensure that WWTA (and that of any outside jurisdiction utilizing Chattanooga's WCTS) is adequately administering its pretreatment program in conformance with the Federal Pretreatment Regulations (40 C.F.R. § 403) and all Chattanooga requirements. If Chattanooga determines that WWTA has failed or has refused to fulfill any pretreatment obligations, Chattanooga may develop and issue a remedial plan containing a description of the nature of the pretreatment deficiencies, an enumeration of steps to be taken by WWTA, and a time schedule for attaining compliance with all pretreatment requirements. WWTA agrees to comply with the terms of such plans.

9. Moratorium. If Chattanooga's WCTS is placed under a moratorium (e.g., from issuing building, construction, or occupancy permits), injunction, administrative order, or any other form of regulatory restriction by any regulatory authority for a portion of Chattanooga's WCTS that receives wastewater from WWTA's WCTS from a connection specified in the Exhibits to this Agreement, WWTA agrees that will also be under an equivalent moratorium for those areas for the same time period that Chattanooga is subject to such restriction. The Parties agree to meet and to develop a joint plan to correct the problems within a reasonable period of time to satisfy the obligations imposed on Chattanooga by any regulatory authority regarding such moratorium or restriction.

10. Excess Flows. In the event that the WWTA's flows exceeds the flows specified in the Exhibits to this Agreement for more than three (3) consecutive months, Chattanooga may take the following actions:

- a. Assess a penalty for such excess flows as set forth in Paragraph 12(b) below.
- b. Issue a notice to WWTA requiring WWTA to conduct an engineering review by a registered professional engineer licensed in the State of Tennessee to determine the actions deemed necessary to lower the flows below the thresholds, and submit such review to Chattanooga for its review and approval. Such plan shall be submitted by WWTA to Chattanooga within ninety (90) days of receipt of written notice and shall include an expeditious schedule to complete all work to address the excess flows.
- c. Issue a moratorium to WWTA restricting it from issuing any building, construction, or occupancy permits in the area or areas exceeding the flow limitations specified in the Exhibits to this Agreement .
- d. Take any other such action in its sole discretion which are necessary to protect its WCTS.

11. Flow Measurement for Billing Purposes.

a. The measurements of wastewater flow from WWTAs' WCTS and into Chattanooga's WCTS at the connection point(s) specified in the Exhibits to this Agreement, shall be by flow monitoring; provided, however, that the Parties recognize that there may be areas where it is technically impractical to install meters and in such event the flow shall be accurately estimated using sound engineering practices for adjusting water metered flow, I/I, and any other particular circumstances.

b. Flow meters shall be of the magnetic type for pump station and force main applications. The meters shall be of the same or equivalent type of meter that is compatible with telemetry equipment as being used in the Chattanooga WCTS. These flow meters shall be installed by WWTAs and approved by Chattanooga. Attached as Exhibits 1A through 1F are the location(s) of the billing flow meters and/or inter-connection points of WWTAs' WCTS to the Chattanooga's WCTS. WWTAs hereby certifies that there are no other known inter-connection points from WWTAs' WCTS and into Chattanooga's WCTS, other than those indicated in the Exhibits to this Agreement.

c. Maintenance. Chattanooga is responsible to operate, maintain, repair and replace flow meters and telemetry equipment used for billing purposes under this Agreement. Any infrastructure requirements for any new inter-connections or modification to inter-connections of WWTAs' WCTS to the Chattanooga WCTS, which are subject to this Agreement, shall be the responsibility of WWTAs.

12. Rates, Billing, and Payments. WWTAs shall pay Chattanooga based on estimated or calculated flows along with any Excess Flow Penalty in the manner hereafter set forth and as set forth in City Code Chapter 31, Article II, Section 31-36, § (c) and (d):

a. Flow Calculations. Flows under this Agreement shall be billed monthly by Chattanooga based on the Total Flow method unless there is a connection specified in the Exhibits to this Agreement where a flow meter cannot be installed, in that event billing will default to the Billable Flow method:

1. Total Flow. The total flow charge is equal to the applicable regional operation and maintenance for wheelage and treatment plus the applicable regional charge for debt (which such charges may contain a capital charge component). The amount due from the regional user shall be the dollar amount derived by applying the Total Flow rate specified in City Code Chapter 31, Article II, Section 31-36, § (d), to the quantity of water measured by a flow meter installed and maintained at or near the point of inter-connection between the system of the regional user and the Chattanooga system. In the event of any malfunction of a flow meter, flow shall be estimated, interpolated and/or projected in a reasonable manner, such as using available readings for periods where there was no malfunction.

2. Billable Flow. The Billable Flow charge is equal to the applicable regional operation and maintenance for wheelage and treatment plus the applicable regional charge for debt (which such charges may contain a capital charge component). The amount due from the regional user shall be the dollar amount derived by applying the total Billable Flow rate



per one thousand (1,000) gallons of water sold (City Code Chapter 31, Article II, Section 31-36, § (c)). If regional customers are billed directly through municipal, utility, or private water company, the rate to be charged shall be equal to the regional billable flow charge applied per one thousand (1,000) gallons.

b. Excess Flow Penalty. If at any time during the billing period, any of the flow rates exceed the maximum flow rate allowed in the Agreement for a connection specified in the Exhibits to this Agreement, Chattanooga in its sole discretion may assess a 15% Excess Flow Penalty to be added to the sewer charge for the billing period for that connection. For the purposes of this Agreement, the maximum flow rates (including instantaneous, daily, and monthly maximum flow rate) are defined as set forth in the Exhibits to this Agreement. For purposes of clarity, any Excess Flow Penalty will be assessed at each location specified in the Exhibits to this Agreement for that month individually, and not to the flows associated with connection points that did not exceed the flow limits set forth in the Exhibits to this Agreement. Further, Chattanooga agrees not to assess the Excess Flow Penalty for a connection whereby the Parties are in the process of implementing a project specified in the e2/i2 Agreement.

c. Payments. Payment from WWTa to Chattanooga shall be made monthly, with payment due within thirty (30) days following the billing date for the preceding month.

d. Source of Payments. The obligation of WWTa to pay for wastewater delivered and treated under this Agreement shall not be construed as a debt of WWTa requiring it to levy and collect a tax to discharge the same unless said obligation has been reduced to a legally enforceable judgment; but shall be an operating charge of its WCTS ranking equally to charges for salaries, wages, and other operating expenses of such system. WWTa covenants at all times to use its best efforts to establish, maintain, prescribe, and collect fees, tolls, and charges for wastewater facilities furnished to its customers, sufficient to provide funds for the payment of all obligations of WWTa under this Agreement.

13. WWTa Sewer Charges and Service Termination.

a. Industrial Surcharges. Chattanooga now has various types of sewer service charges which apply to various dischargers to Chattanooga's WCTS. To the extent that the "industrial user surcharge," as that term is defined by Chattanooga ordinances now in effect or similar charges hereafter adopted, shall apply to industries which may locate within WWTa covered by this Agreement, WWTa agrees to bill said charges directly to the parties responsible.

b. Service Termination. WWTa agrees to terminate the service, by means of its water utility or through any other water utility district or WWTa's WCTS that discharges through the connection point(s) specified in the Exhibits to this Agreement, for any user who does not pay the billings within sixty (60) days, subject to any pending dispute about the accuracy of the billing and provided that the bill shall have been paid except to the extent of any claimed overcharge.

14. Rate Review and Revisions.

a. Chattanooga has the right to periodically revise the charges for users or user classes, from time to time, in its sole discretion. In revising the rates, Chattanooga may consider the following factors:

1. Maintaining the proportionate distribution of operation and maintenance costs among users and user classes as required by federal law and regulations (See 33 U.S.C. §1284(b) and 40 C.F.R. §35-929, et seq.).

2. Generating sufficient revenue to pay the total operation and maintenance costs necessary for the proper operation and maintenance (including replacement) of the treatment works.

3. Applying excess revenues collected from a class of users to the costs of operation and maintenance attributable to that class and adjust the rates accordingly.

4. Chattanooga's ability to comply with Section 204(b) of the Act (33 U.S.C. § 1284(b)) and all applicable federal or state laws and regulations.

5. The cost of operation and maintenance of Chattanooga's WCTS and treatment works not used by WWTA under this agreement.

b. Rate changes may be promulgated through Chattanooga's wastewater ordinance, City Code Chapter 31, Article II, Section 31-36, which provides WWTA notice and opportunity to comment on rate changes.

c. WWTA agrees to maintain a user charge system for its users in accordance with Section 204(b)(1)(A) of the Act (33 U.S.C. § 1284(b)(1)(A)) and 40 C.F.R. § 35.929 through § 35.929-3, or other applicable federal or state laws or regulations. These rates shall be incorporated in appropriate municipal legislative enactments and following the public notification requirements of 40 C.F.R. § 25.

15. Liability for Wastewater. WWTA shall remain fully responsible for any and all liability related to the discharge of wastewater discharged to the Chattanooga WCTS under this Agreement and shall indemnify, defend, and hold harmless the City of Chattanooga, and its officers, employees, agents, and representatives from an against any and all claims, demands, causes of action, judgments, costs, expenses, damages or other liability of any kind, including but not limited to damages for injury or death, and from damage to persons or property. Any payments by WWTA under this provision shall be deemed an operation and maintenance expense of WWTA for purposes of determining the user fees which shall be necessary to ensure that the WCTS has sufficient revenues for operation. *This covenant is not made for the benefit of any third party except as set forth in Paragraph 21(d) herein. Nothing herein shall be deemed to waive any defenses that WWTA may have to the claims of a third party pursuant to the Tennessee Governmental Tort Liability Act (T.C.A. § 29-20-101, et seq.), or otherwise.*

16. Chattanooga's Obligations. Chattanooga covenants and agrees to acquire, equip, operate, and maintain sufficient treatment facilities to comply with the NPDES Permit and in conformance with applicable statutes and regulations. Nothing herein shall prevent Chattanooga from entering into other contracts or agreements relating to the conveyance and treatment of wastewater from other municipalities or agencies.

17. Inter-jurisdictional Contracts. If any industrial users, private owner or owners, or outside jurisdiction discharge to WWTAs WCTS but are located outside of the jurisdictional limits of Chattanooga, then WWTAs shall regulate said user by a contract, ordinance, or resolution so as to enforce terms substantially equivalent to this Agreement, and if by contract it shall be jointly executed by Chattanooga, WWTAs, and the outside jurisdiction. Regulation through the use of an ordinance or resolution shall be the preferred method of regulating users and this method shall be used where legally possible.

18. Stipulated Penalties.

a. WWTAs shall be liable for stipulated penalties to Chattanooga for violations of this Agreement as specified herein. A violation includes failing to perform any obligation required by this Agreement, including without limitation meeting any schedule approved under this Agreement. Stipulated penalties shall begin to accrue on the day after performance is due or the day the violation occurs, whichever is applicable, and shall continue to accrue until performance is satisfactorily completed or until the violation ceases.

b. The following stipulated penalties shall accrue per violation or failure to perform per day for each violation or failure to perform the requirements identified above or herein (except for flow obligations, for which penalties are applied elsewhere in this Agreement):

Period of Failure to Comply	Penalty per Violation per Day
1st through 15th Day	\$350
16th through 30th Day	\$500
31st Day and beyond	\$1,000

c. WWTAs shall pay any stipulated penalty within sixty (60) days of receiving Chattanooga's written demand. Chattanooga's demand for payment of the stipulated penalties shall identify the particular violation or failure to perform to which the stipulated penalty relates, the amount of stipulated penalty being demanded, the calculation method underlying the demand, and the grounds on which the demand is based.

d. If WWTAs fails to pay the stipulated penalties according to the terms of this Agreement, WWTAs shall be liable for interest on such penalties, accruing as of the date payment becomes due. The interest rate shall be three (3) percent (%) plus the prime interest rate or the amount allowable by law, whichever is greater.

e. If a violation exceeds thirty (30) days or if WWTAs fails to make payment of any stipulated penalty within sixty (60) days, it shall be grounds for immediate termination of

this Agreement by Chattanooga. Chattanooga may terminate this agreement and the termination of the physical inter-connection(s) of WWTA WCTS by providing written notice.

19. Dispute Resolution.

a. Disputes about review of WWTA deliverables. Unless otherwise specifically provided for herein, if there is a dispute between the Parties related to the provisions of this Agreement related to WWTA Consent Decree deliverables submitted to Chattanooga for review as set forth in Paragraph 6, the Parties shall meet and confer for a period not to exceed thirty (30) days. If the time needed for resolution of the dispute is expected to extend beyond the deadline for WWTA to submit the deliverable at issue to EPA by the deadline provided by the WWTA Consent Decree, WWTA may submit the deliverable as is or with any changes to which it does not object.

b. All Other disputes. Unless otherwise specifically provided for herein, if there is a dispute between the Parties, other than a dispute that involves WWTA Consent Decree deliverables submitted to Chattanooga for review pursuant to Paragraph 6, the Parties shall meet and confer for a period not to exceed thirty (30) days. If the matter is not resolved to the mutual satisfaction of the Parties, WWTA shall implement the change subject to its right to seek review of the reasonableness of the change in a court of competent jurisdiction. The prevailing party has the right to seek reimbursement of the cost of such legal challenge, including without limitation the reimbursement of attorney's fees, costs, and expenses.

20. Notices. Unless otherwise specified herein, whenever notifications, submissions, or communications are required by this Agreement, they shall be made in writing and addressed as follows:

To the City of Chattanooga:

Attn: City Attorney  
100 E. 11th Street, Suite 200  
Chattanooga, Tennessee 37402

To WWTA:

Attn: Executive Director  
1250 Market St. Suite 3050  
Chattanooga, TN 37402-2713

Any Party may, by written notice to the other Party, change its designated notice recipient or notice address provided above. Further, Notices submitted pursuant to this Agreement shall be deemed submitted upon mailing, unless otherwise provided in this Agreement or by mutual agreement of the Parties in writing.

21. General Provisions.

a. Integration. This Agreement constitutes the final, complete, and exclusive agreement and understanding among the Parties with respect to the terms set forth in this Agreement and supersedes all prior agreements and understandings, whether oral or written, including without limitation the Lee Highway Agreement, concerning the subject matter embodied herein; **provided, however, that the e2/i2 Agreement shall remain in full force and effect to the extent the terms of the e2/i2 Agreement do not conflict with the terms of this Agreement, and in the event of a conflict between the e2/i2 Agreement and this Agreement, this Agreement shall control.** No other document, nor any representation, inducement, agreement, understanding, or promise, constitutes any part of this Agreement, nor shall it be used in construing the terms of this Agreement.

b. Records. WWTA shall file with Chattanooga a certified copy of its ordinance and any amendments thereto, other inter-jurisdictional agreements, each industrial waste discharge permit issued, and any contract entered into for the purposes of industrial waste control. Further, WWTA shall keep copies of any and all records related to WWTA's performance under this agreement until three (3) years after the term of this Agreement expires, and provide Chattanooga access and or copies of such documents within thirty (30) days of Chattanooga's written request.

c. Entry and inspection. Any authorized officer or employee of Chattanooga may enter and inspect at any reasonable time any part of the WCTS of WWTA. The right of entry and inspection shall extend to public property, streets, and sewer easements. Additionally, Chattanooga shall be permitted, as appropriate, to enter onto private property to inspect industrial waste discharges. If a request to enter private property is refused and there is a reasonable need to enter the property, WWTA shall institute necessary legal procedures to obtain an administrative search warrant or easement as appropriate. The right of inspection shall include on-site inspection of pretreatment and sewer facilities, observation, measurement, sampling, testing, and access to (with the right to copy) all pertinent compliance records located on the premises of the industrial user.

d. Third-Party Beneficiaries. The Parties hereto agree that the State of Tennessee is a third-party beneficiary of this Agreement and shall have all rights granted the Parties hereunder to enforce the rights and obligations of the Parties. TDEC shall have the right to enforce all rights on behalf of the State of Tennessee under this Agreement. The Parties do not intend to create any rights in third persons and the Parties agree that there are no third-party beneficiaries to this Agreement, other than TDEC. Except as expressly set forth herein, no person other than a Party to this Agreement and TDEC may enforce this Agreement's terms, claim the right to benefit from its provisions, or rely upon the existence of its terms or conditions for its benefit.

e. Additional Documentation. Each Party hereto covenants to execute such additional documentation as will be necessary to effectuate the intent of this Agreement.

f. Force Majeure. In case by reason of "force majeure" either Party hereto shall be rendered unable wholly or in part to carry out its obligations under this Agreement, then if such Party shall give notice and full particulars of such "force majeure" in writing to the other Party within five (5) days of the occurrence of the event or cause relied on, the obligation of the

Party giving such notice, so far as it is affected by such "force majeure," shall be suspended during the continuance of the inability then claimed, but for no longer period, and any such Party shall endeavor to remove or overcome such inability with all reasonable dispatch. The term "force majeure" as employed herein shall mean acts of God, strikes, lockouts, acts of a public enemy, orders of the United States or the State of Tennessee (excluding orders requiring action to comply with Chattanooga's NPDES permit, a sewer collection permit, or other permit related to the operation of a WCTS) or the State of Georgia or of any civil or military authority, insurrections, riots, earthquakes, fires, hurricanes, restraint of government and people, civil disturbances, or explosions. Nothing herein shall be deemed to relieve Chattanooga or WWTAs of its responsibility to operate their respective WCTS to reasonably control I/I in a storm or flood in accordance with generally accepted standards or government regulatory requirements.

g. Severability Clause. Should any phrase, clause, sentence, or paragraph of this contract be held invalid, or unconstitutional by any Court or competent jurisdiction of the State of Tennessee, the State of Georgia, or the United States of America in any manner or respect whatsoever, it shall in nowise affect any or all of the remaining provisions, all of which shall remain in full force and effect. Provided that if such invalidity or unconstitutionality shall destroy the essence or effectiveness of this Agreement and the Parties are unable to reach a new agreement which rectifies the invalidity or unconstitutionality, then the Parties shall continue the physical arrangements concerning the flow and treatment of sewage upon a quantum meruit basis, subject to applicable state laws and regulations for a reasonable period of time until other suitable arrangements can be made for the treatment and disposal of the wastewater.

h. Controlling Law and Venue. The Parties hereto agree that this Agreement will be enforced and interpreted according to the laws of the State of Tennessee. The Parties hereto further agree that any action brought to enforce this agreement shall be brought in the State or Federal Courts in the State of Tennessee.

i. Assignment. The Parties agree that the rights, liabilities, and obligations of either may be assigned to a successor governmental entity or authority, and that either Party's interest in this agreement may be used to secure financing to improve the system of that Party or to establish a sewer authority. Providing, if the assignment involves a change in operational control of the WCTS or any material part thereof, the assignee shall agree to assume the liability and duty of the assignor to perform all of the terms and conditions of this Agreement.

j. Counterparts. This Agreement may be signed in counterparts, and its validity shall not be challenged on that basis.


22. Exhibits. The following Exhibits are attached to and part of this Agreement:

- a. Exhibit 1A – East Ridge.
- b. Exhibit 1B – Hamilton County WWTAs.
- c. Exhibit 1C – Lookout Mountain.
- d. Exhibit 1D – Red Bank.
- e. Exhibit 1E – Soddy Daisy.


f. Exhibit 1F – Lee Highway.

IN WITNESS WHEREOF, the Parties hereto acting by and through their duly authorized officers, pursuant to the appropriate resolutions hereinbefore duly and properly adopted by each, have caused this contract and Agreement to be executed.

**For the City of Chattanooga, Tennessee:**

By: William C. Payne  
(Print Name)  
Signature:   
Title: Interim Administrator  
Date: 12-11-2020


**For the Hamilton County Water and Wastewater Treatment Authority:**

By: Dick Lee  
(Print Name)  
Signature:   
Title: Board Chairman  
Date: 12/10/20

**Exhibits 1A-1F**



# Exhibit 1A - East Ridge



Sources: Esri, HERE, Garmin, FAO, NOAA, USGS, © OpenStreetMap contributors, and the GIS User Community

## Legend

- |                      |         |                  |           |                      |            |
|----------------------|---------|------------------|-----------|----------------------|------------|
| <b>Flow Monitors</b> | Billing | Billing (Former) | Temporary | <b>Pipe Segments</b> | ForceMains |
|                      | Billing |                  | Permanent | Collector            |            |
|                      |         |                  |           | Interceptor          |            |




City of Chattanooga  
 Inter-Jurisdictional Agreement  
 Exhibit 1A - East Ridge  
 Peak Factor - 3.0  
 Max. Instantaneous Flow - 5.7 MGD  
 (East\_Ridge\_M158P601+East\_Ridge\_ER02  
 +East\_Ridge\_ER03)



Date Saved: 7/28/2020

**Exhibit 1B - Hamilton County WWTA**




**Legend**

- |                      |         |                  |           |                      |            |
|----------------------|---------|------------------|-----------|----------------------|------------|
| <b>Flow Monitors</b> | Billing | Billing (Former) | Temporary | <b>Pipe Segments</b> | ForceMains |
|                      | Billing |                  | Permanent | Collector            | VAAP PS    |
|                      |         |                  |           | Interceptor          |            |




**City of Chattanooga**  
**Inter-Jurisdictional Agreement**  
**Exhibit 1B - Hamilton County WWTA**  
**Peak Factor - 3.0**  
**Max. Instantaneous Flow - 6.6 MGD**  
**(Ramsgate+ Hurricane Creek +VAAP PS)**



**Scale:** 0 3,000 6,000 12,000 Feet

Date Saved: 7/29/2020

# Exhibit 1C - Lookout Mountain



Sources: Esri, HERE, Garmin, FAO, NOAA, USGS, © OpenStreetMap contributors, and the GIS User Community

## Legend

- |                      |                  |                  |                      |                   |
|----------------------|------------------|------------------|----------------------|-------------------|
| <b>Flow Monitors</b> | <b>Billing</b>   | <b>Temporary</b> | <b>Pipe Segments</b> | <b>ForceMains</b> |
| Billing              | Billing (Former) | Temporary        | Collector            | Lookout Mtn PS    |
|                      |                  | Permanent        | Interceptor          |                   |




City of Chattanooga  
 Inter-Jurisdictional Agreement  
 Exhibit 1C - Lookout Mountain  
 Peak Factor - 3.0  
 Max. Instantaneous Flow - 1.0 MGD  
 (Lookout\_Mtn\_01+ Lookout\_Mtn\_02 +Lookout Mtn PS)



0 5001,000 2,000 Feet

Date Saved: 7/29/2020

Exhibit 1D - Red Bank



Sources: Esri, HERE, Garmin, FAO, NOAA, USGS, © OpenStreetMap contributors, and the GIS User Community

**Legend**

- |                      |                  |           |                      |             |
|----------------------|------------------|-----------|----------------------|-------------|
| <b>Flow Monitors</b> | Billing          | Temporary | <b>Pipe Segments</b> | ForceMains  |
|                      | Billing (Former) | Permanent | Collector            | Interceptor |




City of Chattanooga  
 Inter-Jurisdictional Agreement  
 Exhibit 1D - Red Bank  
 Peak Factor - 3.0  
 Max. Instantaneous Flow - 3.0 MGD  
 (Red Bank)



Date Saved: 7/29/2020

# Exhibit 1E - Soddy Daisy



Sources: Esri, HERE, Garmin, FAO, NOAA, USGS, © OpenStreetMap contributors, and the GIS User Community

## Legend

### Flow Monitors



Billing  
(Former)



Temporary



Permanent

### Pipe Segments

Collector

Interceptor

ForceMains



City of Chattanooga  
Inter-Jurisdictional Agreement


Exhibit 1E - Soddy Daisy  
Peak Factor - 3.0  
Max. Instantaneous Flow - 2.1 MGD  
(M082P008-M082P006)



0 387.5 775 1,550 Feet

Date Saved: 7/29/2020

# Exhibit 1F - Lee Highway



Sources: Esri, HERE, Garmin, FAO, NOAA, USGS, © OpenStreetMap contributors, and the GIS User Community

### Legend

- |                      |                  |             |                      |           |
|----------------------|------------------|-------------|----------------------|-----------|
| <b>Flow Monitors</b> | Permanent        | Temporary   | <b>Pipe Segments</b> | ForceMain |
| Billing              | Billing (Former) | Interceptor | Collector            |           |



City of Chattanooga  
 Inter-Jurisdictional Agreement  
 Exhibit 1F - Lee Highway  
 Peak Factor - 3.0  
 Max. Instantaneous Flow - 3.3 MGD  
 (LeeHwy)



Date Saved: 10/21/2020 12:35 PM

IN THE UNITED STATES DISTRICT COURT  
FOR THE EASTERN DISTRICT OF TENNESSEE  
(Southern Division)

UNITED STATES OF AMERICA and, )  
the STATE OF TENNESSEE, *ex. rel.* )  
ROBERT E. COOPER, in his representative )  
capacity as the Attorney General and )  
Reporter of Tennessee, )  
Plaintiffs, )

v. )

THE CITY OF CHATTANOOGA, )  
Defendant. )

Case: No. 1:12-cv-00245 Collier/Lee

CONSENT DECREE

---

TENNESSEE CLEAN WATER )  
NETWORK, )  
Plaintiff, )

v. )

CITY OF CHATTANOOGA, )  
Defendant. )

) Consolidated with

) Case No. 1:10-CV-281  
) Collier/Lee

TABLE OF CONTENTS

**I. JURISDICTION AND VENUE . . . . . 7**

**II. APPLICABILITY . . . . . 8**

**III. OBJECTIVES . . . . . 9**

**IV. DEFINITIONS. . . . . 10**

**V. REVIEW OF DELIVERABLES/CERTIFICATION OF DELIVERABLES . . . 18**

**VI. COMPLIANCE REQUIREMENTS . . . . . 23**

**VII. CIVIL PENALTY. . . . . 64**

**VIII. SUPPLEMENTAL ENVIRONMENTAL PROJECT. . . . . 65**

**IX. REPORTING REQUIREMENTS. . . . . 68**

**X. STIPULATED PENALTIES. . . . . 72**

**XI. FORCE MAJEURE. . . . . 78**

**XII. DISPUTE RESOLUTION. . . . . 81**

**XIII. RIGHT OF ENTRY AND INFORMATION COLLECTION  
AND RETENTION . . . . . 83**

**XIV. EFFECT OF SETTLEMENT/RESERVATION OF RIGHTS. . . . . 85**

**XV. COSTS. . . . . 87**

**XVI. NOTICES. . . . . 88**

**XVII. EFFECTIVE DATE. . . . . 90**

**XVIII. RETENTION OF JURISDICTION. . . . . 90**

**XIX. MODIFICATION. . . . . 91**



**XX. TERMINATION.....91**

**XXI. PUBLIC PARTICIPATION..... 92**

**XXII. SIGNATORIES/SERVICE..... 93**

**XXIII. INTEGRATION..... 93**

**XXIV. FINAL JUDGMENT.....94**

**XXV. APPENDICES..... 94**

WHEREAS, Plaintiff, the United States of America (“United States”), by the authority of the Attorney General of the United States and through its undersigned counsel, acting at the request and on behalf of the United States Environmental Protection Agency (“EPA”), filed a Complaint (the “Complaint”) concurrently with the lodging of this Consent Decree alleging that Defendant, the City of Chattanooga, Tennessee (“Chattanooga”), has violated and will continue to violate Section 301 of the Clean Water Act, 33 U.S.C. § 1311 (“CWA”), and terms and conditions of its National Pollutant Discharge Elimination System (“NPDES”) permit issued under Section 402 of the CWA, 33 U.S.C. § 1342;

WHEREAS, Plaintiff, the State of Tennessee (“State”), acting at the request of the Tennessee Department of Environment and Conservation (“TDEC”), joined in the Complaint and seeks injunctive relief and civil penalties for Chattanooga’s alleged violations of the Tennessee Water Quality Control Act (“TWQCA”), Tenn. Code Ann. §§ 69-3-101 *et seq.*, and the regulations promulgated pursuant thereto;

WHEREAS, TDEC has been authorized by EPA to administer the NPDES program pursuant to Section 402(b) of the CWA, 33 U.S.C. § 1342(b);

WHEREAS, the State is also a plaintiff in this action and is joined as a party under Section 309(e) of the CWA, 33 U.S.C. § 1319(e), which requires the state in which a municipality is located to be joined as a party whenever the municipality is a party to a civil action brought by the United States under Section 309 of the CWA;

WHEREAS, on October 13, 2010, Plaintiff, the Tennessee Clean Water Network (“TCWN”), filed a complaint against Chattanooga, Civil Action No. 1:10-CV-281 Collier/Lee (USDC E.D. TN), alleging CWA violations, including unauthorized discharges from the West Bank and East Bank Outfalls, sanitary sewer overflows (“SSO”), combined sewer overflows (“CSOs”) during dry weather, exceedances of E. coli limits in the discharge from the Moccasin Bend Wastewater Treatment Plant, and failure to properly measure and report the volume of SSOs (the “TCWN Complaint”);

WHEREAS, Chattanooga disputes the allegations set forth in the TCWN Complaint;

WHEREAS, by Agreed Order entered January 20, 2011, the lawsuit between the TCWN and Chattanooga was stayed for a period of one hundred eighty (180) days;

WHEREAS, by an Agreed Order entered September 12, 2011, the lawsuit between the TCWN and Chattanooga was stayed for an additional period of one hundred eighty (180) days;

WHEREAS, by an Agreed Order entered January 18, 2012, the lawsuit between the TCWN and Chattanooga was stayed for an additional period of one hundred eighty (180) days;

WHEREAS, by stipulation filed by the Parties as of the date of the filing of this Consent Decree, the Parties requested that the United States’ and the State’s Complaint be consolidated with the TCWN Complaint;

WHEREAS, Chattanooga is a “municipality” pursuant to Section 502 of the CWA, 33 U.S.C. § 1362;

WHEREAS, Chattanooga owns and operates municipal wastewater collection, retention and transmission systems (“WCTS”) that consists of a separate sanitary sewer system (“SSS”) and a combined sewer system (“CSS”) and that are designed to collect and convey municipal sewage (domestic, commercial and industrial) to its Moccasin Bend Wastewater Treatment Plant (the “WWTP”) and to its eight (8) permitted CSO outfalls pursuant to NPDES Permit Number TN0024210 (the “NPDES Permit”) issued to Chattanooga by TDEC;

WHEREAS, Chattanooga has reported to EPA and TDEC numerous SSOs of sewage from its WCTS since October 13, 2005, including a number of SSOs from unpermitted outfalls known as the East Bank Outfall and West Bank Outfall;

WHEREAS, Chattanooga has reported to EPA and TDEC that it had discharges of sewage during dry weather from its permitted CSO outfalls on a number of occasions since October 13, 2005;

WHEREAS, Chattanooga has reported that it discharged wastewater from its permitted CSO outfalls without receiving full primary treatment on several occasions since October 13, 2005;

WHEREAS, Chattanooga has reported to EPA and TDEC that it has failed to consistently monitor for all parameters specified in its NPDES Permit and has reported a number of exceedances of the effluent limitations in the NPDES Permit since October 13, 2005;

WHEREAS, the United States, the State, and the TCWN contend that these SSOs, dry weather and untreated discharges from the CSO outfalls, failures to consistently monitor water

quality, and effluent limit exceedances are violations of the CWA, the TWQCA, and the NPDES Permit;

WHEREAS, Plaintiffs contend that Chattanooga must provide an updated Long Term Control Plan to ensure that its CSO discharges and its WWTP discharges fully comply with EPA's 1994 *Combined Sewer Overflow (CSO) Control Policy*, 59 Fed. Reg. 18688 (the "CSO Control Policy");

WHEREAS, this Consent Decree requires Chattanooga to develop, submit, finalize, and implement plans for the continued improvement of its WCTS and WWTP to eliminate SSOs, to eliminate dry weather and untreated CSOs, to establish consistent water quality monitoring, to correct effluent limit violations, and to ensure compliance with the CSO Control Policy;

WHEREAS, the Parties to this Consent Decree have negotiated in good faith and have reached a settlement of the issues raised in the Complaint and the TCWN Complaint;

WHEREAS, Chattanooga's agreement to this Consent Decree is not an admission of liability and, except for Chattanooga's consent to jurisdiction and venue as provided in Section I of this Consent Decree, this Consent Decree is not an adjudication or admission of any fact or law;

WHEREAS, the Parties recognize, and the Court by entering this Consent Decree finds, that this Consent Decree has been negotiated by the Parties in good faith and will avoid litigation between the Parties and that this Consent Decree is fair, reasonable, and in the public interest;

NOW THEREFORE, with the consent of the Parties, it is hereby ORDERED, ADJUDGED and DECREED as follows:

### **I. JURISDICTION AND VENUE**

1. This Court has jurisdiction over the subject matter of this action, pursuant to 28 U.S.C. §§ 1331, 1345, and 1355, and Sections 309(b) and 505 of the CWA, 33 U.S.C. §§ 1319(b) and 1365, and over the Parties. This Court has supplemental jurisdiction over the state law claims asserted by the State pursuant to 28 U.S.C. § 1367. Venue is proper in the Eastern District of Tennessee pursuant to Section 309(b) of the CWA, 33 U.S.C. § 1319(b), and 28 U.S.C. §§ 1391(b) and 1395(a), because the violations alleged in the Complaint and the TCWN Complaint are alleged to have occurred in this judicial district. For purposes of this Consent Decree, or any action to enforce this Consent Decree, Chattanooga consents to the Court's jurisdiction over this Consent Decree and any such action and over Chattanooga and consents to venue in this judicial district.

2. For purposes of this Consent Decree, Chattanooga agrees that the Complaint states claims upon which relief may be granted pursuant to Section 309(b) of the CWA, 33 U.S.C. § 1319(b), and the TWQCA, Tenn. Code Ann. §§ 69-3-101 *et seq.* For purposes of this Consent Decree, Chattanooga agrees that the TCWN Complaint states claims upon which relief may be granted pursuant to Section 309(b) and 505(a)(1) of the CWA, 33 U.S.C. §§ 1319(b) & 1365(a)(1).

## **II. APPLICABILITY**

3. The obligations of this Consent Decree apply to and are binding upon the United States, the State, the TCWN, and upon Chattanooga and any successors, assigns, or other entities or persons otherwise bound by law.

4. No transfer of ownership or operation of the Sewer System, whether in compliance with the procedures of this Paragraph or otherwise, shall relieve Chattanooga of its

obligation to ensure that the terms of this Consent Decree are implemented with respect to any of the other remaining portions of the Sewer System that are owned or operated by Chattanooga. Within twenty-one (21) Days prior to such transfer, Chattanooga shall provide a copy of this Consent Decree to the proposed transferee and shall simultaneously provide written notice of the prospective transfer, together with a copy of the proposed written agreement, to the United States and TDEC in accordance with Section XVI of this Consent Decree (Notices). Chattanooga shall require, as a condition of any sale or transfer, that the purchaser or transferee agrees in writing to be bound by this Consent Decree and submit to the jurisdiction of the Court for its enforcement. Provided, however, that Chattanooga may transfer within any twelve (12) Month period, an ownership interest, operation, management, or other control of portions of the WCTS of up to one hundred (100) residential customer accounts, or the volumetric equivalent thereof, without this Paragraph applying to the successor and/or assigns who takes ownership or control of such portions of the WCTS from Chattanooga. Any attempt to transfer ownership or operation of the Sewer System without complying with this Paragraph constitutes a violation of this Consent Decree.

5. Within thirty (30) Days after the Effective Date of the Consent Decree, Chattanooga shall provide a copy of this Consent Decree to all officers, employees, and agents whose duties might reasonably include compliance with any substantive provision of this Consent Decree, as well as to any contractor retained to perform work required under this Consent Decree.

6. In any action to enforce this Consent Decree, Chattanooga shall not raise as a defense the failure by any of its officers, directors, employees, agents, or contractors to take any actions necessary to comply with the provisions of this Consent Decree.

### **III. OBJECTIVES**

7. All plans, measures, reports, construction, maintenance, operational requirements, and other obligations in this Consent Decree or resulting from the activities required by this Consent Decree shall have the objective of causing Chattanooga to achieve and maintain full compliance with the CWA, the TWQCA, the CSO Control Policy and the NPDES Permit, including the goal of eliminating all SSOs.

### **IV. DEFINITIONS**

8. Terms used in this Consent Decree that are defined in the CWA or in regulations promulgated pursuant to the CWA shall have the meanings assigned to them in the CWA, 33 U.S.C. §§ 1251 *et seq.*, and regulations promulgated under the CWA, unless otherwise provided in this Consent Decree. Whenever the terms set forth below are used in this Consent Decree, the following definitions shall apply:

(a). “Building Backup” shall mean a wastewater release or backup into a building that is caused by blockages, flow conditions, or other malfunctions in Chattanooga’s WCTS. A wastewater backup or release that is caused by blockages, flow conditions, or other malfunctions of a Private Lateral is not a Building Backup.

(b). “Bypass” shall have the meaning set forth at 40 C.F.R. § 122.41(m).

(c). “Calendar Quarter” shall mean the three (3) month periods ending on March 31, June 30, September 30, and December 31.

(d). “Calendar Year” shall mean the twelve (12) month period starting on January 1 and ending on December 31.

(e). “Certification” or “Certify” when used in this Consent Decree shall require Chattanooga to comply with Paragraph 17 of this Consent Decree.

(f). “Chattanooga” shall mean the City of Chattanooga, Tennessee, including all of its departments, agencies, instrumentalities such as the Public Works Department, and any successor thereto.

(g). “CMOM” or “Capacity, Management, Operations, and Maintenance” shall mean a flexible program of accepted industry practices to properly manage, operate and maintain sanitary wastewater collection, transmission and treatment systems, investigate capacity-constrained areas of these systems, and respond to SSO events.

(h). “Combined Sewer Overflow” or “CSO” shall mean any discharge from the CSS from any outfall currently identified, or identified in the future, as a permitted combined sewer overflow outfall in any Chattanooga NPDES permit.

(i). “Combined Sewer Overflow Outfall” or “CSO Outfall” shall mean the outfalls currently identified, or identified in the future, as a permitted combined sewer overflow outfall in any Chattanooga NPDES permit from which CSOs are discharged to waters of the United States or the State.

(j). “Combined Sewer System” or “CSS” shall mean the portion of Chattanooga’s WCTS designed to convey municipal sewage (domestic, commercial and



industrial wastewaters) and stormwater runoff through a single-pipe system to Chattanooga's WWTP or CSO Outfalls.

(k). "Complaint" shall mean the complaint filed by the United States and the State in this action.

(l). "Consent Decree" shall mean this Consent Decree and all appendices attached hereto (listed in Section XXV). In the event of a conflict between this document and any appendix, this document shall control.

(m). "CWA" shall mean the Clean Water Act, as amended, 33 U.S.C. §§ 1251, *et seq.*

(n). "Date of Entry" shall mean the date on which this Consent Decree is entered by the United States District Court for the Eastern District of Tennessee.

(o). "Date of Lodging" shall mean the date this Consent Decree is filed for lodging with the Clerk of the Court for the United States District Court for the Eastern District of Tennessee.

(p). "Day" shall mean a calendar day unless expressly stated to be a business day. In computing any period of time under this Consent Decree, where the last day would fall on a Saturday, Sunday, or federal holiday, the period shall run until the close of business of the next business day.

(q). "Defendant" shall mean the City of Chattanooga, Tennessee including all of its departments, agencies, instrumentalities such as the Public Works Department, and any successor thereto.

(r). “Deliverable” shall mean any written document required to be prepared and/or submitted by or on behalf of Chattanooga pursuant to this Consent Decree.

(s). “Discharge Monitoring Report” or “DMR” is defined as the monitoring report which Chattanooga submits to TDEC on a monthly basis pursuant to its NPDES Permit.

(t). “DOJ” shall mean the United States Department of Justice and any of its successor departments or agencies.

(u). “EPA” shall mean the United States Environmental Protection Agency and any of its successor departments or agencies.

(v). “Effective Date” shall have the definition provided in Section XVII (Effective Date).

(w). “Excessive Inflow / Infiltration” or “Excessive I/I” shall have the meaning provided in 40 C.F.R. § 35.2005(b)(16).

(x). “Force Main” shall mean any pipe that receives and conveys, under pressure, wastewater from the discharge side of a Pump Station. A Force Main is intended to convey wastewater under pressure.

(y). “Gravity Sewer Line” or “Gravity Sewer” shall mean a pipe that receives, contains and conveys wastewater not normally under pressure, but is intended to flow unassisted under the influence of gravity.

(z). “Infiltration” as defined by 40 C.F.R. § 35.2005(b)(20) shall mean water other than wastewater that enters the WCTS (including sewer service connections and foundation drains) from the ground through such means as defective pipes, pipe joints, connections, or manholes.

(aa). “Inflow” as defined by 40 C.F.R. § 35.2005(b)(21) shall mean water other than wastewater that enters the WCTS (including sewer service connections) from sources such as, but not limited to, roof leaders, cellar drains, yard drains, area drains, drains from springs and swampy areas, manhole covers, cross connections between storm sewers and sanitary sewers, catch basins, cooling towers, storm water, surface runoff, street wash waters, or drainage.

(bb). “I/I” shall mean the total quantity of water from inflow, infiltration, and rainfall induced inflow and infiltration without distinguishing the source.

(cc). “Major Gravity Line” shall mean any of the following:

i. All Gravity Sewer Lines that are twelve (12) inches in diameter or larger;

ii. All Gravity Sewer Lines that convey wastewater from one pumping station service area to another pumping station service area; and

iii. All Gravity Sewer Lines that have caused or contributed to, or that Chattanooga knows will likely cause or contribute to, a capacity-related SSO.

(dd). “Month” shall mean shall mean one calendar month running from the numbered day to the same numbered day of the following calendar month, regardless of whether the particular month has 28, 29, 30 or 31 days. In the case where a triggered event would occur on a day of the month which does not exist (for example, on February 30), then the event shall be due on the first (1<sup>st</sup>) day of the following month (for example, March 1).

(ee). “NPDES” shall mean the National Pollutant Discharge Elimination System authorized under Section 402 of the CWA, 33 U.S.C. § 1342.

(ff). “NPDES Permit” shall mean NPDES permit No. TN0024210 issued to Chattanooga pursuant to Section 402 of the Clean Water Act, 33 U.S.C. § 1342, for the Moccasin Bend WWTP, and any future extended, modified, or reissued permits.

(gg). “Paragraph” shall mean a portion of this Consent Decree identified by an Arabic numeral.

(hh). “Parties” shall mean the United States of America on behalf of EPA, the State on behalf of TDEC, the TCWN, and Chattanooga.

(ii). “Plaintiffs” shall mean the United States of America on behalf of EPA, the State of Tennessee on behalf of TDEC, and the TCWN.

(jj). “Private Lateral” shall mean that portion of a sanitary sewer conveyance pipe that extends from the wastewater main to the single-family, multi-family, apartment, or other dwelling unit or commercial or industrial structure to which wastewater service is or has been provided.

(kk). “Prohibited Bypass” shall mean the intentional diversion of waste streams from any portion of a treatment facility which is prohibited pursuant to the terms set forth at 40 C.F.R. § 122.41(m).

(ll). “Public Document Repository” or “PDR” shall mean the Downtown Branch of the Chattanooga City Library, located at 1001 Broad Street, Chattanooga, TN 37402, and such repository that Chattanooga shall make available via the internet, including through its website, [www.chattanooga.gov](http://www.chattanooga.gov).

(mm). “Pump Station” shall mean facilities owned or operated by Chattanooga that are comprised of pumps which lift wastewater to a higher hydraulic elevation, including all

related electrical, mechanical, and structural systems necessary to the operation of that pump station; provided, however, this definition shall not include any residential grinder pumps.

(nn). “Sanitary Sewer Overflow” or “SSO” shall mean any discharge of wastewater to waters of the United States or the State from Chattanooga’s Sewer System through a point source not permitted in any NPDES permit, as well as any overflow, spill, or release of wastewater to public or private property from the Sewer System that may not have reached waters of the United States or the State, including all Building Backups.

(oo). “Sanitary Sewer System” or “SSS” shall mean the portion of Chattanooga’s WCTS designed to convey only municipal sewage (domestic, commercial and industrial wastewaters) to Chattanooga’s WWTP.

(pp). “Secondary Treatment” shall mean a biological wastewater treatment technology required by the CWA for discharges from Publicly Owned Treatment Works, as that term is defined at 40 C.F.R. § 403.3(q). The minimum level of effluent quality attainable through the application of secondary treatment is established in 40 C.F.R. § 133.102 in terms of the parameters for 5-day biochemical oxygen demand (“BOD<sub>5</sub>”) concentration and percent removal, total suspended solids (“TSS”) concentration and percent removal, and pH.

(qq). “Section” shall mean a portion of this Consent Decree identified by a Roman numeral.

(rr). “Sewershed” shall mean all portions of Chattanooga’s WCTS that are a tributary to a trunk sewer entering the WWTP. Each Sewershed is hydraulically linked and independent of other Sewersheds, unless otherwise noted. A map of Chattanooga’s Sewersheds is attached hereto as Appendix A.

(ss). “Sewer System” shall mean the WCTS and the WWTP.

(tt). “State” shall mean the State of Tennessee including all of its departments, agencies, and instrumentalities, and any successor departments, agencies, and instrumentalities.

(uu). “Subparagraph” shall mean a portion of a paragraph identified by lowercase letters.

(vv). “TCWN” shall mean the Tennessee Clean Water Network.

(ww). “TCWN Complaint” shall mean the complaint filed by the TCWN against the City of Chattanooga on October 13, 2010, Civil No. 1:10-CV-281 Collier/Lee (USDC E.D. TN).

(xx). “TDEC” shall mean the Tennessee Department of Environment and Conservation and any successor departments or agencies of the State, and any successor departments or agencies.

(yy). “Timely” when applied to the submittal of a Deliverable shall mean submitted no later than the deadline established in this Consent Decree (or in a document approved pursuant to this Consent Decree) and containing all of the elements pertaining to the submittal as set forth in this Consent Decree (or in a document approved pursuant to this Consent Decree). “Timely,” when applied to the implementation of any Work shall mean implemented no later than the deadline established in this Consent Decree (or in a document approved pursuant to this Consent Decree) and in accordance with the elements pertaining to such Work as set forth in this Consent Decree (or in a document approved pursuant to this Consent Decree).

(zz). “TWQCA” shall mean the Tennessee Water Quality Control Act, Tenn. Code Ann. §§ 69-3-101, *et seq.*

(aaa). “United States” shall mean the United States of America, acting on behalf of EPA, including its departments, agencies, and instrumentalities, and any successor departments, agencies, and instrumentalities.

(bbb). “Wastewater Collection and Transmission System” or “WCTS” shall mean the wastewater collection, retention, and transmission systems, including all pipes, Force Mains, Gravity Sewer Lines, lift stations, Pump Stations, manholes and appurtenances thereto, owned or operated by Chattanooga that are designed to collect and convey municipal sewage (domestic, commercial and industrial) to Chattanooga’s WWTP or CSOs. The WCTS is comprised of the SSS and CSS.

(ccc). “Wastewater Treatment Plant” or “WWTP” shall mean devices or systems used in the storage, treatment, recycling, and reclamation of municipal wastewater at the Moccasin Bend WWTP located at 455 Moccasin Bend Road, Chattanooga, TN 37405-4403.

(ddd). “Work” shall mean all activities Chattanooga is required to perform under this Consent Decree.

## **V. REVIEW, APPROVAL AND IMPLEMENTATION OF DELIVERABLES**

### **9. Public Document Repository.**

(a) Except as otherwise set forth in Paragraphs 9-10, prior to the submission of a Deliverable to EPA and TDEC pursuant to Section VI and VIII of this Consent Decree, Chattanooga shall provide notice of a draft Deliverable in the PDR for review and comment by the public by taking the following steps:

(i). Notify the Reference Librarian at the downtown branch of the Chattanooga-Hamilton County Public Library (located at 1001 Broad Street in downtown

Chattanooga) identifying the Deliverable to be submitted and provide the Reference Librarian with a copy of the draft deliverable and a one-page instruction form containing a brief synopsis of the Deliverable.

(ii). Post a copy of the Deliverable and the instruction form containing a brief synopsis of the Deliverable on Chattanooga's website.

(iii). Allow the public a period of thirty (30) Days to inspect and comment to Chattanooga on the Deliverable, either at the library or through Chattanooga's website ("Public Review Requirement").

(b). Following the end of the Public Review Requirement, Chattanooga shall consider any public comments received for a period of up to fifteen (15) Days ("Public Comment Review Period"). Following the end of the Public Comment Review Period, Chattanooga shall submit the Deliverable to EPA and TDEC and provide notice to TCWN. Within seven (7) Days after its submission to EPA and TDEC, Chattanooga shall place a copy of the submitted version of the Deliverable in the PDR. Within seven (7) Days after EPA's approval, approval upon conditions, or modification by EPA pursuant to this Section, if revised, Chattanooga shall place a copy of such version of the Deliverable in the PDR. All of the documents referenced above shall remain in the PDR along with all comments until termination of this Consent Decree. However, if Chattanooga resubmits a Deliverable to EPA in response to EPA comments pursuant to Paragraph 12, such resubmission is not subject to the thirty (30) Day public comment period nor is Chattanooga required to obtain public comment on the resubmission.



10. EPA Action on Deliverables. After review of any Deliverable that is required to be submitted pursuant to this Consent Decree, EPA, after consultation with TDEC, shall in writing:

- (a). Approve the submission;
- (b). Approve part of the submission and disapprove the remainder; or
- (c). Disapprove the submission.

11. Approved Deliverables. If a Deliverable is approved by EPA pursuant to Subparagraph 10.(a)., Chattanooga shall take all actions required by the Deliverable in accordance with the schedules and requirements of the Deliverable as approved. If the Deliverable is approved only in part pursuant to Subparagraph 10.(b)., Chattanooga shall, upon written direction from EPA, after consultation with TDEC, take all actions required by the approved plan, report, or other item that EPA, after consultation with TDEC, determines are technically severable from any disapproved portions, subject to Chattanooga's right to dispute only the specified conditions or the disapproved portions under Section XII of this Consent Decree (Dispute Resolution). Following EPA approval of any Deliverable or portion thereof, such Deliverable or portion thereof so approved shall be incorporated into and become enforceable under this Consent Decree.

12. Disapproved Deliverables. If the Deliverable is disapproved in whole or in part pursuant to Subparagraph 10.(b). or (c)., subject to Chattanooga's right to dispute only the specified conditions or the disapproved portions under Section XII of this Consent Decree (Dispute Resolution), Chattanooga shall, within thirty (30) Days or such other time as EPA and Chattanooga agree to in writing, correct all deficiencies and resubmit to EPA the Deliverable, or

disapproved portion thereof, for approval, in accordance with Paragraphs 10 and 11. If the resubmission is approved in whole or in part, Chattanooga shall proceed in accordance with Paragraph 11.

13. Stipulated Penalties Accruing. Subject to Chattanooga's right to dispute only the specified conditions or the disapproved portions under Section XII of this Consent Decree (Dispute Resolution), any stipulated penalties applicable to the original Deliverable, as provided in Section X of this Consent Decree, shall accrue during the thirty (30)-Day period or other specified period, but shall not be payable unless the resubmitted Deliverable is untimely or is disapproved in whole or in part; provided that, if the original submission was so deficient as to constitute a material breach of Chattanooga's obligations under this Consent Decree, the stipulated penalties applicable to the original submission shall be due and payable notwithstanding any subsequent resubmission.

14. Resubmitted Deliverable. If a resubmitted Deliverable, or portion thereof, is disapproved in whole or in part, EPA, after consultation with TDEC, may again require Chattanooga to correct any deficiencies, in accordance with Paragraph 12, or may itself correct any deficiencies, subject to Chattanooga's right to invoke Dispute Resolution under Section XII of this Consent Decree and the right of EPA to seek stipulated penalties as provided in preceding Paragraph 13. Upon EPA's correction of any deficiencies, such resubmitted plan, report, or other item, or portion thereof will be incorporated into and become enforceable under this Consent Decree and shall be implemented by Chattanooga according to the approved schedule subject to Chattanooga's right to invoke Dispute Resolution.

15. Timing of Review of Deliverables. EPA and TDEC agree to use best efforts to expeditiously review and comment on Deliverables. If EPA issues written comments and decisions on a Deliverable required in Paragraphs 21, 23 or 24 more than one-hundred twenty (120) Days after receipt of such submission, or on any other Deliverable more than sixty (60) Days after receipt of such submission, any subsequent deadline or milestone that is dependent upon such comments or decisions shall be extended. The length of the extension shall be determined by calculating the number of Days between EPA's receipt of the submission and the date of EPA's written response, less one-hundred twenty (120) Days (in case of a Deliverable required in Paragraphs 21, 23 or 24) or less sixty (60) Days (in case of any other Deliverable). Within thirty (30) Days of the date that Chattanooga knows or should know of a deadline or milestone that Chattanooga believes is extended under this Paragraph, Chattanooga shall inform EPA, in writing, of its belief and the amount of time Chattanooga believes the deadlines or milestones are extended. If EPA disagrees with Chattanooga's determination that a deadline is dependent upon such comments or decisions, EPA shall inform Chattanooga in writing. Chattanooga may dispute EPA's conclusion regarding whether a deadline is dependent upon such comments or decisions pursuant to Section XII (Dispute Resolution).

16. Revisions to Deliverables. The Parties recognize that Chattanooga may need or want to revise certain Deliverables during the term of this Consent Decree. Such revisions shall not be considered modifications to the Consent Decree for purposes of Section XXI (Modification). Chattanooga must obtain EPA's prior written approval of any revision to the substance of a Deliverable and shall place copies of any such revised Deliverable in the PDR in accordance with the provisions of Paragraph 9. Chattanooga may revise the form of any

Deliverable without consulting EPA and shall place a copy of any such revised Deliverable in the PDR within seven (7) Days after making such revision.

17. Certification. In all Deliverables, notices, documents, or reports required to be submitted to the United States and State pursuant to this Consent Decree, Chattanooga shall, pursuant to 40 C.F.R. § 122.22, sign and certify such notices, documents, and reports as follows:

*I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering such information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.*

## **VI. COMPLIANCE REQUIREMENTS**

18. Obligation to Perform Work. Upon the Date of Entry, Chattanooga shall implement the Work pursuant to this Consent Decree. All Work shall be performed using sound engineering practices, which may include appropriate provisions of the *Handbook: Sewer System Infrastructure Analysis and Rehabilitation*, EPA/625/6-91/030, 1991; *Existing Sewer Evaluation and Rehabilitation*, WEF MOP FD-6, 1994; and the *Tennessee Design Criteria for Sewage Works* in accordance with Tenn. Comp. R. & Regs., ch. 1200-4-2-.03.

19. Community Input. Pursuant to Section 31-57(a) of the Chattanooga City Code, the City has established a seven (7)-member Wastewater Regulations and Appeals Board (the "Board"), consisting of the following: one (1) environmental engineer or environmental scientist; one (1) attorney; one (1) person employed or retired from an industrial or commercial establishment regulated by this article; one (1) person that is experienced in the science or practice of finance; one (1) member of the Board that is nominated by a regional user located in the State of Georgia, subject to approval by the mayor and confirmation by the city council of Chattanooga; one (1) Board member that is nominated by a regional user in the State of Tennessee, subject to approval by the mayor and confirmation by the city council of Chattanooga; and one (1) person that has no other qualification other than being an adult citizen of the area served by the regional system. Pursuant to Section 31-57(c)(9) of the Chattanooga City Code, the Board shall hold an annual meeting. Pursuant to the Consent Decree, Chattanooga shall review with the Board at its annual meeting the requirements under the Consent Decree and the annual budget for meeting those requirements. Within seven (7) Months after the Effective Date of the Consent Decree, Chattanooga shall also develop a Community Input Program for Chattanooga to provide education to the public and solicit input from the public on the implementation of the Consent Decree, which it shall present to the Board for its review and approval. Chattanooga agrees that if the Chattanooga City Code is modified such that the Board is modified or eliminated, that it will provide notice to EPA and, if the Board is eliminated, it will submit to EPA for review and approval within seven (7) Months after Board elimination a mechanism to replace the functions of the Board identified herein. Such revisions

shall not be considered material modifications to the Consent Decree for purposes of Section XIX (Modification).

20. Capacity, Management, Operation and Maintenance (“CMOM”) Programs.

Chattanooga shall develop and implement the CMOM programs as provided below. All CMOM programs shall be developed in accordance with EPA Region IV guidance, as set forth in the CDROM disk attached hereto as Appendix B. Chattanooga shall ensure that each CMOM program has a written, defined purpose; a written, defined goal; is documented in writing with specific detail; is implemented by appropriately trained personnel; has established performance measures; and has written procedures for periodic review. The Parties recognize that Chattanooga may need or want to revise the CMOM Programs set forth below during the term of this Consent Decree. Such revisions shall not be considered material modifications to the Consent Decree for purposes of Section XIX (Modification). However, Chattanooga must obtain EPA's written approval of any revision to the substance of any CMOM Program required by this Consent Decree and shall comply with the provisions of Section V. Chattanooga may revise the form of any CMOM Program required by this Consent Decree without EPA's approval and shall provide a copy of any revised Program to EPA and TDEC, and place a copy of any such revised Program in the PDR within seven (7) Days after making such revision.

(a). Sewer Overflow Response Protocol (“SORP”). Within seven (7) Months after the Effective Date of the Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment a SORP, including a schedule for full implementation of the program, to provide for Chattanooga's timely and effective response to all SSOs. The SORP shall have the following components:

i. Staff Communication and Duties. Chattanooga shall establish procedures for ensuring that it is made aware of all SSOs as expeditiously as possible, and shall document in writing the responsibilities of employees (by position) charged with responding to SSOs.

ii. Prompt Response to SSOs. Chattanooga shall make all reasonable efforts to respond to an SSO in a timely manner after being notified of an SSO. Chattanooga shall maintain records of all SSO responses, including response times.

iii. Public Notification. Chattanooga shall establish procedures for providing appropriate notice to the public (e.g., through the local news media or other means including without limitation signs or barricades to restrict access) that may be impacted by an SSO.

iv. Assessment of Cause and Impact. Chattanooga shall establish procedures for identifying the cause of an SSO, for identifying the extent of potential threats to human health or the environment from the SSO, and for quantifying the volume and duration of the SSO. The SORP shall clearly identify the process a customer may follow to dispute a determination by Chattanooga that a wastewater backup into a building is caused by a blockage or other malfunction of a Private Lateral, and therefore is not a Building Backup.

v. Elimination of Cause and Mitigation of Impact. Chattanooga shall establish procedures for remedying the cause of an SSO. Standard repairs for typical SSO causes shall be identified, as shall the resources needed and available for such repairs. Procedures for diverting flow around blockages or line failures shall be included, as shall

procedures for minimizing human contact with overflowed sewage. Standard containment procedures for typical SSOs shall be identified.

vi. Cleanup of SSOs. Chattanooga shall establish procedures for cleaning up all SSOs completely and expediently, and for minimizing adverse impact to human health or the environment from the SSO. With respect to Building Backups, the repair and mitigation procedures shall include measures necessary to disinfect and/or remove items potentially contaminated by the Building Backup. These may include wet vacuuming or other removal of spillage, wiping floors and walls with cleaning solution and disinfectant, flushing out and disinfecting plumbing fixtures, carpet cleaning and/or replacement, and other appropriate measures to disinfect and/or remove items potentially contaminated by the Building Backup.

vii. Regulatory Reporting. Chattanooga shall provide notice to TDEC of an SSO as required by the NPDES Permit, including without limitation, within twenty-four (24) hours of the time it becomes aware of an SSO.

viii. Training. Chattanooga shall provide adequate training necessary for Chattanooga employees, contractors, and personnel of other affected agencies to effectively implement the SORP. The SORP shall provide training guidelines to ensure adequate response training is provided to management and field personnel responsible for responding to SSOs. Chattanooga shall establish procedures, and provide adequate training to response personnel, for estimating volumes from SSOs.

(b). Emergency Response Plan. Within nineteen (19) Months after the Effective Date of the Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment an Emergency Response Plan (“ERP”), including a schedule for full



implementation of the program. The ERP shall address emergencies that include situations such as floods, tornados, earthquakes or other natural events, serious chemical spills, and widespread electrical failure. The ERP shall address areas of vulnerability and determine the effect of such a failure to operations, equipment, and public safety and health based upon such factors as topography, weather, sewer system size, and other site-specific factors. The ERP shall have the following components:

i. Sewer System. The WCTS component of the ERP shall establish standard operating procedures for use in emergency operations, including identification of the actions staff should take in the event of emergency situations (specific to the type of emergency that could occur); criteria for initiating and ceasing emergency operations; identification of appropriate repair equipment and sources thereof; and instructions on how to operate equipment and systems during an emergency when they are not functioning as intended but are not fully inoperable. The WWTP component of the ERP shall also establish standard operating procedures for use in an emergency situation at the WWTP, including changes in process controls.

ii. Public Notification of Emergencies. In addition to the reporting requirements set forth in Section IX (Reporting Requirements), Chattanooga shall establish, in coordination with public health authorities: (A) criteria to be used as the basis for immediately notifying the public and other impacted entities, such as users with a downstream water intake, of an emergency situation caused by an SSO, Prohibited Bypass, or effluent limit violation; (B) a list identifying, by name, phone number and pager number, all Chattanooga staff who are responsible for notifying the public; (C) a list identifying, by name and phone number, all public

contacts, including local media outlets, who must be contacted during an emergency situation; (D) a list identifying Chattanooga staff who are authorized to make public statements during emergency situations; and (E) pre-scripted news releases for various types of emergency situations.

iii. Notification of Regulatory Authorities. In addition to the notification requirements set forth in the NPDES Permit, and the reporting requirements set forth in Section IX (Reporting Requirements), Chattanooga shall establish, in coordination with public health authorities: (A) criteria to be used as the basis for immediately notifying regulatory authorities, TDEC, and the public health authorities of any emergency situation caused by an SSO, Prohibited Bypass, or effluent limit violation; (B) a list identifying, by name, phone number and pager number, all Chattanooga staff who are responsible for notifying the regulatory authorities; and (C) a list identifying, by name and phone number, all officials who must be contacted.

(c). Fats, Oils, and Grease (“FOG”) Management Program. Chattanooga has developed and has been implementing a Fats, Oils and Grease (“FOG”) Management Program since its FOG ordinance was adopted in June 2005. Notwithstanding any improvements already achieved through its FOG Management Program, Chattanooga shall fully re-evaluate its FOG Management Program to determine if its effectiveness can be improved. No later than thirteen (13) Months from the Effective Date of this Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment its FOG Management Program, including a schedule for full implementation of the program, and the results of its re-evaluation and any proposal to expand or modify its existing FOG Management Program to control further the entry of FOG into

Chattanooga's Sewer System. The FOG Management Program shall include, but not be limited to:

- i. Establishment of a public education program directed at reducing the amount of grease entering the Sewer System from private residences.
- ii. Establishment of methods to identify persistent sources of FOG causing problems in the WCTS and the best method or mechanism for addressing those sources.
- iii. Establishment of performance indicators to be used by Chattanooga to measure the effectiveness of the FOG Management Program.

(d). Gravity Line Preventive Maintenance Program. Within thirteen (13) Months after the Effective Date of the Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment a Gravity Line Preventive Maintenance Program, including a schedule for full implementation of the program. The Gravity line Preventive Maintenance Program shall include, at a minimum, the following components:

- i. A preventive hydraulic cleaning component which shall include protocols for implementing the routine hydraulic cleaning of Gravity Sewer Lines and which may vary depending on the size of the Gravity Sewer Line. This component shall include provisions for needs determination; establishing priorities and scheduling; hydraulic cleaning equipment to be used; standard hydraulic cleaning maintenance procedures; standard forms, records and performance measures; and a method for information management.
- ii. A preventive mechanical cleaning component which shall include protocols for implementing the routine mechanical cleaning of Gravity Sewer Lines and which may vary depending on the size of the Gravity Sewer Line. This component shall include

provisions for needs determination; establishing priorities and scheduling; mechanical cleaning equipment to be used; standard mechanical cleaning maintenance procedures; standard forms, records and performance measures; and a method for information management.

iii. A root control component which shall include protocols for implementing root control for Gravity Sewer Lines and which may vary depending on the size of the Gravity Sewer Line. This component shall include provisions for needs determination; establishing priorities and scheduling; root control methods and approaches; root control maintenance procedures; standard forms, records and performance measures; and a method for information management.

iv. A manhole preventive maintenance component which shall include protocols for implementing a routine inspection and maintenance of manholes. This component shall include provisions for needs determination; establishing priorities and scheduling; inspection methods and approaches; standard maintenance procedures; standard forms, records and performance measures; and a method for information management.

v. A process for addressing Gravity Sewer Line segments with repeated SSOs and an assessment of how all components of this program (Paragraph 20.(d).i. through v.) will work together to proactively maintain the integrity of the WCTS.

(e). Pump Station Operations Program. Within nineteen (19) Months after the Effective Date of the Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment a Pump Station Operations Program, including a schedule for full implementation of the program. The Pump Station Operations Program shall include, at a minimum, the following components:

i. Routine Pump Station Operations. The Routine Pump Station Operations component shall be developed to ensure proper Pump Station operations that will necessitate prevention of Pump Station failure. This program shall include, at a minimum, the following:

(A) Procedures for reading and recording information appropriate to each Pump Station including, as applicable, pump run-time meter readings, start counters, amperage readings, checking and resetting conditions, wet-well points, grease accumulations, and any other information that is necessary for the proper operation of a Pump Station;

(B) Development of standard inspection routes and schedules; and

(C) Provisions for needs determination; establishing priorities and scheduling; standard forms, records and performance measures; and a method for information management.

ii. Emergency Pump Station Operations. The Emergency Pump Station Operations component shall be developed to necessitate emergency operations in the event of Pump Station failure. This program shall provide guidance and ensure timely response to atypical situations in the WCTS through the use of written standard emergency operating procedures for each type of Pump Station and shall include, at a minimum, the following:

(A) Emergency contact information;

(B) Location(s) of auxiliary power including portable or fixed emergency generators applicable to each Pump Station;

(C) Location(s) of portable pumping equipment;

(D) Guidance for initiating auxiliary power with portable or fixed generators;

(E) Guidance for installing portable pumps during high flow;

(F) Applicable contingency plans;

(G) Standard forms, records, and performance measures and a method for information management; and

(H) A description of each Pump Station monitoring system.

(f). Pump Station Preventive Maintenance Programs Within nineteen (19) Months after the Effective Date of the Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment a Pump Station Preventive Maintenance Program, including a schedule for full implementation of the program. The Pump Station Preventive Maintenance Program shall include, at a minimum, the following components:

i. An electrical maintenance component which shall provide guidance to managers and field personnel responsible for electrical maintenance to ensure that preventive maintenance on Pump Station electrical components are performed on a routine basis. This component shall include meter calibration schedules for any meter used to record data collected at or from a Pump Station.

ii. A mechanical maintenance component that shall provide guidance to managers and field personnel responsible for mechanical maintenance to ensure that preventive maintenance on Pump Station mechanical components are performed on a routine basis.

iii. A physical maintenance component that shall provide guidance to managers and field personnel responsible for physical maintenance (pipes, walls, inverts, covers, etc.) to ensure that preventive maintenance on Pump Station physical components are performed on a routine basis.

iv. A Pump Station repair component that shall serve as a reactive maintenance system to repair Pump Stations that are currently in a state of disrepair but still cost-effective to service. This component shall provide for the identification, prioritization, scheduling, and repair of Pump Stations on a timely basis once a Pump Station has deteriorated beyond the scope of the preventive maintenance programs. This component shall include, at a minimum, the following:

(A) Guidance outlining when a Pump Station is to be placed in the program;

(B) A prioritized inventory of Pump Stations in need of repair;

(C) An ongoing inventory of completed repairs;

(D) A work schedule for repairs; and

(E) Standard forms, records, and performance measures and a method for information management.

(g). Hydraulic Model Development. Within thirty-seven (37) Months after the Effective Date of the Consent Decree, Chattanooga shall develop a computerized model of the WCTS (the “Hydraulic Model”) using a hydraulic modeling software package. The Hydraulic Model shall utilize a widely-accepted software package such as EPA’s SWMM model or InfoWorks or one of the widely accepted commercial variants. Chattanooga shall use the

Hydraulic Model in the assessment of the hydraulic capacity of the WCTS, and in the identification of appropriate remedial measures to address all capacity and condition limitations identified in its WCTS. Chattanooga shall develop the Hydraulic Model to provide a detailed understanding of the response of the WCTS to wet weather events and an evaluation of the impacts of proposed remedial measures and removal of I/I flow, as follows:

i. Chattanooga shall configure the Hydraulic Model to accurately represent the WCTS, in accordance with sound engineering practices. Chattanooga may model its WCTS in different levels of detail, as necessary to aid in the identification of the causes of wet weather-related SSOs, and to assess proposed remedial measures with the goal to eliminate those SSOs. Chattanooga's Hydraulic Model shall include as a minimum: all Major Gravity Lines; all Pump Stations; all Force Mains and all wet weather-related SSO locations (e.g., a 5-year look back of wet weather-related SSO locations).

ii. Chattanooga shall configure the Hydraulic Model using adequate, accurate, and sufficiently current physical data of the Sewer System, such as invert and ground elevations, pipe diameters, slopes, pipe run lengths, Manning roughness factors, manhole sizes and configurations, and pumping station performance factors. In particular, Chattanooga shall sufficiently field verify physical data to allow calibration and verification of the Hydraulic Model.

iii. Chattanooga shall calibrate and verify the Hydraulic Model using appropriate rainfall data, actual hydrographs, and flow data. As part of the calibration process, Chattanooga shall either use existing sensitivity analyses for the selected model, or perform its own sensitivity analyses, such that calibration effectiveness is maximized.



(h). Capacity Assurance Program.

i. The Program. Within thirty-seven (37) Months after the Effective Date of the Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment a Capacity Assurance Program (“CAP”). The CAP shall identify each Sewershed or part of a Sewershed with insufficient capacity under either one (1) hour peak flows, or average conditions, or both, consistent with the capacity provisions of this Section. It shall also analyze all portions of the SSS that hydraulically impact all known wet weather-related SSOs and all portions of the WWTP that may contribute to violations of the NPDES Permit. The CAP shall assess the one (1) hour peak flow capacity of all major system components for existing and proposed flows. The CAP shall enable Chattanooga to authorize new sewer service connections, or increases in flow from existing sewer service connections, only after Chattanooga certifies that the analysis procedures contained in the approved CAP have been used and that Chattanooga has determined, based on those procedures, that there is Adequate Treatment Capacity, Adequate Transmission Capacity, and Adequate Collection Capacity as set forth in Paragraph 20.(h).ii. through ix. below. At a minimum, the CAP shall contain all of the following components:

(A) The technical information, methodology, and analytical techniques, including the model or software, to be used by Chattanooga to calculate collection, transmission, and treatment capacity;

(B) The means by which Chattanooga will integrate its certification of Adequate Treatment Capacity, Adequate Transmission Capacity, and Adequate

Collection Capacity with the issuance of building permits, and Chattanooga's acquisition of new or existing sewers from other owners;

(C) A method for information management capable of tracking the Chronic Overflow Locations;

(D) The technical information, methodology, and analytical techniques, including the model or software, to be used by Chattanooga to calculate the net (cumulative) increase or decrease in volume of wastewater introduced to the SSS as a result of Chattanooga's authorization of new sewer service connections and increases in flow from existing connections and the completion of: (a) specific projects that add or restore capacity to the SSS or the WWTP ("Capacity Enhancing Projects"), (b) specific projects that reduce peak flow through removal of I/I ("I/I Projects"), and (c) permanent removal of sewer connections ("Removal of Connections");

(E) A method for information management capable of tracking the accumulation of banked credits, earned pursuant to Paragraph 20.(h).iv. below, from completion of Capacity Enhancing Projects, I/I Projects, and Removal of Connections; the capacity-limited portion of the Sewershed in which those credits were earned; and the expenditure of such credits on future increases in flow from new and existing sewer service connections in that capacity-limited portion of the Sewershed; and

(F) All evaluation protocols to be used to calculate collection, transmission, and treatment capacity including, but not limited to, standard design flow rate rules of thumb regarding pipe roughness, manhole head losses, as-built drawing accuracy (distance and slope), and water use (gallons per capita per day); projected flow impact calculation

techniques; and metering of related existing one (1) hour peak flows (flows metered in support of analysis and/or manual observation of existing one (1) hour peak flows). Chattanooga may identify sewer line segments which have been specifically designed and constructed to operate under surcharge conditions (e.g., segments with welded or bolted joints) and identify the level of surcharge for those segments.

ii. Capacity Certifications. Except as provided in Paragraph 20.(h).iii. through vi. below, after twenty-five (25) Months of EPA's approval of the CAP, Chattanooga shall authorize a new sewer service connection in the SSS, or additional flow from an existing sewer service connection in the SSS, only after it certifies that the analysis procedures contained in the approved CAP have been used and that Chattanooga has determined, based on those procedures, that there is Adequate Treatment Capacity, Adequate Transmission Capacity, and Adequate Collection Capacity as set forth in Paragraph 20.(h).ii.(A) through (E) below.

(A) Treatment Capacity Certifications. Chattanooga's certification of "Adequate Treatment Capacity" shall confirm that, at the time the WWTP receives the flow from a proposed sewer service connection(s) or increased flow from an existing sewer service connection(s), when combined with the flow predicted to occur from all other authorized sewer service connections (including those which have not begun to discharge into the WCTS), the WWTP will not be in "non-compliance" for quarterly reporting as defined in 40 C.F.R. Part 123.45, Appendix A. In addition, upon EPA's approval of the Process Controls Program (see Paragraph 25 below), Chattanooga's certification of "Adequate Treatment

Capacity” shall confirm that the new or increased flow to the WWTP will not result in Prohibited Bypasses.

(B) Transmission Capacity Certifications. Chattanooga’s certification of “Adequate Transmission Capacity” shall confirm that each Pump Station, through which the proposed additional flow from new or existing sewer service connections would pass to the WWTP, has the capacity to transmit, with its largest pump out of service (except for those Pump Stations with only one pump as of the Effective Date of the Consent Decree), the existing one (1) hour peak flow passing through the Pump Station, plus the addition to the existing one (1) hour peak flow predicted to occur from the proposed connection, plus the addition to the existing one (1) hour peak flow predicted to occur from all other authorized sewer service connections which have not begun to discharge into the SSS.

(C) Collection Capacity Certifications. Chattanooga’s certification of “Adequate Collection Capacity” shall confirm that each Gravity Sewer Line in the SSS, through which the proposed additional flow from new or existing connections would pass, has the capacity to carry the existing one (1) hour peak flow passing through the Gravity Sewer Line, plus the addition to the existing one (1) hour peak flow from the proposed connection, plus the addition to the existing one (1) hour peak flow predicted to occur from all other authorized sewer service connections which have not begun to discharge into the SSS without causing a Surcharge Condition.

(D) Definition of “One (1) Hour Peak Flow” and “Surcharge Condition”. For purposes of this Paragraph 20.(h). only, the term “one (1) hour peak flow” shall mean the greatest flow in a sewer averaged over a sixty (60) minute period at a specific location

expected to occur as a result of a representative 2 year-24 hour storm event. For purposes of this Paragraph 20.(h). only, the term “Surcharge Condition” shall mean the condition that exists when the supply of wastewater resulting from the one (1) hour peak flow is greater than the capacity of the pipes to carry it and the surface of the wastewater in manholes rises to an elevation greater than twenty-four (24) inches above the top of the pipe or within thirty-six (36) inches of the rim of the manhole, and the sewer is under pressure or head, rather than at atmospheric pressure, unless Chattanooga has, pursuant to Paragraph 20.(h).i.(F), above, identified that pipe segment and manhole as designed to operate in that condition, in which case the identified level of surcharge will be used. Notwithstanding the foregoing, no criteria contained in the CAP shall be construed as setting standards for the ultimate design or rehabilitation of Chattanooga’s SSS.

(E) Minor Sewer Connections. For minor sewer service connections, Chattanooga may elect to perform a Quarterly capacity analysis for each Sewershed or part of a Sewershed by certifying that the Sewershed has adequate capacity, as defined in Paragraph 20.(h).ii.(A) through (C) above, to carry the existing one (1) hour peak flows and the additional flows generated by all such minor sewer service connections projected to be approved in the subsequent Quarter. For any Sewershed or part of a Sewershed which can be so certified, Chattanooga may approve these projected minor sewer service connections without performing individual certifications for each connection. For the purposes of this subparagraph, a “minor sewer service connection” is a connection with an average flow not to exceed 2,500 gallons per day.

iii. Chronic Overflow Locations. Notwithstanding the provisions of Paragraph 20.(h).ii., Chattanooga shall not authorize a new sewer service connection or an increase in flow from an existing connection in any part of a Sewershed up sewer from a Chronic Overflow Location unless Chattanooga certifies that the cause(s) of the Chronic Overflow Location has been or will be eliminated, or Chattanooga satisfies the requirements of Paragraph 20.(h).iv., v. or vi. below. Any new sewer service connection or increase in flow from an existing connection authorized prior to the elimination of such cause(s) of the Chronic Overflow Location shall be conditioned upon the completion of any project eliminating such cause(s) prior to the time that the new sewer service connection or flow increase is introduced into the SSS. For purposes of this subparagraph, "Chronic Overflow Location" shall mean those locations within 500 yards of each other that have experienced collectively, within the twelve (12) Months prior to the date of certification, more than five (5) SSOs; provided, however, for purposes of this definition only, SSOs occurring within 500 yards of each other that are caused by a Single Rainfall Event shall be counted as one (1) SSO at the location of the largest SSO. For purposes of this Section, "Single Rainfall Event" shall have the meaning as defined in Part 4 of Chattanooga's NPDES Permit, which provides: "A 'rainfall event' is defined as any occurrence of rain, preceded by ten (10) hours without precipitation, that results in an accumulation of 0.01 inches or more. Instances of rainfall occurring within ten (10) hours of each other will be considered a single rainfall event."

iv. Capacity for Treatment, Transmission and Collection in Lieu of Certification. Chattanooga may authorize a new sewer service connection, or additional flow from an existing sewer service connection, even if it cannot satisfy the requirements of

Paragraph 20.(h).ii. and/or iii. above, provided Chattanooga certifies that all of the following provisions, where applicable, are satisfied:

(A) Chattanooga is in substantial compliance with this Consent Decree;

(B) The sewer lines which will convey the proposed additional flow from new or existing sewer service connections have not experienced dry weather SSOs due to inadequate capacity within the previous twelve (12) Months; or, in the alternative, the causes of any dry weather SSOs due to inadequate capacity have been eliminated;

(C) Chattanooga has identified the sewer line segment(s), Pump Station(s) and/or wastewater treatment systems that do not meet the conditions for certification of Adequate Treatment Capacity, Adequate Collection Capacity, and/or Adequate Transmission Capacity;

(D) Chattanooga has identified the sewer line segment(s) that constitute a Chronic Overflow Location(s);

(E) Chattanooga shall complete, prior to the time the proposed additional flow from new or existing sewer service connections is introduced into the SSS, specific Capacity Enhancing Projects, I/I Projects, and/or Removal of Connections which will add sewer capacity or reduce peak flows to the identified sewer line segment(s), Pump Station(s), wastewater treatment system(s), and/or Chronic Overflow Location(s) in accordance with the factors set forth in subparagraphs (F) and (G) below;

(F) Where Chattanooga has undertaken specific Capacity Enhancing Projects that provide for additional off-line storage and/or specific Removal of

Connections to satisfy the requirements of subparagraph (E) above, the estimated added capacity resulting from such projects must be equal to or greater than the estimated amount of any proposed additional flow;

(G) Where Chattanooga has undertaken specific I/I Projects or Capacity Enhancing Projects, other than those that provide for additional off-line storage, to satisfy the requirements of subparagraph (E) above, the estimated reduction in peak flows or added capacity resulting from such projects must exceed the estimated amount of any proposed additional flow by the following factors: (a) a factor of 4:1 for I/I Projects and such other Capacity Enhancing Projects related to a Chronic Overflow Location; and (b) a factor of 2:1 for I/I Projects and such other Capacity Enhancing Projects not related to a Chronic Overflow Location;

(H) Commencing twelve (12) Months after EPA approves the CAP and annually thereafter, Chattanooga has performed a review of specific Capacity Enhancing Projects and I/I Projects undertaken to determine if actual added capacity and one (1) hour peak flow reductions are in line with what Chattanooga originally estimated for such projects; and Chattanooga has used the results of this review to adjust future estimates as necessary;

(I) Any new sewer service connection or increase in flow to an existing connection authorized prior to the completion of a necessary added capacity or one (1) hour peak flow reduction project as set forth above shall be conditioned upon completion of such project prior to the time that the new sewer service connection or flow increase is introduced into the SSS;



(J) In implementing the provisions of this Paragraph 20.(h).iv., Chattanooga may use a “banking credit system” for the sewer line segment(s), Pump Station(s), wastewater treatment systems, and/or Chronic Overflow Locations for which Chattanooga is not able to satisfy the conditions set forth in Paragraph 20(h).ii. and iii. above. The addition of sewer capacity and/or reduction in one (1) hour peak flows from Capacity Enhancement Projects, I/I Projects, and Removal of Connections, completed after the Effective Date of this Consent Decree, to the affected sewer line segment, pump station, wastewater treatment system, or Chronic Overflow Location may be accumulated in the form of credits in the banking credit system in accordance with the factors set forth in subparagraphs (H) and (I) above, which may then be used for authorization of future sewer service connections or increases in flow from existing connections to the affected sewer line segment, Pump Station, wastewater treatment system, or Chronic Overflow Location in the capacity-limited portion of the Sewershed; and

(K) Following EPA’s approval of the CAP, Chattanooga shall also establish a list of all authorized new sewer service connections or increases in flow from existing connections which flows have not yet been introduced into the SSS. The following information shall be recorded for each authorized connection: street address, estimated average daily flow, estimated peak flow, Sewershed, WWTP, date authorized, and estimated Calendar Quarter when the additional flow from the connection will begin. Chattanooga shall update and maintain this list until full implementation of the CAP, as approved by EPA, and, upon introduction into the SSS, any such new sewer service connections or increases in flow from existing connections shall be accumulated in the form of debits in the banking credit system.

v. Essential Services. Notwithstanding the provisions of Paragraph 20.(h).ii. and iii. above, Chattanooga may authorize a new sewer service connection, or additional flow from an existing sewer service connection, even if it cannot certify that it has Adequate Transmission Capacity, Adequate Collection Capacity, and/or Adequate Treatment Capacity as set forth in Paragraph 20.(h).ii.(A), (B) and (C) above for health care facilities, public safety facilities, public schools, government facilities, and other facilities as agreed upon in writing by EPA; and in those cases where a pollution or sanitary nuisance condition exists, as determined by Chattanooga-Hamilton County Health Department or its regulatory successor, as the result of a discharge of untreated wastewater from an on-site septic tank. For all such new service connections, or additions to flow from an existing connection, Chattanooga shall make the appropriate subtraction to the balance in the credit bank described in Paragraph 20.(h).iv. above.

vi. Existing Illicit Connections. Notwithstanding the provisions of Paragraph 20.(h).ii. and iii. above, Chattanooga may authorize a new sewer service connection, or additional flow from an existing sewer service connection, even if it cannot certify that it has Adequate Transmission Capacity, Adequate Collection Capacity, and/or Adequate Treatment Capacity as set forth in Paragraph 20.(h).ii.(A), (B) and (C) above for any illicit connections or discharge of wastewater to the stormwater system or to waters of the State. For all such new service connections or additions to flow from an existing connection, created before the Effective Date of the Consent Decree that result from the elimination of illicit connections or discharges, Chattanooga shall not be required to make a subtraction from the balance in the credit bank described in Paragraph 20.(h).iv. above. For all such new service connections or

additions to flow from an existing connection created after the Effective Date of the Consent Decree that result from the elimination of illicit connections or discharges, Chattanooga shall make a subtraction from the balance in the credit bank described in Paragraph 20.(h).iv. above.

vii. Reconnections following Termination as a Result of Chattanooga's Private Lateral Program. Notwithstanding the provision of Paragraph 20(h)(ii)-(iv) above, in the event of a temporary suspension or interruption of a customer's service as a result of Chattanooga's Private Lateral program, any service that is resumed from a newly replaced or repaired Private Lateral shall not be deemed to be a new service connection or an addition to flow from an existing connection.

viii. Certifications. All certifications pursuant to this Paragraph 20.(h). shall be made by a professional engineer registered in the State of Tennessee and shall be approved by a responsible party of Chattanooga as defined by 40 C.F.R. § 122.22(b). Chattanooga shall maintain all such certifications, and all data on which the certifications are based, in its offices for inspection by EPA and TDEC. EPA, TDEC, and TCWN may request, and Chattanooga shall provide, any and all documentation necessary to support any certification made by Chattanooga pursuant to this Paragraph 20.(h)., and make available, to the extent possible, individuals providing such certifications to meet with EPA and TDEC.

ix. Upon its execution of this Consent Decree and until EPA approves the CAP as required by this Paragraph 20.(h), Chattanooga agrees to continue to implement its current capacity program, to ensure that new sewer service connections, or increases in flow from existing sewer service connections, are authorized only if there will be adequate treatment,

transmission, and collection capacity prior to the time such proposed additional flow is introduced into the WCTS.

(i). Inter-Jurisdictional Agreement Program. Within thirteen (13) Months after the Effective Date of the Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment an Inter-Jurisdictional Agreement Program, including a schedule for full implementation of the program, for when Chattanooga renews existing agreements or enters into new agreements that cover the collection, conveyance, and treatment of sewage by Chattanooga from municipal satellite sewer systems. The Inter-Jurisdictional Agreement Program shall include, at a minimum, the following components:

i. A delineation of the minimum provisions to be set forth in these inter-jurisdictional agreements with which the contracting municipality must comply. Such provisions shall include, but not be limited to, the following:

(A) Flow limitation requirements on the contracting party to ensure adequate capacity within Chattanooga's WCTS;

(B) Requirements on the contracting party to properly manage, operate, and maintain its sewage collection and conveyance systems so as to minimize peak flows into Chattanooga's WCTS by excluding, to the maximum reasonable extent, the intrusion of surface and ground water and other extraneous flows; and

(C) Requirements on the contracting party to ensure compliance with the legal authorities required in 40 C.F.R. § 403.8(f) with regard to equivalent control, monitoring, and enforcement of industrial use dischargers into Chattanooga's WCTS from municipal satellite sewer systems.

ii. A delineation of provisions addressing the term or life of these agreements; mechanisms for appropriate modification of the agreements; and mechanisms for enforcement of the agreements (including a description of the legal support necessary to develop, oversee and enforce the agreements) such as provisions permitting termination of the agreement and physical disconnection from Chattanooga's WCTS within a reasonable time not exceeding two (2) years upon the failure of the contracting party to comply with its capacity, management, operations, and maintenance obligations.

iii. Provisions for when any of Chattanooga's currently existing agreements expire or terminate, Chattanooga may, but shall not be required to, renew any such agreement or enter into a new agreement covering the collection, conveyance, and treatment of sewage from such other municipal satellite sewer system. In the event Chattanooga does renew such an agreement or enters into any such new agreement, each agreement shall be consistent with the requirements of the Inter-Jurisdictional Agreement Program.

21. Sanitary Sewer Evaluation Study ("SSES") Work Plan.

(a). Within nineteen (19) Months after the Effective Date of this Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment a SSES Work Plan to assess, analyze, and rehabilitate the infrastructure of the WCTS to, among other things, address I/I, structural defects, and the other conditions causing, or that are likely to cause, SSOs. Chattanooga shall develop and implement the SSES Work Plan in accordance with sound engineering practices and the following guidance documents: EPA's *Handbook: Sewer System Infrastructure Analysis and Rehabilitation*, EPA/625/6-91/030, October 1991; Water Environment Federation's Manual of Practice FD-6, *Existing Sewer Evaluation &*

*Rehabilitation*, 1994; EPA's guidance: *Computer Tools for Sanitary Sewer System Capacity Analysis and Planning*, EPA/600/R-07/111, October 2007; and the *Tennessee Design Criteria for Sewage Works* in accordance with Tenn. Comp. R. & Regs., ch. 1200-4-2-.03.

(b). The SSES Work Plan shall establish procedures for setting priorities and expeditious schedules for undertaking the WCTS assessment and rehabilitation components set forth in Subparagraphs 21.(c).i. through viii. below. Chattanooga shall develop these priorities and expeditious schedules taking into consideration the nature and extent of customer complaints; flow monitoring, including flow isolation studies; location and cause of SSOs; any remedial measures already undertaken; field crew work orders; any preliminary sewer assessments; and any other relevant information. In addition, areas near surface waters that have been included on TDEC's CWA Section 303(d) list of impaired waters for pathogens shall also receive priority by Chattanooga. Finally, Chattanooga shall also consider areas that have been identified by EPA as potentially having environmental justice issues (minority and/or low income neighborhoods) when developing the priorities.

Furthermore, Chattanooga has completed an initial flow monitoring study in which it has divided the WCTS into approximately equal sized Sewersheds and ranked the Sewersheds based on the normalized net rainfall-induced I/I ("RD I/I") (defined for purposes of this Consent Decree only as twenty (20) gallons per day per linear foot) in gallons per day per linear foot for each Sewershed. Based on this information, along with other criteria, Chattanooga shall implement the SSES Work Plan in two (2) phases. SSES Phase I shall be completed on or before five (5) years after EPA's approval of the SSES Work Plan and shall include the following five (5) Sewersheds, as shown on the map attached hereto as Appendix A,

which represent areas with the most normalized net RD I/I: Chattanooga Creek 4; Dobbs Branch 3; South Chickamauga Creek 1; South Chickamauga Creek 5; and South Chickamauga Creek 16. However, if Chattanooga determines based on new data or information that a different Sewershed should replace one of the five (5) Sewersheds identified above, Chattanooga shall submit a request in writing to EPA and TDEC for such replacement along with a detailed explanation justifying the proposed replacement. Any such replacement approved by EPA shall not constitute a material modification to this Consent Decree as set forth in Section XIX (Modification) below. SSES Phase II shall be completed for the remaining twenty four (24) Sewersheds, as shown on the map attached hereto as Appendix A, within fifteen (15) years after EPA's approval of the SSES Work Plan.

(c). The SSES Work Plan shall include standard procedures for an information management system, performance goals for each of the components of the SSES Work Plan set forth below, and procedures for analysis of the effectiveness of completed rehabilitation. The SSES Work Plan shall include the following components:

i. Corrosion Defect Identification. The Corrosion Defect Identification component of the SSES Work Plan shall establish standard procedures for inspecting and identifying WCTS infrastructure that is either corroded or at risk of corrosion. The Corrosion Defect Identification component shall include a system for prioritizing repair of existing corrosion defects, corrosion identification forms, and procedures for a corrosion defect analysis.

ii. Manhole Condition Assessment and Rehabilitation. The Manhole Condition Assessment and Rehabilitation component of the SSES Work Plan shall establish

standard procedures for the condition assessment of manholes within the WCTS. This component shall include manhole inspection forms and procedures for a manhole defect analysis. This component shall also establish a process for setting manhole rehabilitation priorities and expeditious schedules; shall establish an ongoing inventory of manhole rehabilitation, including identification of the rehabilitation techniques to be used; and shall require an analysis of the effectiveness of completed rehabilitation.

iii. Flow Monitoring. The Flow Monitoring component of the SSES Work Plan shall establish procedures for initiating routine flow monitoring during dry and wet weather to support engineering analyses related to Sewer System capacity and peak flow studies. Dry weather monitoring shall be carried out so as to allow the characterization of base flows and I/I rates within the WCTS. Wet weather monitoring shall be conducted periodically during events of sufficient duration and intensity that cause significant I/I into the WCTS. The procedures shall identify the process used to establish flow monitoring locations, appropriate flow monitoring techniques, sewer cleaning associated with flow monitoring and a procedure for rainfall measurement.

iv. Closed Circuit Television (“CCTV”) Inspection. The CCTV inspection component of the SSES Work Plan shall establish standard procedures for CCTV inspection within the WCTS to support sewer assessment and rehabilitation activities, and shall include procedures for CCTV cleaning and a process for the retention and retrieval of CCTV inspection data.

v. Gravity Sewer Line Defect Analysis and Rehabilitation. The Gravity Sewer Line and Force Main defect analysis component of the SSES Work Plan shall



establish standard procedures for analysis of Gravity Sewer Line defects within the WCTS which may vary depending on the size of the Gravity Sewer Line. Such procedures shall include Private Lateral investigations to identify sources of I/I to the WCTS. The Gravity Sewer Line Defect Analysis component shall establish standard defect codes, defect identification procedures and guidelines, and a standardized process for cataloging Gravity Sewer Line defects. This component shall also establish a process for setting Gravity Sewer Line rehabilitation priorities and expeditious schedules; shall establish an ongoing inventory of Gravity Sewer Line rehabilitation, including identification of the rehabilitation techniques to be used; and shall require an analysis of the effectiveness of completed rehabilitation.

vi. Force Main Condition Assessment and Rehabilitation. The Force Main Condition Assessment and Rehabilitation component of the SSES Work Plan shall establish standard procedures for the condition assessment of Force Mains within the WCTS. This component shall include inspection forms and procedures for a Force Main defect analysis. This component shall also establish a process for setting Force Main rehabilitation priorities and expeditious schedules; shall establish an ongoing inventory of Force Main rehabilitation, including identification of the rehabilitation techniques to be used; and shall require an analysis of the effectiveness of completed rehabilitation.

vii. Smoke Testing. The Smoke Testing component of the SSES Work Plan shall establish standard procedures for smoke testing of the Gravity Sewer Lines within the WCTS to identify sources of I/I, including cross connections and other unauthorized connections. Such procedures shall include Private Lateral investigations to identify sources of I/I.

viii. Pump Station Performance and Rehabilitation. The Pump Station Performance and Rehabilitation component of the SSES Work Plan shall establish standard procedures for the evaluation of Pump Station performance and Pump Station adequacy within the WCTS. The Pump Station Performance and Rehabilitation component shall include:

(A) The use of pump run time meters; pump start counters; computation of Nominal Average Pump Operating Time ("NAPOT"); root cause failure analysis protocols; and appropriate remote sensing such as Supervisory Control and Data Acquisition ("SCADA");

(B) The evaluation of station capacity, as described in the *Pumping Systems* chapter of the most current version of WEF's Manual of Practice FD-4, *Design of Wastewater and Stormwater Pumping Stations*;

(C) The evaluation of critical response time, defined as the time interval between activation of the high wet well level alarm and the first (1<sup>st</sup>) SSO, under peak flow conditions;

(D) The evaluation of station conditions, based upon both physical inspection and recent operating and mechanical failure history during at least the past five (5) years;

(E) The evaluation of station design and equipment, including redundancy of pumps and electrical power supply, and other equipment installed, based upon Chapter 40, *Wastewater Pumping Stations* of the most recent edition of *Recommended Standards for Wastewater Facilities* by the Great Lakes-Upper Mississippi River Board of

State and Provincial Public Health and Environmental Managers (commonly known as the “Ten State Standards”);

(F) The evaluation of the ability of maintenance personnel to take corrective action within the critical response time calculated for each Pump Station; and

(G) A process for setting Pump Station rehabilitation priorities and expeditious schedules and an ongoing inventory of Pump Station rehabilitation, including identification of the rehabilitation techniques to be used, and an analysis of the effectiveness of completed rehabilitation.

22. Early Action Capital Improvement Projects. Based on previous investigations, Chattanooga has identified certain rehabilitation and other projects that are intended to address conditions currently causing SSOs in the WCTS and other violations alleged in the Complaint and the TCWN Complaint which shall be referred to as “Early Action Capital Improvement Projects.” The Early Action Capital Improvement Projects are identified and described in Appendix C, attached hereto and incorporated herein. Chattanooga contends that the Early Action Capital Improvement Projects, along with the Sewersheds to be remediated in SSES Phase I, constitute approximately fifteen percent (15 %) of the WCTS by linear foot. Chattanooga shall complete each of these Early Action Capital Improvement Projects in accordance with the schedules set forth in Appendix C. Such schedules do not extend past five (5) years after the Effective Date of this Consent Decree. Any change to this list of projects or schedule approved by EPA shall not constitute a material modification to this Consent Decree as set forth in Section XIX below.

23. East Bank/West Bank Outfall Assessment and Rehabilitation Plan.

Chattanooga's WCTS has experienced SSOs containing large volumes of wet weather flow from the CSS and SSS at unpermitted outfalls known as the East Bank Outfall and the West Bank Outfall. Based on previous investigations, Chattanooga contends that the SSOs from these unpermitted outfalls will be eliminated through the reduction of I/I in the WCTS as a result of implementation of the Inter-jurisdictional Agreement Program, SSES Phase I, and the Early Action Capital Improvement Projects. However, in the event that either the East Bank Outfall or the West Bank Outfall experiences an SSO within the first (1<sup>st</sup>) year following completion of SSES Phase I and the Early Action Capital Improvement Projects, Chattanooga shall submit to EPA and TDEC for review and comment within seven (7) Months after such SSO event an East Bank/West Bank Assessment and Rehabilitation Plan to eliminate SSOs from these unpermitted outfalls. The Parties acknowledge that this Plan may include a proposal by Chattanooga to have the East Bank and/or West Bank Outfall permitted as a CSO Outfall. The East Bank/West Bank Assessment and Rehabilitation Plan shall include expeditious schedules for specific assessment and rehabilitation projects for the elimination of the SSOs and/or the potential permitting of the East Bank and/or West Bank Outfall as a CSO Outfall. Such expeditious schedules shall not exceed seven (7) years after EPA approves the East Bank/West Bank Assessment and Rehabilitation Plan.

24. Long Term Control Plan Updates. In 1989, Chattanooga developed and began to implement a Combined Sewer Overflow Facilities Plan. This plan predated EPA's 1994 CSO Control Policy and thus, while it may have contained many of the elements of a Long Term Control Plan as required in the CSO Control Policy, it did not adequately include or address all

of the required components of a Long Term Control Plan. Therefore, Chattanooga shall submit the Long Term Control Plan Updates set forth below to satisfy certain requirements of the CSO Control Policy.

(a). Additional Operational Plan for Chattanooga Creek CSO Outfalls.

Despite Chattanooga's implementation of CSO control measures pursuant to its Combined Sewer Overflow Facilities Plan, CSO discharges from the Central Avenue CSO Outfall (Outfall 002 in the NPDES Permit) and the Williams Street CSO Outfall (Outfall 003 in the NPDES Permit), both of which discharge into Chattanooga Creek, are not in compliance with State water quality standards for dissolved oxygen and Escherichia coli ("*E. coli*") as set forth in the Tennessee Water Quality Criteria Chapter 1200-4-3. As a result, within forty-eight (48) Months after the Effective Date of this Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment an Additional Operational Plan for the Chattanooga Creek CSO Outfalls (Central Avenue CSO Outfall and William Street CSO Outfall) that shall provide for additional long term CSO controls for these CSO outfalls that will ensure discharges from these CSO outfalls will comply with State water quality standards in accordance with the CSO Control Policy. Such Additional Operational Plan shall include expeditious schedules for implementation and completion of such CSO controls not to exceed three (3) Years from EPA's approval of the Additional Operational Plan.

(b). Post Construction Compliance Monitoring Program. Within nineteen (19)

Months after the Effective Date of this Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment a Post Construction Compliance Monitoring Program for the CSO outfalls that discharge into Chattanooga Creek (Central Avenue CSO Outfall and William

Street CSO Outfall) in accordance with Section II.C.9 of the CSO Control Policy to verify compliance of such discharges with State water quality standards and protection of designated uses as well as to ascertain the effectiveness of CSO controls. The Post Construction Monitoring Program shall be developed in consideration of the effects of reservoir operations and the effects of the tributaries to Chattanooga Creek. Both far-field and near-field water quality models should be employed to predict the area of impact from the CSOs. The program shall include a map of the monitoring stations, monitoring schedules (including the frequency and duration of sampling at each station), a parameter list, a discussion of monitoring protocols, and a quality assurance project plan. The program shall also include data collection to measure the overall effects of the program on water quality and to determine the effectiveness of CSO controls. Monitoring should be coordinated with any ongoing or planned state monitoring programs, programs of other permittees within the same watershed, or both. The program shall include expeditious schedules for conducting such monitoring, and such schedules shall take into consideration the schedule for completion of the CSO control measures Chattanooga will implement pursuant to the Additional Operational Plan for these CSO outfalls as set forth in the above paragraph.

(c). Maximizing Treatment at the Moccasin Bend WWTP. Chattanooga's Moccasin Bend WWTP has experienced Bypasses of flow from its treatment processes. Based on previous investigations, Chattanooga contends that most, if not all, of these Bypass events in the future may be avoided through the reduction of I/I in the WCTS as a result of implementation of the Inter-jurisdictional Agreement Program, SSES Phase I and the Early Action Capital Improvement Projects. However, in the event that a Bypass occurs within the

first (1<sup>st</sup>) year following completion of SSES Phase I and the Early Action Capital Improvement Projects, Chattanooga shall submit to EPA and TDEC for review and comment within twelve (12) Months after such Bypass event a Feasible Alternatives Analysis in accordance with Section II.C.7 of the CSO Control Policy. The Feasible Alternatives Analysis shall include an assessment and proposal for implementation of any feasible alternatives to prevent the Bypass of flow from any treatment process. In addition, at a minimum, in order to provide support for any Bypass of flow legally in accordance with 40 C.F.R. § 122.41(m), the Feasible Alternatives Analysis shall provide justification for the cut-off point at which the flow at the Moccasin Bend WWTP will be diverted from the secondary treatment portions of the WWTP, and provide a benefit-cost analysis demonstrating that conveyance of wet weather flow to the WWTP for primary treatment is more beneficial than other CSO abatement alternatives such as storage and pump back for secondary treatment, sewer separation, or satellite treatment. In the event the Feasible Alternatives Analysis proposes implementation of certain feasible alternatives to prevent the Bypass of flow, such Analysis shall include expeditious schedules for specific rehabilitation projects that shall not exceed seven (7) years from the date of submittal of the Feasible Alternatives Analysis.

25. Moccasin Bend WWTP Process Controls Program. Within nineteen (19) Months after the Effective Date of the Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment a Process Controls Program designed to minimize the frequency, duration, and volume of any Bypass and violation of an effluent limit at the Moccasin Bend WWTP through proper management, operation and maintenance controls. The Process Controls Program shall include, but not be limited to, the following:

(a). Identification of necessary activities to insure that SSOs from the East and West Bank Outfalls are minimized to the greatest extent possible.

(b). Identification of staffing needs to insure that plant operators are present during periods during which the WWTP is likely to have a Bypass.

(c). A process for monitoring and recording plant operations and metrics such as influent flow, Secondary Treatment flow, effluent flow, concentration of mixed liquor suspended solids (“MLSS”), depth of sludge blanket levels and other appropriate criteria that the operations staff will use to determine the effective treatment capacity of the secondary system, which establishes when a Bypass will commence and will cease.

(d). The use of available laboratory and on-line instrumentation data before making a decision to change process controls.

(e). Identification of the staff positions that will be responsible for implementing the Process Control Program.

(f). Identification of activities that Chattanooga shall undertake when conditions indicate a probable need to have a Bypass. Such activities may include monitoring and/or adjusting clarifier sludge blankets, balancing flows to Secondary Treatment units, etc.

(g). A process for evaluating the effectiveness of the controls and for making adjustments as necessary to meet the goals of the Process Controls Program.

(h). An operations record keeping protocol which shall establish a system for accurately recording operations of the Moccasin Bend WWTP including its Bypass and effluent monitoring activities. Such records shall include operator logs, activity reports,



performance reports, documentation of all Bypass events and a listing of the criteria that determined when a Bypass commenced and ceased.

(i). Performance measures for ensuring that the controls being implemented are as effective as possible.

26. Green Infrastructure Plan. Within twenty-four (24) months after the Effective Date of the Consent Decree, Chattanooga shall submit to EPA and TDEC for approval a Green Infrastructure Program Plan (the “GI Plan”) for the CSS. For the purposes of this Consent Decree, “Green Infrastructure” shall mean the range of stormwater control measures that use plant/soil systems, permeable pavement, stormwater harvest and reuse, or native landscaping to store, infiltrate, and/or evapotranspire stormwater and reduce flows to the sewer systems or to surface waters. Green Infrastructure may include, but is not limited to, bio-retention, extended detention wetland areas, green roofs and permeable pavement. Green Infrastructure practices also include control measures to harvest and reuse stormwater, such as rain barrels and cisterns. The GI Plan shall include the following elements:

(a). Green Infrastructure Controls. The GI Plan shall identify specific Green Infrastructure control measures that store, infiltrate, or evapotranspire precipitation and reduce wet weather flows into the CSS. The GI Plan shall also identify maintenance requirements for the control measures identified.

(b). Comprehensive Land Use Policy. The GI Plan shall include the development of a Comprehensive Land Use Policy for land owned by Chattanooga that assesses the potential for Chattanooga, either on its own or in partnership with private parties

or other governmental agencies, to implement Green Infrastructure on property owned or operated by Chattanooga.

(c). Green Infrastructure Community Assistance. Chattanooga shall establish and describe in the Plan a public participation process that provides information about Green Infrastructure.

(d). Implementation Schedule. The GI Plan shall include a process for setting Green Infrastructure control measure priorities and expeditious implementation schedules.

27. Schedule Reconsideration Based on Financial Circumstances. The schedule for completion of any of the projects required by this Consent Decree may be extended if Chattanooga is able to demonstrate a need for such an extension by submitting a request in writing to EPA and TDEC, including a Financial Capability Analysis. Any such extension shall constitute a material change to this Consent Decree for purposes of Section XXIV of this Consent Decree (Modification). As more particularly set forth below, such Financial Capability Analysis must demonstrate that the expected per household cost of Chattanooga's compliance with this Consent Decree will cause Chattanooga's cost per household to exceed 2.5% of the Median Household Income ("MHI") for Chattanooga's entire service area, calculated using EPA's *Combined Sewer Overflows Guidance for Financial Capability Assessment and Schedule Development*, EPA 8320B-97-004, published February 1997, or the most current version of EPA's affordability guidance or regulation in effect at the time of such request (the "Financial Capability Assessment Guidance").

(a). The schedule extension request must be provided at the same time as the Financial Capability Analysis, and must include a demonstration, complete with supporting documentation, that:

i. The Residential Indicator, when calculated in accordance with the Financial Capability Assessment Guidance, as modified by the requirements of Subparagraph 27.(c). below and using the inputs described and defined in Subparagraph 27(c). below, and using a reasonable engineering estimate of the remaining costs of completing construction of the projects required by this Consent Decree expressed in the value of dollars during the year that Chattanooga submits the schedule extension request, exceeds 2.5%, or other applicable percentage contained in the Financial Capability Assessment Guidance;

ii. A description of each requirement and associated deadline in the approved schedule for which Chattanooga seeks an extension; and

iii. Each request for a deadline extension is as short as reasonably possible.

(b). To determine Chattanooga's MHI, Chattanooga shall use MHI data for the most recent year from either the Federal Census or American Community Survey ("ACS"), whichever is the most current at the time of the submittal of the request for extension. If the most current ACS data includes both a one (1)-year estimate and three (3)-year estimate of MHI, Chattanooga shall use the one (1)-year estimate to determine their MHI, although Chattanooga may also submit an MHI figure based on the three (3)-year estimate of MHI under the ACS.

(c). To calculate and determine Chattanooga's Residential Indicator at the time a schedule extension request is submitted, Chattanooga shall use the following inputs:

i. Current annual operation and maintenance expenses for the WCTS and WWTP calculated as total expenses, including depreciation, in Chattanooga's Comprehensive Annual Financial Report ("CAFR") for the most recent year, but only if Chattanooga's CAFR accurately states Chattanooga's operation and maintenance expenses. If Chattanooga's CAFR for the most recent year either does not exist or does not accurately state its operation and maintenance expenses, Chattanooga shall calculate and determine this input with appropriate accounting records, including source documents, and submit to EPA and TDEC copies of the accounting records and source documents.

ii. Current annual debt service for the WCTS and WWTP calculated as the total principal and interest payments on bonds and notes from the financing activities section of the cash flow statement in Chattanooga's CAFR for the most recent year, but only if it accurately reflects the principal and interest payments. If Chattanooga's CAFR for the most recent year either does not exist or does not accurately reflect Chattanooga's principal and interest payments, Chattanooga shall calculate and determine this input with appropriate accounting records, including source documents, and shall submit to EPA and TDEC copies of the accounting records and source documents;

iii. Reasonable documented engineering estimates projecting the increase in operation and maintenance expenses expected after completing construction of the projects required by the Consent Decree, expressed in value of dollars for the year during which Chattanooga submits the schedule extension request;

iv. The annual capital costs based on the expected financing of a reasonable, documented engineering estimate of the costs of completing construction of the projects required by this Consent Decree expressed in the value of dollars during the year that Chattanooga submit the schedule extension request. To support Chattanooga's calculation of this input, Chattanooga shall submit to EPA and TDEC an explanation of the basis for, and calculation of, the annual cost estimate and the engineering estimates, accounting records, and source documents on which Chattanooga relied to calculate this input;

v. When calculating Chattanooga's residential share of wastewater treatment costs in accordance with the Financial Capability Assessment Guidance, Chattanooga shall use the most recent year of Federal Census or ACS data and billing data regarding Chattanooga's customer base not reflected in such data. Chattanooga also shall use the same ratio between total wastewater flow and residential I/I that Chattanooga uses for rate setting purposes, if any, to calculate the residential share of wastewater treatment costs; and

vi. When calculating the total number of households in Chattanooga's service area, Chattanooga shall count each single family house, and each unit in multi-family housing structures such as apartment buildings and duplexes as one household, but shall not count households that have onsite sewage disposal (septic) systems. To the extent that customers' billing data does not accurately reflect the number of units in multi-family housing structures, Chattanooga shall use ACS and Federal Census data to more accurately estimate the total number of households in Chattanooga's service area.

(d). In addition to the calculation of the Residential Indicator as required in Subparagraph 27.(c), Chattanooga may submit an additional calculation using alternative

inputs that Chattanooga contends produces a more accurate calculation of the Residential Indicator, provided such inputs are consistent with the Financial Capability Assessment Guidance.

(e). If EPA denies in writing Chattanooga's request for an extension for completing any of the deadlines in an approved schedule under this Consent Decree, in whole or in part, or if more than ninety (90) Days elapses from the date that Chattanooga submits such a request for an extension, and Chattanooga has not either received from EPA a written denial or approval of Chattanooga's schedule extension request, then Chattanooga may pursue dispute resolution pursuant to Section XII of this Consent Decree (Dispute Resolution).

(f). If Chattanooga invokes the dispute resolution procedures of Section XII of this Consent Decree (Dispute Resolution) for a denial of its request for a schedule extension, then Chattanooga's obligations pursuant to this Consent Decree shall not be extended, postponed, or otherwise affected in any way unless and until final resolution of the dispute so provides.

## **VII. CIVIL PENALTY**

28. Chattanooga shall pay the sum of \$476,400 as a civil penalty in accordance with the provisions of Paragraphs 29 and 30.

29. Within thirty (30) Days after the Effective Date of this Consent Decree, Chattanooga shall pay to the United States fifty percent (50%) of the civil penalty due (\$238,200) by FedWire Electronic Funds Transfer ("EFT") to the U.S. Department of Justice in accordance with written instructions to be provided to Chattanooga, following lodging of the Consent Decree, by the Financial Litigation Unit of the U.S. Attorney's Office for the Eastern

District of Tennessee, 1110 Market Street, Suite 301, Chattanooga, Tennessee 37401, (423) 752-5140. At the time of payment, Chattanooga shall send a copy of the EFT authorization form and the EFT transaction record, together with a transmittal letter, which shall state that the payment is for the civil penalty owed pursuant to the Consent Decree in United States et al. v. City of Chattanooga, and shall reference the civil action number and DOJ case number 90-5-1-1-10145, to the United States in accordance with Section XIV of this Consent Decree (Notices); by email to [acctsreceivable.CINWD@epa.gov](mailto:acctsreceivable.CINWD@epa.gov); and by mail to:

EPA Cincinnati Finance Office  
26 Martin Luther King Drive  
Cincinnati, Ohio 45268

In the event that full cash payment to the United States is not made within thirty (30) Days of the Date of Entry, Chattanooga shall pay to the United States interest on the balance due from the original due date to the date of payment, at the rate calculated pursuant to 28 U.S.C. § 1961.

30. Chattanooga shall make payment as directed by the State of fifty percent (50%) of the civil penalty due as follows: Chattanooga shall spend \$238,200 on the State Project in accordance with, and as more particularly set forth in, Appendix D of this Consent Decree. TDEC has approved this payment as an appropriate State Project recognizing the value of the project and its potential to positively impact the local environment.

### **VIII. SUPPLEMENTAL ENVIRONMENTAL PROJECT**

31. Chattanooga shall satisfactorily implement and complete a Supplemental Environmental Project ("SEP") involving the restoration of a tributary of South Chickamauga Creek in accordance with this Section VIII and Appendix E of this Consent Decree.

Chattanooga may use contractors or consultants in planning and implementing the SEP. The SEP shall be completed in accordance with the schedule set forth in Appendix E.

32. With regard to the SEP, Chattanooga certifies the truth and accuracy of each of the following:

(a). That all cost information provided to EPA in connection with EPA's approval of the SEP is complete and accurate and that Chattanooga in good faith estimates that the cost to implement the SEP is \$800,000.

(b). That, as of the date of executing this Consent Decree, Chattanooga is not required to perform or develop the SEP by any federal, state, or local law or regulation and is not required to perform or develop the SEP by agreement, grant, or as injunctive relief awarded in any other action in any forum.

(c). That Chattanooga is not a party to any open federal financial assistance transaction that is funding or could be used to fund the same activity as the SEP, and that there is no such open federal financial assistance transaction that is funding or could be used to fund the same activity as the SEP, nor has the same activity been described in an unsuccessful federal financial assistance transaction proposal submitted to EPA within two (2) years of the date of Chattanooga's execution of this Consent Decree (unless the project was barred from funding as statutorily ineligible). For purposes of this certification, the term "open federal financial assistance transaction" refers to a grant, cooperative agreement, loan, federally-guaranteed loan guarantee, or other mechanism for providing federal financial assistance whose performance period has not yet expired.



(d). That the SEP is not a project that Chattanooga was planning or intending to construct, perform, or implement other than in settlement of the claims resolved in this Consent Decree.

(e). That Chattanooga has not received, and will not receive, credit for the SEP in any other enforcement action.

(f). That Chattanooga will not receive any reimbursement for any portion of the SEP from any other person.

33. SEP Completion Report. Within thirty (30) Days after the date set for completion of the SEP as set forth in Appendix E of this Consent Decree, Chattanooga shall submit a SEP Completion Report to the EPA and TDEC for review and comment. The SEP Completion Report shall contain all of the following information:

- (a). A detailed description of the SEP as implemented.
- (b). A description of any problems encountered in completing the SEP and the solutions thereto.
- (c). An itemized list of all eligible SEP costs expended.
- (d). Certification that the SEP has been fully implemented pursuant to the provisions of this Consent Decree.
- (e). A description of the environmental and public health benefits resulting from implementation of the SEP (with a quantification of the benefits and pollutant reductions, if feasible).

34. EPA may, in its sole discretion, require information in addition to that described in the preceding Paragraph, in order to evaluate Chattanooga's SEP Completion Report.

35. After receiving the SEP Completion Report, EPA shall notify Chattanooga whether or not Chattanooga has satisfactorily completed the SEP. If Chattanooga has not completed the SEP in accordance with this Consent Decree, stipulated penalties may be assessed under Section X of this Consent Decree (Stipulated Penalties).

36. Disputes concerning the satisfactory performance of the SEP and the amount of eligible SEP costs may be resolved under Section XII of this Consent Decree (Dispute Resolution).

37. Any public statement, oral or written, in print, film, or other media, made by Chattanooga making reference to the SEP under this Consent Decree shall include the following language: “This project was undertaken in connection with the settlement of an enforcement action, United States et al. v. City of Chattanooga, taken on behalf of the U.S. Environmental Protection Agency under the Clean Water Act.”

#### **IX. REPORTING REQUIREMENTS**

38. Quarterly Reports. Beginning thirty (30) Days after the first (1<sup>st</sup>) full three (3) Month period following the Effective Date of this Consent Decree, and thirty (30) Days after each subsequent three (3) Month period thereafter until termination of the Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment a Quarterly Report that shall include the date, time, location, source, estimated duration, estimated volume, receiving water (if any), and cause of all SSO Events, Bypasses at the Moccasin Bend WWTP, and discharges from CSO Outfalls occurring in the applicable three (3) Month period. In reporting such data, Chattanooga shall provide the information in a tabulated electronic format (*e.g.*, Excel spreadsheet) as it deems appropriate. For purposes of this Section IX (Reporting Requirements),

a “SSO Event” shall mean the total time period a SSO(s) (as defined in Subparagraph 8.(nn). of this Consent Decree) occurs at the same location and due to the same causes(s). For example, a collapsed pipe that results in a SSO on multiple days is a single SSO Event.

39. Semi-Annual and Annual Work Progress Reports. Beginning thirty (30) Days after the first (1<sup>st</sup>) full six (6)-Month period following the Effective Date of this Consent Decree, and thirty (30) Days after each subsequent six (6)-Month period until the twelfth (12<sup>th</sup>) report is submitted, Chattanooga shall submit to EPA and TDEC for review and comment a Semi-Annual Work Progress Report. Beginning thirty (30) Days after the first (1<sup>st</sup>) full twelve (12)-Month period following the submittal of the twelfth (12<sup>th</sup>) Semi-Annual Work Progress Report until termination of this Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment an Annual Work Progress Report. Each Semi-Annual and Annual Work Progress Report shall include, at a minimum:

(a). A description of projects and activities completed and milestones achieved during the previous applicable six (6) or twelve (12)-Month period pursuant to the requirements of this Consent Decree, in Gantt chart or similar format, including a description of the status of compliance or non-compliance with the requirements of this Consent Decree and, if applicable, the reasons for non-compliance. If any non-compliance cannot be fully explained at the time the report is due, Chattanooga shall include a statement to that effect in the report. Chattanooga shall investigate to determine the cause of the non-compliance and then shall submit an amendment to the report, including a full explanation of the cause of the non-compliance, within thirty (30) Days after submission of the report.

(b). A summary of significant projects and activities anticipated to be performed, and milestones anticipated to be achieved, in the successive applicable six (6) or twelve (12)-Month period to comply with the requirements of this Consent Decree, in Gantt chart or similar format.

(c). Any additional information Chattanooga determines is appropriate to demonstrate that Chattanooga is implementing the remedial actions required under this Consent Decree in an adequate and timely manner.

40. Annual Reports. Beginning sixty (60) Days after the first (1<sup>st</sup>) full twelve (12)-Month period following the Effective Date, and sixty (60) Days after each subsequent twelve (12) Month-period until termination of this Consent Decree, Chattanooga shall submit to EPA and TDEC for review and comment an Annual Report. Each Annual Report shall cover the most recent applicable twelve (12)-Month period and shall include a summary of the CMOM Programs implemented or modified pursuant to this Consent Decree, including a comparison of actual performance with any performance measures that have been established. For the first (1<sup>st</sup>) five (5) Annual Reports only, Chattanooga shall include a trends analysis of the number, volume, duration, and cause of Chattanooga's SSO Events for a twenty-four (24)-Month rolling period updated to reflect the SSO Events that occurred during the previous twelve (12)-Month period. Beginning with the sixth (6<sup>th</sup>) Annual Report, Chattanooga shall include a trends analysis of the number, volume, duration, and cause of Chattanooga's SSO Events for a five (5)-year rolling period updated to reflect the SSO Events that occurred during the previous twelve (12)-Month period. In reporting trends and other SSO data, Chattanooga shall provide the information in such format as it deems appropriate.

41. Except as otherwise provided in the SORP or ERP, whenever any violation of this Consent Decree or any other event affecting Chattanooga's performance under this Consent Decree or its NPDES Permit may pose an immediate threat to the public health or welfare or the environment, Chattanooga shall notify EPA and TDEC orally or by electronic or facsimile transmission as soon as possible, but no later than twenty-four (24) hours after Chattanooga first knew of the violation or event.

42. All reports shall be submitted to the persons designated in Section XVI of this Consent Decree (Notices) for EPA and TDEC and shall be certified pursuant to Paragraph 17 of this Consent Decree. The certification requirement in Paragraph 17 does not apply to emergency or similar notifications where compliance would be impractical. In addition, a copy of all reports submitted pursuant to this Section (IX. Reporting Requirements) shall also be made available to the public in the PDR.

43. Compliance with this Section does not relieve Chattanooga of any other reporting obligations required by the CWA, the TWQCA, or implementing regulations, or by any other Federal, state, or local law, regulation, permit, or other requirement, including the NPDES Permit.

44. Notification to EPA or TDEC pursuant to this Section of an anticipated delay shall not by itself excuse the delay or otherwise satisfy the notification requirements set forth in Section XI (Force Majeure).

45. Any information provided pursuant to this Consent Decree may be used by the United States and the State in any proceeding to enforce the provisions of this Consent Decree and as otherwise permitted by law.

## **X. STIPULATED PENALTIES**

46. Chattanooga shall be liable for stipulated penalties to the United States and the State for violations of this Consent Decree as specified below, unless excused under Section XI (Force Majeure). A violation includes failing to perform any obligation required by the terms of this Consent Decree, including any work plan or schedule approved under this Consent Decree, according to all applicable requirements of this Consent Decree and within the specified time schedules established by or approved under this Consent Decree.

47. If Chattanooga fails to pay the civil penalty required to be paid to the United States under Section VII of this Consent Decree (Civil Penalty) when due, Chattanooga shall pay a stipulated penalty of \$1,000 per day for each day that the payment is late.

48. The following stipulated penalties shall accrue for each violation identified below:

(a). SSO Events Reaching Waters. For each SSO Event discharging wastewater to waters of the United States occurring after the Effective Date of this Consent Decree, a stipulated penalty may be assessed as follows:

If an SSO Event Occurs:	Penalty per SSO Event:
Within twenty-four (24) Months of the Effective Date	\$350
Between twenty-four (24) Months and sixty (60) Months of the Effective Date	\$500
After sixty (60) Months of the Effective Date for each SSO Event less than 250,000 gallons	\$1,000
After sixty (60) Months of the Effective Date for each SSO Event 250,000 gallons or more	\$2,000

For purposes of this Subparagraph 48.(a), a “SSO Event” shall mean the total time period a SSO discharging wastewater to waters of the United States occurs at the same location and due to the same causes(s). For example, a collapsed pipe that results in a SSO discharging wastewater to waters of the United States or State on multiple days is a single SSO Event.

(b). Failure to Timely Submit Deliverable. For each day Chattanooga fails to Timely submit any Deliverable, a stipulated penalty for each such Deliverable may be assessed as follows:

Period of Noncompliance:	Penalty Per Deliverable Per Day:
One (1) to fifteen (15) days	\$350
Sixteen (16) to thirty (30) days	\$500
Thirty-one (31) to sixty (60) days	\$1,000
More than sixty (60) days	\$2,000

(c). Failure to Comply with CAP. Beginning twenty-five (25) Months after EPA approval of the CAP, for each authorization by Chattanooga of a new sewer service connection in the SSS, or additional flow from an existing sewer service connection in the SSS, not consistent with the requirements of the CAP, a stipulated penalty of \$10,000 may be assessed.

(d). Failure to Complete SSES Phase I and/or SSES Phase II. For each day Chattanooga fails to Timely complete SSES Phase I and/or SSES Phase II in accordance with the final deadlines set forth in Subparagraph 21.(b)., daily stipulated penalties may be assessed as follows:

Period of Noncompliance:	Penalty Per Day:
One (1) to thirty (30) days	\$500
Thirty-one (31) to sixty (60) days	\$1,000
Sixty-one (61) to one hundred-eighty (180) days	\$2,500
More than one hundred-eighty (180) days	\$5,000

(e). Failure to Complete the East Bank/West Bank Outfall Assessment and Rehabilitation Plan. For each day Chattanooga fails to Timely complete the East Bank/West Bank Outfall Assessment and Rehabilitation Plan in accordance with the final deadline set forth in Paragraph 23, daily stipulated penalties may be assessed as follows:

Period of Noncompliance:	Penalty Per Day:
One (1) to thirty (30) days	\$500
Thirty-one (31) to sixty (60) days	\$1,000
Sixty-one (61) to one hundred-eighty (180) days	\$2,500
More than one hundred-eighty (180) days	\$5,000

(f). Failure to Complete the Additional Operational Plan for Chattanooga Creek CSO Outfalls. For each day Chattanooga fails to Timely complete the Additional Operational Plan for Chattanooga Creek CSO Outfalls in accordance with the final deadline set forth in Subparagraph 24.(a)., daily stipulated penalties may be assessed as follows:

Period of Noncompliance:	Penalty Per Day:
One (1) to thirty (30) days	\$500
Thirty-one (31) to sixty (60) days	\$1,000



Sixty-one (61) to one hundred-eighty (180) days \$2,500

More than one hundred-eighty (180) days \$5,000

(g). Failure to Complete Rehabilitation at the Moccasin Bend WWTP Pursuant to Feasible Alternative Analysis. For each day Chattanooga fails to Timely complete any identified rehabilitation projects at the Moccasin Bend WWTP pursuant to Feasible Alternative Analysis in accordance with the final deadline set forth in Subparagraph 24.(c)., daily stipulated penalties may be assessed as follows:

Period of Noncompliance:	Penalty Per Day:
One (1) to thirty (30) days	\$500
Thirty-one (31) to sixty (60) days	\$1,000
Sixty-one (61) to one hundred-eighty (180) days	\$2,500
More than one hundred-eighty (180) days	\$5,000

(h). Failure to Complete the SEP. After receiving the SEP Completion Report, in the event EPA notifies Chattanooga that Chattanooga has failed to satisfactorily complete the SEP in accordance with the terms of this Consent Decree as described in Section VIII and Appendix E (including the allowable expenditures for the SEP), a stipulated penalty of \$375,000 may be assessed if Chattanooga does not cure the deficiencies identified in EPA's notice within ninety (90) Days after receiving such notice. Notwithstanding the foregoing, if EPA determines that Chattanooga has made good faith efforts to satisfactorily complete the SEP and has certified, with supporting documentation, that at least ninety (90) percent of the required amount of money has been spent on the SEP, Chattanooga shall not be liable for any stipulated penalty.

(i). Failure to Timely Implement State Project Milestones. For each Day

Chattanooga fails to Timely implement a State Project milestone set forth in Appendix D, daily stipulated penalties may be assessed as follows:

Period of Noncompliance:	Penalty Per Violation Per Day:
One (1) to thirty (30) Days	\$500
Thirty-one (31) to sixty (60) Days	\$1,500
More than sixty (60) Days	\$2,250

49. Stipulated penalties under this Section shall begin to accrue on the day after performance is due or on the day a violation occurs, whichever is applicable, and shall continue to accrue until performance is satisfactorily completed or until the violation ceases. Stipulated penalties shall accrue simultaneously for separate violations of this Consent Decree.

50. Except for the stipulated penalty in Subparagraph 48.(i)., Chattanooga shall pay stipulated penalties within thirty (30) Days of a written demand by EPA. For the stipulated penalty in Subparagraph 48.(i)., Chattanooga shall pay stipulated penalties within thirty (30) Days of a written demand by TDEC. Except for the stipulated penalties in Subparagraphs 48.(a) and (i)., Chattanooga shall pay fifty (50) percent of the total stipulated penalty amount due to the United States and fifty (50) percent to the State. For the stipulated penalty in Subparagraph 48.(a), Chattanooga shall pay one hundred (100) percent of the total stipulated penalty amount due to the United States. For the stipulated penalty in Subparagraphs 48.(i)., Chattanooga shall pay one hundred (100) percent of the total stipulated penalty amount due to the State.

51. Except for the stipulated penalty in Subparagraph 48.(i)., the United States may in the unreviewable exercise of its discretion, reduce or waive stipulated penalties otherwise due

under this Consent Decree. TDEC may in the unreviewable exercise of its discretion, reduce or waive stipulated penalties otherwise due under Subparagraph 48.(i) of this Consent Decree.

52. Stipulated penalties shall continue to accrue as provided in Paragraph 49 during any Dispute Resolution, but need not be paid until the following:

(a). If the dispute is resolved by agreement or by a decision of EPA that is not appealed to the Court, Chattanooga shall pay accrued penalties determined to be owing, together with interest, to the United States and the State within thirty (30) Days of the effective date of the agreement or the receipt of EPA's decision or order.

(b). If the dispute is appealed to the Court and the United States prevails in whole or in part, Chattanooga shall pay all accrued penalties determined by the Court to be owed, together with interest, within sixty (60) Days of receiving the Court's decision or order, except as provided in Subparagraph 52.(c). below.

(c). If the District Court's decision is appealed, Chattanooga shall pay all accrued penalties determined to be owed, together with interest, within fifteen (15) Days of receiving the final appellate court decision.

53. Chattanooga shall pay stipulated penalties owing to the United States in the manner set forth and with the confirmation notices required by Paragraph 29, except that the transmittal letter shall state that the payment is for stipulated penalties and shall state for which violation(s) the penalties are being paid. Chattanooga shall pay stipulated penalties owing to the State by check payable to the "State of Tennessee." Each check shall reference the case name and civil action number herein and shall be sent to:

Phillip Hilliard  
Office of the Attorney General  
Environmental Division  
P.O. 20207  
Nashville, Tennessee 37202

54. If Chattanooga fails to pay stipulated penalties according to the terms of this Consent Decree, Chattanooga shall be liable for interest on such penalties, as provided for in 28 U.S.C. § 1961, accruing as of the date payment became due. Nothing in this Paragraph shall be construed to limit the United States or the State from seeking any remedy otherwise provided by law for Chattanooga's failure to pay any stipulated penalties.

55. Subject to the provisions of Section XIV of this Consent Decree (Effect of Settlement/Reservation of Rights), the stipulated penalties provided for in this Consent Decree shall be in addition to any other rights, remedies, or sanctions available to the United States and the State for Chattanooga's violation of this Consent Decree or applicable law. Where a violation of this Consent Decree is also a violation of the CWA and/or the TWQCA, Chattanooga shall be allowed a credit, for any stipulated penalties paid, against any statutory penalties imposed for such violation.

#### **XI. FORCE MAJEURE**

56. "Force majeure," for purposes of this Consent Decree, is defined as any event arising from causes beyond the control of Chattanooga, of any entity controlled by Chattanooga, or of Chattanooga's consultants and contractors, that delays or prevents the performance of any obligation under this Consent Decree despite Chattanooga's best efforts to fulfill the obligation. The requirement that Chattanooga exercise "best efforts to fulfill the obligation" includes using best efforts to anticipate any potential force majeure event and best efforts to address the effects

of any such event (a) as it is occurring and (b) after it has occurred to prevent or minimize any resulting delay to the greatest extent possible. "Force Majeure" does not include Chattanooga's financial inability to perform any obligation under this Consent Decree.

57. If any event occurs or has occurred that may delay the performance of any obligation under this Consent Decree, whether or not caused by a force majeure event, Chattanooga shall provide written notice to EPA and TDEC, within twenty-one (21) days from the date that Chattanooga first knew that the event might cause a delay. Such written notice shall include the following: an explanation and description of the reasons for the delay; the anticipated duration of the delay; all actions taken or to be taken to prevent or minimize the delay; a schedule for implementation of any measures to be taken to prevent or mitigate the delay or the effect of the delay; Chattanooga's rationale for attributing such delay to a force majeure event if it intends to assert such a claim; and a statement as to whether, in the opinion of Chattanooga, such event may cause or contribute to an endangerment to public health, welfare, or the environment. Chattanooga shall include with any notice all available documentation supporting the claim that the delay was attributable to a force majeure event. Failure to comply with the above requirements shall preclude Chattanooga from asserting any claim of force majeure for that event for the period of time of such failure to comply, and for any additional delay caused by such failure. Chattanooga shall be deemed to know of any circumstance of which Chattanooga, any entity controlled by Chattanooga, or Chattanooga's contractors knew or should have known.

58. If EPA, after a reasonable opportunity for review and comment by TDEC, agrees that the delay or anticipated delay is attributable to a force majeure event, the time for

performance of the obligations under this Consent Decree that are affected by the force majeure event will be extended by EPA, after a reasonable opportunity for review and comment by TDEC, for such time as is necessary to complete those obligations. An extension of the time for performance of the obligations affected by the force majeure event shall not, of itself, extend the time for performance of any other obligation. EPA will notify Chattanooga in writing of the length of the extension, if any, for performance of the obligations affected by the force majeure event.

59. If EPA, after a reasonable opportunity for review and comment by TDEC, does not agree that the delay or anticipated delay has been or will be caused by a force majeure event, EPA will notify Chattanooga in writing of its decision.

60. If Chattanooga elects to invoke the dispute resolution procedures set forth in Section XII (Dispute Resolution), it shall do so no later than fifteen (15) Days after receipt of EPA's notice. In any such proceeding, Chattanooga shall have the burden of demonstrating by a preponderance of the evidence that the delay or anticipated delay has been or will be caused by a force majeure event, that the duration of the delay or the extension sought was or will be warranted under the circumstances, that best efforts were exercised to avoid and mitigate the effects of the delay, and that Chattanooga complied with the requirements of Paragraphs 56 and 58 above. If Chattanooga carries this burden, the delay at issue shall be deemed not to be a violation by Chattanooga of the affected obligation of this Consent Decree identified to EPA and the Court.

## **XII. DISPUTE RESOLUTION**

61. Unless otherwise expressly provided for in this Consent Decree, the dispute resolution procedures of this Section shall be the exclusive mechanism to resolve disputes arising under or with respect to this Consent Decree. Chattanooga's failure to seek resolution of a dispute under this Section shall preclude Chattanooga from raising any such issue as a defense to an action by the United States or the State to enforce any obligation of Chattanooga arising under this Consent Decree.

62. Informal Dispute Resolution. Any dispute subject to Dispute Resolution under this Consent Decree shall first be the subject of informal negotiations. The dispute shall be considered to have arisen when Chattanooga sends the United States a written Notice of Dispute. Such Notice of Dispute shall state clearly the matter in dispute. The period of informal negotiations shall not exceed thirty (30) Days from the date the dispute arises, unless that period is modified by written agreement between the United States and Chattanooga. The United States shall consult with the State and the TCWN during the period of informal negotiations. If the United States and Chattanooga cannot resolve a dispute by informal negotiations, then the position advanced by the United States shall be considered binding unless, within forty-five (45) Days after the conclusion of the informal negotiation period, Chattanooga invokes formal dispute resolution procedures as set forth below.

63. Formal Dispute Resolution. Chattanooga shall invoke formal dispute resolution procedures, within the time period provided in the preceding Paragraph, by serving on the United States and the State a written Statement of Position regarding the matter in dispute. The Statement of Position shall include, but need not be limited to, any factual data, analysis, or opinion supporting Chattanooga's position and any supporting documentation relied upon by

Chattanooga. The United States shall serve its Statement of Position within sixty (60) Days of receipt of Chattanooga's Statement of Position. The United States' Statement of Position shall include, but need not be limited to, any factual data, analysis, or opinion supporting that position and any supporting documentation relied upon by the United States. The United States shall consult with the State and the TCWN during preparation of its Statement of Position. The United States' Statement of Position shall be binding on Chattanooga, unless Chattanooga files a motion for judicial review of the dispute in accordance with the following Paragraph.

64. Judicial Dispute Resolution. Chattanooga may seek judicial review of the dispute by filing with the Court and serving on the United States and the State, in accordance with Section XVI of this Consent Decree (Notices), a motion requesting judicial resolution of the dispute. The motion must be filed within thirty (30) Days of receipt of the United States' Statement of Position pursuant to the preceding Paragraph. The motion shall contain a written statement of Chattanooga's position on the matter in dispute, including any supporting factual data, analysis, opinion, or documentation, and shall set forth the relief requested and any schedule within which the dispute must be resolved for orderly implementation of the Consent Decree. The United States shall respond to Chattanooga's motion within the time period allowed by the Local Rules of this Court ("Local Rules"). The United States shall consult with the State and the TCWN during preparation of its response. Chattanooga may file a reply memorandum, to the extent permitted by the Local Rules.

65. Except as otherwise provided in this Consent Decree, in any dispute brought before this Court that was invoked under Paragraph 64, Chattanooga shall bear the burden of



proof, and each Party reserves the right to argue what the appropriate standard of proof and standard of review should be under applicable principles of law.

66. The invocation of dispute resolution procedures under this Section shall not, by itself, extend, postpone, or affect in any way any obligation of Chattanooga under this Consent Decree, unless and until final resolution of the dispute so provides. Stipulated penalties with respect to the disputed matter shall continue to accrue from the first (1<sup>st</sup>) day of noncompliance, but payment shall be stayed pending resolution of the dispute as provided in Paragraph 52. If Chattanooga does not prevail on the disputed issue, stipulated penalties shall be assessed and paid as provided in Section X (Stipulated Penalties).

### **XIII. RIGHT OF ENTRY AND INFORMATION COLLECTION AND RETENTION**

67. The United States, the State, and their representatives, including attorneys, contractors, and consultants, shall have the right of entry into any facility covered by this Consent Decree, at all reasonable times, upon presentation of credentials, to:

- (a). Monitor the progress of activities required under this Consent Decree;
  - (b). Verify any data or information submitted to the United States or the State in accordance with the terms of this Consent Decree;
  - (c). Obtain samples and, upon request, splits of any samples taken by Chattanooga or its representatives, contractors, or consultants;
  - (d). Obtain documentary evidence, including photographs and similar data;
- and
- (e). Assess Chattanooga's compliance with this Consent Decree.

68. Upon request, Chattanooga shall provide EPA and TDEC or their authorized representatives splits of any samples taken by Chattanooga. Upon request, EPA and TDEC shall provide Chattanooga splits of any samples taken by EPA or TDEC.

69. Until three (3) years after the termination of this Consent Decree, Chattanooga shall retain, and shall instruct its contractors and agents to preserve, all non-identical copies of all documents, records, or other information (including documents, records, or other information in electronic form) in its or its contractors' or agents' possession or control, or that come into its or its contractors' or agents' possession or control, and that relate in any manner to Chattanooga's performance of its obligations under this Consent Decree. This information-retention requirement shall apply regardless of any contrary corporate or institutional policies or procedures. At any time during this information-retention period, upon request by the United States or the State, Chattanooga shall provide copies of any documents, records, or other information required to be maintained under this Paragraph.

70. After the conclusion of the information-retention period provided in the preceding Paragraph, Chattanooga shall notify the United States and the State at least ninety (90) Days prior to the destruction of any documents, records, or other information subject to the requirements of the preceding Paragraph and, upon request by the United States or the State, Chattanooga shall deliver any such documents, records, or other information to EPA or TDEC. Chattanooga may assert that certain documents, records, or other information is privileged under the attorney-client privilege or any other privilege recognized by federal law. If Chattanooga asserts such a privilege, it shall provide the following:

- (a). The title of the document, record, or information;

- (b). The date of the document, record, or information;
- (c). The name and title of each author of the document, record, or information;
- (d). The name and title of each addressee and recipient;
- (e). A description of the subject of the document, record, or information; and
- (f). The privilege asserted by Chattanooga.

However, no documents, records, or other information created or generated pursuant to the requirements of this Consent Decree shall be withheld on grounds of privilege.

71. Chattanooga may also assert that information required to be provided under this Section is protected as Confidential Business Information (“CBI”) under 40 C.F.R. Part 2. As to any information that Chattanooga seeks to protect as CBI, Chattanooga shall follow the procedures set forth in 40 C.F.R. Part 2.

72. This Consent Decree in no way limits or affects any right of entry and inspection, or any right to obtain information, held by the United States or the State pursuant to applicable federal or state laws, regulations, or permits, nor does it limit or affect any duty or obligation of Chattanooga to maintain documents, records, or other information imposed by applicable federal or state laws, regulations, or permits.

#### **XIV. EFFECT OF SETTLEMENT/RESERVATION OF RIGHTS**

73. This Consent Decree resolves the civil claims of the United States and the State for the violations alleged in the Complaint filed in this action through the Date of Lodging of this Consent Decree.

74. This Consent Decree also resolves the civil claims of the TCWN for the violations alleged, or that could have been alleged, in the TCWN Complaint filed in this action through the

Date of Lodging of this Consent Decree. In addition, this Consent Decree resolves all civil claims of the TCWN for the penalties associated with any activity subject to a stipulated penalty under this Consent Decree.

75. The United States and the State reserve all legal and equitable remedies available to enforce the provisions of this Consent Decree, except as expressly stated in Paragraph 73. This Consent Decree shall not be construed to limit the rights of the United States or the State to obtain penalties or injunctive relief under the CWA, the TWQCA, or their implementing regulations, or under other federal or state laws, regulations, or permit conditions, except as expressly specified in Paragraph 73. The United States and the State further reserve all legal and equitable remedies to address any imminent and substantial endangerment to the public health or welfare or the environment arising at, or posed by, Chattanooga's Sewer System, whether related to the violations addressed in this Consent Decree or otherwise.

76. The TCWN reserves all legal and equitable remedies available to enforce the provisions of this Consent Decree, except as expressly stated in Paragraph 74. This Consent Decree shall not be construed to limit the rights of the TCWN to obtain penalties or injunctive relief under the CWA or its implementing regulations, or under other federal laws, regulations, or permit conditions, except as expressly specified in Paragraph 74.

77. In any subsequent administrative or judicial proceeding initiated by the United States or the State for injunctive relief, civil penalties, other appropriate relief relating to the Sewer System or Chattanooga's violations, Chattanooga shall not assert, and may not maintain, any defense or claim based upon the principles of waiver, res judicata, collateral estoppel, issue preclusion, claim preclusion, claim-splitting, or other defenses based upon any contention that

the claims raised by the United States or the State in the subsequent proceeding were or should have been brought in the instant case, except with respect to claims that have been specifically resolved pursuant to Paragraph 73 of this Section.

78. This Consent Decree is not a permit, or a modification of any permit, under any federal, State, or local laws or regulations. Chattanooga is responsible for achieving and maintaining complete compliance with all applicable federal, State, and local laws, regulations, and permits; and Chattanooga's compliance with this Consent Decree shall be no defense to any action commenced pursuant to any such laws, regulations, or permits, except as set forth herein. The United States and the State do not, by their consent to the entry of this Consent Decree, warrant or aver in any manner that Chattanooga's compliance with any aspect of this Consent Decree will result in compliance with provisions of the CWA, the TWQCA, or with any other provisions of federal, State, or local laws, regulations, or permits.

79. This Consent Decree does not limit or affect the rights of any of the Parties against any third parties, not party to this Consent Decree, nor does it limit the rights of third parties, not party to this Consent Decree, against Chattanooga, except as otherwise provided by law.

80. This Consent Decree shall not be construed to create rights in, or grant any cause of action to, any third party not party to this Consent Decree.

## **XV. COSTS**

81. The Parties shall bear their own costs of this action, including attorneys' fees, except as follows:

(a). The United States and the State shall be entitled to collect the costs (including attorneys' fees) incurred in any action necessary to collect any portion of the civil penalty or any stipulated penalties due but not paid by Chattanooga.

(b). Chattanooga agrees to pay TCWN's reasonably related attorney fees and expenses as detailed in the itemization provided to Chattanooga's attorneys by written correspondence dated March 19, 2012 (in the sum of \$36,804.11). TCWN and its attorneys will make no further claim for fees or expenses incurred in this action after the Date of Entry.

## **XVI. NOTICES**

82. Unless otherwise specified herein, whenever notifications, submissions, or communications are required by this Consent Decree, they shall be made in writing and addressed as follows:

To the United States:

Chief, Environmental Enforcement Section  
Environment and Natural Resources Division  
Environmental Enforcement Section  
U.S. Department of Justice  
Box 7611 Ben Franklin Station  
Washington, D.C. 20044-7611

and

Chief, Clean Water Enforcement Branch  
Water Protection Division  
U.S Environmental Protection Agency, Region 4  
61 Forsyth Street, S.W.  
Atlanta, GA 30303  
(404) 562-9776

To EPA:

Chief, Clean Water Enforcement Branch

Water Protection Division  
U.S Environmental Protection Agency, Region 4  
61 Forsyth Street, S.W.  
Atlanta, GA 30303  
(404) 562-9776

To the State:

Phillip Hilliard  
Senior Counsel  
Office of the Attorney General  
Environmental Division  
P.O. Box 20207  
Nashville, Tennessee 37202

and

Enforcement Coordinator, Water Pollution Control  
Tennessee Department of Environment and Conservation  
6<sup>th</sup> Floor, L&C Annex  
401 Church Street  
Nashville, Tennessee 37243-1534  
(615) 532-0625

To TDEC:

Enforcement Coordinator, Water Pollution Control  
Tennessee Department of Environment and Conservation  
6<sup>th</sup> Floor, L&C Annex  
401 Church Street  
Nashville, Tennessee 37243-1534  
(615) 532-0625

To Chattanooga:

Director, Public Works  
City of Chattanooga, Tennessee  
1250 Market St # 2100  
Chattanooga, TN 37402  
(423) 643-6000

Chattanooga City Attorney  
City of Chattanooga, Tennessee

100 E. 11th Street, Suite 200  
Chattanooga, TN 37402  
(423) 643-8250

and

Adam G. Sowatzka  
Baker Donelson  
Monarch Plaza, Suite 1600  
3414 Peachtree Road, N.E.  
Atlanta, Georgia 30326  
(404) 443-6715

To TCWN:

Stephanie Durman Matheny  
Tennessee Clean Water Network  
P.O. Box 1521  
Knoxville, Tennessee 37901

83. Any Party may, by written notice to the other Parties, change its designated notice recipient or notice address provided above.

84. Notices submitted pursuant to this Section shall be deemed submitted upon mailing, unless otherwise provided in this Consent Decree or by mutual agreement of the Parties in writing.

#### **XVII. EFFECTIVE DATE**

85. The Effective Date of this Consent Decree shall be the date upon which this Consent Decree is entered by the Court or a motion to enter the Consent Decree is granted, whichever occurs first, as recorded on the Court's docket.

#### **XVIII. RETENTION OF JURISDICTION**

86. The Court shall retain jurisdiction over this case until termination of this Consent Decree for the purpose of resolving disputes arising under this Consent Decree or entering orders



modifying this Consent Decree, pursuant to Sections XII (Force Majeure) and XIV (Effect of Settlement/Reservation of Rights), or effectuating or enforcing compliance with the terms of this Consent Decree.

### **XIX. MODIFICATION**

87. The terms of this Consent Decree, including any attached appendices, may be modified only by a subsequent written agreement signed by all the Parties. Where the modification constitutes a material change to this Consent Decree, it shall be effective only upon approval by the Court. Non-material changes to this Consent Decree (including appendices) may be made by written agreement of the Parties without court approval, and the Parties may by mutual agreement determine whether a modification is non-material.

88. Any disputes between the Parties concerning modification of this Consent Decree shall be resolved pursuant to Section XII (Dispute Resolution), provided, however, that, instead of the burden of proof provided by Paragraph 65, the Party seeking the modification bears the burden of demonstrating that it is entitled to the requested modification in accordance with Federal Rule of Civil Procedure 60(b).

### **XX. TERMINATION**

89. This Consent Decree may be terminated when the United States determines that Chattanooga has satisfactorily completed performance of its compliance (Section VI) and SEP (Section VIII) obligations required by this Consent Decree, provided that Chattanooga has fulfilled all other obligations of this Consent Decree, including payment of the civil penalty under Section VII of this Consent Decree and any accrued stipulated penalties as required by Section X of this Consent Decree not waived or reduced by the United States. Chattanooga may

serve upon the United States a Request for Termination, certifying that Chattanooga has satisfied those requirements, together with all necessary supporting documentation.

90. Following receipt by the United States of Chattanooga's Request for Termination, the United States and Chattanooga shall confer informally concerning the Request and any disagreement that they may have as to whether Chattanooga has satisfactorily complied with the requirements for termination of this Consent Decree. If the United States, after consultation with the State and TCWN, agrees that this Consent Decree may be terminated, the United States and Chattanooga shall submit, for the Court's approval, a joint stipulation terminating the Consent Decree.

91. If the United States, after consultation with the State and TCWN, does not agree that this Consent Decree may be terminated, Chattanooga may invoke Dispute Resolution under Section XII of this Consent Decree. However, Chattanooga shall not seek Dispute Resolution of any dispute regarding termination, under Paragraph 63 of Section XII, until ninety (90) Days after service of its Request for Termination.

## **XXI. PUBLIC PARTICIPATION**

92. This Consent Decree shall be lodged with the Court for a period of not less than thirty (30) Days for public notice and comment in accordance with 28 C.F.R. § 50.7. The United States reserves the right to withdraw or withhold its consent if the comments regarding the Consent Decree disclose facts or considerations indicating that the Consent Decree is inappropriate, improper, or inadequate. Chattanooga, the State, and TCWN all consent to entry of this Consent Decree without further notice, and agree not to withdraw from, or oppose entry of, this Consent Decree by the Court or to challenge any provision of the Consent Decree, unless the

United States has notified the Parties in writing that it no longer supports entry of the Consent Decree.

## **XXII. SIGNATORIES/SERVICE**

93. Each undersigned representative of Chattanooga, EPA, the Assistant Attorney General for the Environment and Natural Resources Division of the Department of Justice, TDEC, the State, and TCWN certifies that he or she is fully authorized to enter into the terms and conditions of this Consent Decree and to execute and legally bind the Party he or she represents to this document.

94. This Consent Decree may be signed in counterparts, and its validity shall not be challenged on that basis. Chattanooga's agent on the signature page agrees to accept service of process by mail with respect to all matters arising under or relating to this Consent Decree and to waive the formal service requirements set forth in Rules 4 and 5 of the Federal Rules of Civil Procedure and any applicable Local Rules of this Court including, but not limited to, service of a summons.

## **XXIII. INTEGRATION**

95. This Consent Decree constitutes the final, complete, and exclusive agreement and understanding among the Parties with respect to the settlement embodied in this Consent Decree and supersedes all prior agreements and understandings, whether oral or written, concerning the settlement embodied herein. Other than Deliverables that are subsequently submitted and approved pursuant to this Consent Decree, no other document, nor any representation, inducement, agreement, understanding, or promise, constitutes any part of this Consent Decree or the settlement it represents, nor shall it be used in construing the terms of this Consent Decree.

#### **XXIV. FINAL JUDGMENT**

96. Upon approval and entry of this Consent Decree by the Court, this Consent Decree shall constitute a final judgment of the Court as to the United States, the State, TCWN, and Chattanooga. The Court finds that there is no just reason for delay and therefore enters this judgment as a final judgment under Rules 54 and 58 of the Federal Rules of Civil Procedure.

#### **XXV. APPENDICES**

98. The following appendices are attached to and part of this Consent Decree:

“Appendix A” is the map of Chattanooga’s Sewersheds.

“Appendix B” is the CDROM disk containing EPA Region IV’s MOM guidance.

“Appendix C” is the list and description of the Early Action Capital Improvement Projects.

“Appendix D” is the description of the State Project.

“Appendix E” is the description of the Supplemental Environmental Project.

Dated and entered this 24th day of April, 2013.

**SO ORDERED.**

**ENTER:**

/s/  

---

**CURTIS L. COLLIER**  
**UNITED STATES DISTRICT JUDGE**

# **Appendix C**

## **Early Action Capital Improvement Projects**

Appendix C  
Early Action Capital Improvement Projects

No.	Projects	Description	Estimated Completion Date
SSO and Wet Weather Volume Reduction Projects			
1	DuPont Pump Station and Basin Improvements	The main features of the project are to perform a flow monitoring study to determine a basis of design, upgrade the pump station to increase capacity, install a storage tank to equalize wet weather flows, and upgrade 700 linear feet of interceptor gravity sewer pipe.	60 mos. after the Effective Date of the Consent Decree
2	Collegedale Pump Station Improvements	The main features of the project include upgrading the pump station to increase capacity and potentially installing a storage tank to equalize wet weather flows. Additionally, as part of the design to increase the capacity of the pump station, a portion of the flow will be rerouted by installing 10,000 linear feet of force main pipe.	60 mos. after the Effective Date of the Consent Decree
3	East Brainerd Pump Station Improvements	The project includes a flow and evaluation study of the sewer basin and collection system and the related hydraulics upstream and downstream of the pump station. Specifically, the SSES study will include cleaning, CCTV, smoke testing and evaluating and prioritizing 255,455 linear feet of pipe and 629 manholes for rehabilitation. The collection system rehabilitation will include rehabilitation of approximately 50% of the SSES study pipes and manholes using trenchless techniques. The upgrade of the pump station and force main will include replacing the existing station to increase capacity and installing a larger, parallel force main of approximately 600 linear feet.	60 mos. after the Effective Date of the Consent Decree
4	Altamont Pump Station Improvements	This project includes the upgrade of the existing pump station with electrical controls and instrumentation, valves and piping, a new back-up power generator, lighting, and other related equipment. Additionally, approximately 17,000 feet of gravity sewer and service pipelines will be rehabilitated.	36 mos. after the Effective Date of the Consent Decree
5	Pineville Pump Station Improvements	This project involves the replacement of the existing can-type Pineville Road pump station and upgrading it to a submersible type pump station. This project includes a new wet well, piping, valves, electrical controls and instrumentation, back-up generator, and a new 1,600 linear foot 8" force main. Additionally, rehabilitation of a portion of the basin's collection system will include, but not be limited to manhole rehabilitation, line segment replacements, and the CIPP lining of line segments and laterals to the property line.	36 mos. after the Effective Date of the Consent Decree
6	Citico Creek Interceptor Rehabilitation	The main features of the project include repair of 6,300 linear feet of 42" gravity sewer interceptor pipe using trenchless rehabilitation techniques and including manhole rehabilitation.	36 mos. after the Effective Date of the Consent Decree

Appendix C  
Early Action Capital Improvement Projects

No.	Projects	Description	Estimated Completion Date
7	Highland Park Sewer Rehabilitation	The main features of the project include repair of 40,000 linear feet of 8", 10" and 12" gravity sewer pipelines using trenchless rehabilitation techniques including manhole rehabilitation.	60 mos. after the Effective Date of the Consent Decree
8	Citico CSOTF Pump Station Study	The study will evaluate alternatives to convey treated combined sewage through Citico CSOTF during conditions when river is above the discharge elevations.	36 mos. after the Effective Date of the Consent Decree
9	Tremont Area Sewer Separation Study	The study will evaluate the feasibility of separating the combined sewer and the sanitary sewer system in the Tremont area.	36 mos. after the Effective Date of the Consent Decree
10	Enterprise South Industrial Park Pump Station Force Main and Interceptor	The main features of the project include the replacement and upgrade of four existing pumps to four new 1.0 mgd pumps. Additionally, a new 4,800 linear foot 16" force main pipe will be installed as well as replacing 15" sewer with 8,500 linear feet of 36" gravity sewer pipe.	36 mos. after the Effective Date of the Consent Decree
11	Orchard Knobb Sanitary Pump Station	The project involves the replacement of the existing pumps, piping, valves, electrical controls and instrumentation and back-up generator.	60 mos. after the Effective Date of the Consent Decree
12	Friars Branch Pump Station Upgrade and Basin Improvements	The project includes a flow and SSES study of the sewer basin and collection system and the related hydraulics upstream and downstream of the pump station. The SSES study will evaluate and prioritize a portion of the collection system for rehabilitation. The collection system rehabilitation will include rehabilitation of approximately 50% of the SSES study pipes and manholes using trenchless techniques. The upgrade of the pump station and force main will include replacing and modernizing the existing station to increase capacity.	60 mos. after the Effective Date of the Consent Decree
13	Chattanooga Creek Interceptor Rehabilitation	This project involves the repair of approximately 9,000 linear feet of 24" and 36" interceptor gravity sewer pipelines using trenchless rehabilitation techniques including manhole rehabilitation.	36 mos. after the Effective Date of the Consent Decree
14	Tannery Flats Interceptor Rehabilitation	This project involves the repair of approximately 6,300 linear feet of 36" interceptor gravity sewer pipelines using trenchless rehabilitation techniques including manhole rehabilitation.	36 mos. after the Effective Date of the Consent Decree
15	East Bank/West Bank Flow Monitoring	This project involves the study, design, and implementation of a more accurate way to determine the discharge volume from the East Bank and West Bank overflow locations.	36 mos. after the Effective Date of the Consent Decree



Appendix C  
Early Action Capital Improvement Projects

No.	Projects	Description	Estimated Completion Date
<b>MBWWTP Projects</b>			
1	Hydraulic and Pump Improvements at MBWWTP	The main features of the project include replacing and upgrading the 4 existing pumps, and upgrading the electrical components, VFDs, and instrumentation of the pump station.	60 mos. after the Effective Date of the Consent Decree
2	Improved Screening Facilities at MBWWTP	The main features of this project include installing and upgrading the concrete channel, installing new bar screens, upgrading the MCC panel, upgrading and replacing the screw conveyors, belt conveyor and slide gates, and updating the electrical and instrumentation system.	60 mos. after the Effective Date of the Consent Decree
3	Secondary Clarifier Valve Motor Operator replacement at MBWWTP	The main features of this project include installing 14 new 16" valve motor operators and new floor stands and upgrading and improving the electrical and instrumentation components of this equipment.	60 mos. after the Effective Date of the Consent Decree
4	Improved Disinfection Facilities to Eliminate E. Coli Issues	The project involves a feasibility and lifecycle study to determine alternatives for chlorination of treated wastewater that will be discharged to the Tennessee river. One alternative under consideration is bulk sodium hypochlorite storage and injection, that would include bulk storage tanks, day tank, shed for tank farm, containment area, chemical safety stations, chemical fill Station (one supplying three tanks), valves, pipe trace, and feed system.	36 mos. after the Effective Date of the Consent Decree
<b>CSO Projects</b>			
1	Carter Street CSOTF Outfall Sewer Replacement	This project involves the rehabilitation of approximately 1,800 linear feet of 30" diameter concrete pipe and associated manholes, using trenchless technology where possible. Portions of the existing sewer are inaccessible where it is located under an industrial landfill.	36 mos. after the Effective Date of the Consent Decree
2	Automation of Valve Operators at CSO Facilities to Reduce Dry Weather Overflows	This project involves the installation of automated sluice gates and control systems at the 19th and Carter Street CSOTF to improve the operation of the facilities (to prevent dry-weather overflows).	36 mos. after the Effective Date of the Consent Decree
<b>Operations Projects</b>			
1	South Chickamauga Pump Station Reliability Improvements	The project involves the replacement of large diameter valves, HVAC system upgrade, influent gate upgrade, and force main modifications.	36 mos. after the Effective Date of the Consent Decree
2	SCADA and Communications Overhaul	The current SCADA communications equipment is outdated. This project involves a study to evaluate alternatives for equipment systems and their feasibility and sustainability for reacting to and controlling equipment to convey wastewater to the MBWWTP.	60 mos. after the Effective Date of the Consent Decree